

GateIn Reference Guide



by the GateIn community , JBoss by Red Hat , and eXo Platform

edited by Scott Mumford (Red Hat), Thomas Heute (Red Hat), Luc Texier (Red Hat), and Christophe Laprun (Red Hat)

1. Introduction	1
1.1. Related Links	1
2. Configuration	3
2.1. Database Configuration	3
2.1.1. Overview	3
2.1.2. Configuring the database for JCR	3
2.1.3. Configuring the database for the default identity store	4
2.2. Email Service Configuration	5
2.2.1. Overview	5
2.2.2. Configuring the outgoing e-mail account	5
3. Portal Development	7
3.1. Skinning the portal	7
3.1.1. Overview	7
3.1.2. Skin Components	7
3.1.3. Skin Selection	8
3.1.4. Skins in Page Markups	8
3.1.5. The Skin Service	9
3.1.6. The Default Skin	11
3.1.7. Creating New Skins	12
3.1.8. Tips and Tricks	20
3.2. Portal Lifecycle	22
3.2.1. Overview	22
3.2.2. Application Server start and stop	22
3.2.3. The Command Servlet	23
3.3. Default Portal Configuration	25
3.3.1. Overview	25
3.3.2. Configuration	25
3.3.3. Tips	26
3.4. Portal Default Permission Configuration	28
3.4.1. Overview	28
3.4.2. Overwrite Portal Default Permissions	29
3.5. Portal Navigation Configuration	30
3.5.1. Overview	30
3.5.2. Portal Navigation	34
3.5.3. Group Navigation	39
3.5.4. User Navigation	39
3.6. Internationalization Configuration	39
3.6.1. Overview	39
3.6.2. Locales configuration	40
3.6.3. ResourceBundleService	42
3.6.4. Navigation Resource Bundles	43
3.6.5. Portlets	44
3.6.6. Translating the language selection form	45
3.7. RTL (Right To Left) Framework	46

3.7.1. Groovy templates	46
3.7.2. Stylesheet	47
3.7.3. Images	48
3.7.4. Client side JavaScript	49
3.8. XML Resources Bundles	49
3.8.1. Motivation	49
3.8.2. XML format	50
3.8.3. Portal support	51
3.9. JavaScript Inter Application Communication	51
3.9.1. Overview	51
3.9.2. Library	51
3.9.3. Syntax	52
3.9.4. Example of Javascript events usage	53
3.10. Upload Component	55
3.10.1. Upload Service	55
3.11. Deactivation of the Ajax Loading Mask Layer	57
3.11.1. Purpose	57
3.11.2. Synchronous issue	57
3.12. JavaScript Configuration	58
4. Portlet development	61
4.1. Portlet Primer	61
4.1.1. JSR-168 and JSR-286 overview	61
4.1.2. Tutorials	63
4.2. Global portlet.xml file	75
4.2.1. Global portlet.xml usecase	75
4.2.2. Global metadata	75
5. Gadget development	77
5.1. Gadgets	77
5.1.1. Existing Gadgets	79
5.1.2. Create a new Gadget	79
5.1.3. Remote Gadget	79
5.1.4. Gadget Importing	80
5.1.5. Gadget Web Editing	80
5.1.6. Gadget IDE Editing	80
5.1.7. Dashboard Viewing	81
5.2. Set up a Gadget Server	82
5.2.1. Virtual servers for gadget rendering	82
5.2.2. Configuration	82
6. Authentication and Identity	85
6.1. Predefined User Configuration	85
6.1.1. Overview	85
6.1.2. Plugin for adding users, groups and membership types	85
6.1.3. Membership types	85
6.1.4. Groups	86

6.1.5. Users	87
6.1.6. Plugin for monitoring user creation	88
6.2. Authentication Token Configuration	89
6.2.1. What is Token Service?	89
6.2.2. Implementing the Token Service API	89
6.2.3. Configuring token services	90
6.3. PicketLink IDM integration	91
6.3.1. Configuration files	91
6.4. Organization API	98
6.5. Accessing User Profile	99
6.6. Single-Sign-On (SSO)	100
6.6.1. Overview	100
6.6.2. Central Authentication Service (CAS)	100
6.6.3. JOSSO	108
6.6.4. OpenSSO - The Open Web SSO project	113
6.6.5. SPNEGO	119
7. Web Services for Remote Portlets (WSRP)	129
7.1. Introduction	129
7.2. Level of support in GatIn 3.1	129
7.3. Deploying GatIn's WSRP services	130
7.3.1. If you consider the WSRP use when running GatIn on a non-default port or hostname	131
7.3.2. Considerations to use WSRP with SSL	131
7.4. Making a portlet remotable	131
7.5. Consuming GatIn's WSRP portlets from a remote Consumer	133
7.6. Consuming remote WSRP portlets in GatIn	133
7.6.1. Overview	133
7.6.2. Configuring a remote producer walk-through	134
7.6.3. Configuring access to remote producers via XML	139
7.6.4. Examples	141
7.7. Consumers maintenance	143
7.7.1. Modifying a currently held registration	143
7.7.2. Consumer operations	146
7.7.3. Importing and exporting portlets	147
7.7.4. Erasing local registration data	148
7.8. Configuring GatIn's WSRP Producer	149
7.8.1. Overview	149
7.8.2. Default configuration	149
7.8.3. Registration configuration	150
7.8.4. WSRP validation mode	152
8. Advanced Development	153
8.1. Foundations	153
8.1.1. GatIn Kernel	153
8.1.2. Configuring services	154

8.1.3. Configuration syntax	154
8.1.4. InitParams configuration object	158
8.1.5. Configuring a portal container	161
8.1.6. Gateln Extension Mechanism, and Portal Extensions	164
8.1.7. Running Multiple Portals	165

Introduction

GateIn 3.1 is the merge of two mature Java projects; JBoss Portal and eXo Portal. This new community project takes the best of both offerings and incorporates them into a single portal framework. GateIn aims at providing an intuitive user-friendly portal, and a framework to address the needs of Web 2.0 applications today.



This book provides thorough information about installation and configuration of the services provided by GateIn.

1.1. Related Links

- GateIn homepage: www.gatein.org [http://www.gatein.org]
- GateIn videos: vimeo.com/channels/gatein [http://vimeo.com/channels/gatein]
- GateIn documentation: www.jboss.org/gatein/documentation.html [http://www.jboss.org/gatein/documentation.html]
- GateIn downloads: www.jboss.org/gatein/downloads.html [http://www.jboss.org/gatein/downloads.html]

Configuration

2.1. Database Configuration

2.1.1. Overview

GateIn 3.1 has two different database dependencies. One is the identity service configuration, which depends on Hibernate. The other is the Java content repository (JCR) service, which depends on JDBC API, and can integrate with any existing datasource implementation.

When you change the database configuration for the first time, GateIn will automatically generate the proper schema (assuming that the database user has the appropriate permissions).

GateIn 3.1 assumes the default encoding for your database is `latin1`. You may need to change this parameter for your database so that GateIn 3.1 works properly.

2.1.2. Configuring the database for JCR

To configure the database used by JCR, edit the file:

```
$JBOSS_HOME/server/default/conf/gatein/configuration.properties
```

.

For Tomcat, the file is located at

```
$TOMCAT_HOME/gatein/conf/configuration.properties
```

.

And edit the values of driver, url, username and password with the values for your JDBC connection. To learn more, refer to your database JDBC driver documentation.

```
gatein.jcr.datasource.driver=org.hsqldb.jdbcDriver
gatein.jcr.datasource.url=jdbc:hsqldb:file:${gatein.db.data.dir}/data/jdbcjcr_${name}
gatein.jcr.datasource.username=sa
gatein.jcr.datasource.password=
```

By default, the name of the database is "jdbcjcr_\${name}" - \${name} should be a part of the database name, as it is dynamically replaced by the name of the portal container extension. For example, gatein-sample-portal.ear defines "sample-portal" as the container name and the default portal defines "portal" as the container name).

In case of HSQL, the databases are created automatically. For any other databases, you need to create a database named `jdbcjcr_portal` (and `"jdbcjcr_sample-portal"` if you have `gatein-sample-portal.ear` in `$JBOSS_HOME/server/default/deploy`). Note that some databases do not accept '-' in the database name, so you may have to remove `$JBOSS_HOME/server/default/deploy/gatein-sample-portal.ear`.

Make sure the user has rights to create tables on `jdbcjcr_portal`, and to update them as they will be automatically created during the first startup.

Also, add your database's JDBC driver into the classpath - you can put it in `$JBOSS_HOME/server/default/lib` (or `$TOMCAT_HOME/lib`, if you are running on Tomcat).

MySQL example:

Configure the JCR to store data in MySQL and assume that you created a user named `"gateinuser"` with a password `"gateinpassword"`. Next, create a database `"mygateindb_portal"` (remember that `portal` is required), and assign the rights to create tables to the users.

Add the MySQL's JDBC driver to the classpath, and finally edit `gatein.ear/02portal.war/WEB-INF/conf/jcr/jcr-configuration` to contain the following:

```
gatein.jcr.datasource.driver=com.mysql.jdbc.Driver
gatein.jcr.datasource.url=jdbc:mysql://localhost:3306/mygateindb${container.name.suffix}
gatein.jcr.datasource.username=gateinuser
gatein.jcr.datasource.password=gateinpassword
```

2.1.3. Configuring the database for the default identity store

By default, users are stored in a database. To change the database where users are stored, you need to edit the file:

```
$JBOSS_HOME/server/default/conf/gatein/configuration.properties
```

For Tomcat, the file is located at

```
$TOMCAT_HOME/gatein/conf/configuration.properties
```

You will find the same type of configuration as in `jcr-configuration.xml`:

```
gatein.idm.datasource.driver=org.hsqldb.jdbcDriver
gatein.idm.datasource.url=jdbc:hsqldb:file:${gatein.db.data.dir}/data/jdbcidm_${name}
gatein.idm.datasource.username=sa
```

```
gatein.idm.datasource.password
```

2.2. Email Service Configuration

2.2.1. Overview

GateIn 3.1 includes an e-mail sending service that needs to be configured before it can function properly. This service, for instance, is used to send emails to users who forgot their password or username.

2.2.2. Configuring the outgoing e-mail account

The e-mail service can use any SMTP account configured in `$JBOSS_HOME/server/default/conf/gatein/configuration.properties` (or `$TOMCAT_HOME/gatein/conf/configuration.properties` if you are using Tomcat).

The relevant section looks like:

```
# EMail
gatein.email.smtp.username=
gatein.email.smtp.password=
gatein.email.smtp.host=smtp.gmail.com
gatein.email.smtp.port=465
gatein.email.smtp.starttls.enable=true
gatein.email.smtp.auth=true
gatein.email.smtp.socketFactory.port=465
gatein.email.smtp.socketFactory.class=javax.net.ssl.SSLSocketFactory
```

It is preconfigured for GMail, so that any GMail account can easily be used (simply use the full GMail address with username and password).

In corporate environments, if you want to use your corporate SMTP gateway over SSL, like in the default configuration, configure a certificate truststore containing your SMTP server's public certificate. Depending on the key sizes, you may then also need to install Java Cryptography Extension (JCE) Unlimited Strength Jurisdiction Policy Files for your Java Runtime Environment.

Portal Development

3.1. Skinning the portal

3.1.1. Overview

GateIn 3.1 provides robust skinning support for the entire portal User Interface (UI). This includes support for skinning all of the common portal elements and being able to provide custom skins and window decoration for individual portlets. It is designed to common graphic resource reuse and ease of development .

3.1.2. Skin Components

The complete skinning of a page can be decomposed into three main parts:

Portal Skin

The portal skin contains the CSS styles for the portal and its various UI components. This should include all the UI components, except for the window decorators and portlet specific styles.

Window Styles

The CSS styles are associated with the portlet window decorators. The window decorators contain the control buttons and borders surrounding each portlet. Individual portlets can have their own window decorator selected, or be rendered without one.

Portlet Skins

The portlet skins affects how portlets are rendered on the page via one of the following ways:

Portlet Specification CSS Classes

The portlet specification defines a set of CSS classes that should be available to portlets. GateIn 3.1 provides these classes as part of the portal skin. This allows each portal skin to define its own look and feel for these default values.

Portlet Skins

GateIn 3.1 provides a means for portlet CSS files to be loaded, basing on the current portal skin. This allows a portlet to provide different CSS styles to better match the look and feel of the current portal. Portlet skins provide a much more customizable CSS experience than just using the portlet specification CSS classes.



Note

The window decorators and the default portlet specification CSS classes should be considered as separate types of skinning components, but they need to be included as part of the overall portal skin. The portal skin must include these component's CSS classes or they will not be displayed correctly.

A portlet skin does not need to be included as part of the portal skin and can be included within the portlets web application.

3.1.3. Skin Selection

3.1.3.1. Skin Selection Through the User Interface

There are a few means for you to select the display skin. The easiest way to change the skin is to select it through the user interface. Administrators can change the default skin for the portal, and users logged in can select their desired display skins.

Please see the User Guide for information on how to change the skin using the user interface.

3.1.3.2. Setting the Default Skin within the Configuration Files

The default skin can also be configured through the portal configuration files if you do not want to use the admin user interface. This will allow the portal to have the new default skin ready when GateIn 3.1 is initially started.

The default skin of the portal is called `Default`. To change this value, add a `skin` tag in the `02portal.war/WEB-INF/conf/portal/portal/classic/portal.xml` configuration file.

To change the skin to `MySkin`, you would make the following changes:

```
<portal-config>
  <portal-name>classic</portal-name>
  <locale>en</locale>
  <access-permissions>Everyone</access-permissions>
  <edit-permission>*/platform/administrators</edit-permission>
  <skin>MySkin</skin>
  ...
```

3.1.4. Skins in Page Markups

The GateIn 3.1 skin contains CSS styles for the portal's components but also shares components that may be reused in portlets. When GateIn 3.1 generates a portal page markup, it inserts the stylesheet links in the page's `head` tag.

There are two main types of CSS links that will appear in the `head` tag: a link to the portal skin CSS file and a link to the portlet skin CSS files.

Portal Skin

The portal skin will appear as a single link to a CSS file. This link contains contents from all the portal skin classes merged into one file. This allows the portal skin to be transferred more

quickly as a single file instead of many multiple smaller files. All pages of the portal have the same skin defined in the CSS file.

Portlet Skin

Each portlet on a page may contribute its own style. The link to the portlet skin will only appear on the page if that portlet is loaded on the current page. A page may contain many portlet skin CSS links or none.

In the code fragment below, you can see two types of links:

```
<head>
...
<!-- The portal skin -->
<link id="CoreSkin" rel="stylesheet" type="text/css" href="/eXoResources/skin/Stylesheet.css" />

<!-- The portlet skins -->
<link id="web_FooterPortlet" rel="stylesheet" type="text/css" href= "/web/skin/portal/webui/
component/UIFooterPortlet/DefaultStylesheet.css" />
<link id="web_NavigationPortlet" rel="stylesheet" type="text/css" href= "/web/skin/portal/webui/
component/UINavigationPortlet/DefaultStylesheet.css" />
<link id="web_HomePagePortlet" rel="stylesheet" type="text/css" href= "/portal/templates/skin/
webui/component/UIHomePagePortlet/DefaultStylesheet.css" />
<link id="web_BannerPortlet" rel="stylesheet" type="text/css" href= "/web/skin/portal/webui/
component/UIBannerPortlet/DefaultStylesheet.css" />
...
</head>
```



Note

Both window styles and portlet specification CSS classes are included in the portal skin.

3.1.5. The Skin Service

The skin service of GateIn 3.1 manages various types of skins. This service is responsible for discovering and deploying the skins into the portal.

3.1.5.1. Skin configuration

GateIn 3.1 automatically discovers web archives that contain a file descriptor for skins (`WEB-INF/gatein-resources.xml`). This file is responsible for specifying the portal, portlet and window decorators to be deployed into the skin service.

The full schema can be found in the lib directory:

exo.portal.component.portal.jar/gatein_resources_1_0.xsd

Here is an example where a skin (MySkin) with its CSS location is defined, and a few window decorator skins are specified:

```
<gatein-resources>
  <portal-skin>
    <skin-name>MySkin</skin-name>
    <css-path>/skin/myskin.css</css-path>
    <overwrite>false</overwrite>
  </portal-skin>
</gatein-resources>

<!-- window style -->
<window-style>
  <style-name>MyThemeCategory</style-name>
  <style-theme>
    <theme-name>MyThemeBlue</theme-name>
  </style-theme>
  <style-theme>
    <theme-name>MyThemeRed</theme-name>
  </style-theme>
  ...

```

3.1.5.2. Resource Request Filter

Because of the Right-To-Left support, all CSS files need to be retrieved through a Servlet filter and the web application needs to be configured to activate this filter. This is already done for the 01eXoResources.war web application which contains the default skin.

Any new web applications containing skinning CSS files will need to have the following added to their web.xml :

```
<filter>
  <filter-name>ResourceRequestFilter</filter-name>
  <filter-class>org.exoplatform.portal.application.ResourceRequestFilter</filter-class>
</filter>

<filter-mapping>
  <filter-name>ResourceRequestFilter</filter-name>
  <url-pattern>*.css</url-pattern>
</filter-mapping>

```




Note

The `display-name` element also needs to be specified in the `web.xml` for the skinning service to work properly with the web application.

3.1.6. The Default Skin

The default skin for GateIn 3.1 is located as part of the `01eXoResource.war`. The main files associated with the skin are shown below:

WEB-INF/gatein-resources.xml

1

WEB-INF/web.xml

2

skin/Stylesheet.css

- 1 gatein-resources.xml: defines the skin setup to use.
- 2 web.xml: contains the resource filter and has the display-name set.
- 3 Stylesheet.css: contains the CSS class definitions for this skin.

gatein-resources.xml

For the default portal skin, this file contains definitions for the portal skin, the window decorations that this skin provides and defines some Javascript resources which are not related to the skin. The default portal skin does not directly define portlet skins which should be provided by the portlets themselves.

web.xml

For the default portal skin, the `web.xml` of `eXoResources.war` contains a lot of information which is mostly irrelevant to the portal skinning. The areas of interest in this file is the `resourcerequestfilter` and the fact that the `display-name` is set.

Stylesheet.css

This file contains the main stylesheet of the portal skin. The file is the main entry point to the CSS class definitions for the skin. The content of this file is shown below:

```
@import url(DefaultSkin/portal/webui/component/UIPortalApplicationSkin.css);
```

1

```
@import url(DefaultSkin/webui/component/Stylesheet.css);
```

2

```
@import url(PortletThemes/Stylesheet.css);
```

3

```
@import url(Portlet/Stylesheet.css);
```

- 1 Skin for the main portal page.
- 2 Skins for various portal components.
- 3 Window decoration skins.
- 4 The portlet specification CSS classes.

Instead of defining all the CSS classes in this file, you can import other CSS stylesheet files, some of which may also import other CSS stylesheets. The CSS classes are split up between multiple files to make it easier for new skins to reuse parts of the default skin.

To reuse the CSS stylesheet from the default portal skin, you need to refer to the default skin from eXoResources. For example, to include the window decorators from the default skin within a new portal skin, you need to use this import:

```
@import url(/eXoResources/skin/Portlet/Stylesheet.css);
```



Note

When the portal skin is added to the page, it merges all the CSS stylesheets into a single file.

3.1.7. Creating New Skins

3.1.7.1. Creating a New Portal Skin

A new portal needs to be added to the portal through the skin service. The web application which contains the skin will need to be properly configured for the skin service to discover them. This means that `ResourceRequestFilter` and `gatein-resources.xml` should be configured properly.

3.1.7.1.1. Portal Skin Configuration

The `gatein-resources.xml` needs to specify the new portal skin. This includes specifying the name of the new skin, where to locate its CSS stylesheet file and whether to overwrite an existing portal theme with the same name.

```
<gatein-resources>
  <portal-skin>
    <skin-name>MySkin</skin-name>
```

```

<css-path>/skin/myskin.css</css-path>
<overwrite>>false</overwrite>
</portal-skin>
</gatein-resources>

```

The default portal skin and window styles are defined in `01eXoResources.war/WEB-INF/gatein-resources.xml`.




Note

The CSS for the portal skin needs to contain the CSS for all the window decorators and the portlet specification CSS classes.

3.1.7.1.2. Portal Skin Preview Icon

When selecting a skin, it is possible to preview it. The current skin needs to know about the skin icons for all the available skins; otherwise, it will not be able to show the previews. When creating a new portal, it is recommended to include the preview icons of the other skins and to update the other skins with your new portal skin preview.



The portal skin preview icon is specified through the CSS of the portal skin. To display the preview for the current portal skin, you must specify a specific CSS class and set the icon as the background.

For the portal named **MySkin**, the CSS class must be defined as follows:

```
.UIChangeSkinForm .UIItemSelector .TemplateContainer .MySkinImage
```

In order for the default skin to know about the skin icon for a new portal skin, the preview screenshot needs to be placed in:

```
01eXoResources.war:/skin/DefaultSkin/portal/webui/component/customization/  
UIChangeSkinForm/background
```


The CSS stylesheet for the default portal needs to have the following updated with the preview icon CSS class. For a skin named **MySkin**, you need to update the following:

```
01eXoResources.war:/skin/DefaultSkin/portal/webui/component/customization/  
UIChangeSkinForm/Stylesheet.css
```

```
.UIChangeSkinForm .UIItemSelector .TemplateContainer .MySkinImage {  
    margin: auto;  
    width: 329px; height:204px;  
    background: url('background/MySkin.jpg') no-repeat top;  
    cursor: pointer ;  
}
```

3.1.7.2. Creating a New Window Style

Window styles are the CSS applied to the window decoration. When the administrator selects a new application to add to a page, he can decide which style of decoration would go around the window if any.



3.1.7.2.1. Window Style Configuration

Window Styles are defined within the `gatein-resources.xml` file which is used by the skin service to deploy the window style into the portal. Window styles can belong in with a window style category, this category and the window styles need to be specified in the resources file.

The following `gatein-resource.xml` fragment adds `MyThemeBlue` and `MyThemeRed` to the `MyTheme` category.

```
<window-style>
  <style-name>MyTheme</style-name>
  <style-theme>
    <theme-name>MyThemeBlue</theme-name>
  </style-theme>
  <style-theme>
    <theme-name>MyThemeRed</theme-name>
  </style-theme>
</window-style>
```

The windows style configuration for the default skin is configured in:

`01eXoResources.war/WEB-INF/gatein-resources.xml`



Note

When a window style is defined in the `gatein-resources.xml` file, it will be available to all portlets whether the current portal skin supports the window decorator or not. When a new window decorator is added, it is recommended that you add it to all portal skins or that portal skins share a common stylesheet for window decorators.

3.1.7.2.2. Window Style CSS

To display the window decorators for the skin service, it must have the CSS classes with specific naming related to the window style name. The service will try and display the CSS based on this naming. The CSS class must be included as part of the current portal skin for displaying the window decorators.

The location of the window decorator CSS classes for the default portal theme is located at:

`01eXoResources.war/skin/PortletThemes/Stylesheet.css`

Create the CSS file:

```
/*---- MyTheme ----*/
```

```
.MyTheme .WindowBarCenter .WindowPortletInfo {
    margin-right: 80px; /* orientation=lt */
    margin-left: 80px; /* orientation=rt */
}
.MyTheme .WindowBarCenter .Controllcon {
    float: right; /* orientation=lt */
    float: left; /* orientation=rt */
    width: 24px;
    height: 17px;
    cursor: pointer;
    background-image: url('background/MyTheme.png');
}
.MyTheme .ArrowDownIcon {
    background-position: center 20px;
}
.MyTheme .OverArrowDownIcon {
    background-position: center 116px;
}
.MyTheme .MinimizedIcon {
    background-position: center 44px;
}
.MyTheme .OverMinimizedIcon {
    background-position: center 140px;
}
.MyTheme .MaximizedIcon {
    background-position: center 68px;
}
.MyTheme .OverMaximizedIcon {
    background-position: center 164px;
}
.MyTheme .RestoreIcon {
    background-position: center 92px;
}
.MyTheme .OverRestoreIcon {
    background-position: center 188px;
}
.MyTheme .NormalIcon {
    background-position: center 92px;
}
.MyTheme .OverNormalIcon {
    background-position: center 188px;
}
.UIPageDesktop .MyTheme .ResizeArea {
    float: right; /* orientation=lt */
```

```
float: left; /* orientation=rt */
width: 18px; height: 18px;
cursor: nw-resize;
background: url('background/ResizeArea18x18.gif') no-repeat left top; /* orientation=lt */
background: url('background/ResizeArea18x18-rt.gif') no-repeat right top; /* orientation=rt */
}
.MyTheme .Information {
height: 18px; line-height: 18px;
vertical-align: middle; font-size: 10px;
padding-left: 5px; /* orientation=lt */
padding-right: 5px; /* orientation=rt */
margin-right: 18px; /* orientation=lt */
margin-left: 18px; /* orientation=rt */
}
.MyTheme .WindowBarCenter .WindowPortletIcon {
background-position: left top; /* orientation=lt */
background-position: right top; /* orientation=rt */
padding-left: 20px; /* orientation=lt */
padding-right: 20px; /* orientation=rt */
height: 16px;
line-height: 16px;
}
.MyTheme .WindowBarCenter .PortletName {
font-weight: bold;
color: #333333;
overflow: hidden;
white-space: nowrap;
width: 100%;
}
.MyTheme .WindowBarLeft {
padding-left: 12px;
background-image: url('background/MyTheme.png');
background-repeat: no-repeat;
background-position: left -148px;
}
.MyTheme .WindowBarRight {
padding-right: 11px;
background-image: url('background/MyTheme.png');
background-repeat: no-repeat;
background-position: right -119px;
}
.MyTheme .WindowBarCenter {
background-image: url('background/MyTheme.png');
background-repeat: repeat-x;
```

```
background-position: left -90px;
}
.MyTheme .WindowBarCenter .FixHeight {
  height: 21px;
  padding-top: 8px;
}
.MyTheme .MiddleDecoratorLeft {
  padding-left: 12px;
  background: url('background/MyTheme.png') repeat-y left;
}
.MyTheme .MiddleDecoratorRight {
  padding-right: 11px;
  background: url('background/MyTheme.png') repeat-y right;
}
.MyTheme .MiddleDecoratorCenter {
  background: #ffffff;
}
.MyTheme .BottomDecoratorLeft {
  MyTheme: 12px;
  background-image: url('background/MyTheme.png');
  background-repeat: no-repeat;
  background-position: left -60px;
}
.MyTheme .BottomDecoratorRight {
  padding-right: 11px;
  background-image: url('background/MyTheme.png');
  background-repeat: no-repeat;
  background-position: right -30px;
}
.MyTheme .BottomDecoratorCenter {
  background-image: url('background/MyTheme.png');
  background-repeat: repeat-x;
  background-position: left top;
}
.MyTheme .BottomDecoratorCenter .FixHeight {
  height: 30px;
}
```

3.1.7.2.3. How to Set the Default Window Style

To set the default window style to be used for a portal, you need to specify the CSS classes for a theme called `DefaultTheme`.

**Note**

You do not need to specify the `DefaultTheme` in `gatein-resources.xml`.

3.1.7.3. How to Create New Portlet skins

Portlets often require additional styles that may not be defined by the portal skin. GateIn 3.1 allows you to define additional stylesheets for each portlet and will append the corresponding `link` tags to the `head`.

The link ID will be of the form `{portletAppName}{PortletName}`. For example: `ContentPortlet` in `content.war` will give `id="contentContentPortlet"`.

To define a new CSS file to include whenever a portlet is available on a portal page, the following fragment needs to be added to `gatein-resources.xml`.

```
<portlet-skin>
  <application-name>portletAppName</application-name>
  <portlet-name>PortletName</portlet-name>
  <skin-name>Default</skin-name>
  <css-path>/skin/DefaultStylesheet.css</css-path>
</portlet-skin>

<portlet-skin>
  <application-name>portletAppName</application-name>
  <portlet-name>PortletName</portlet-name>
  <skin-name>OtherSkin</skin-name>
  <css-path>/skin/OtherSkinStylesheet.css</css-path>
</portlet-skin>
```

This will load the `DefaultStylesheet.css` or `OtherSkinStylesheet.css` when the `Default` skin or `OtherSkin` is used respectively.

**Note**

If the current portal skin is not defined as part of the supported skins, the portlet CSS class will not be loaded. It is recommended that you update portlet skins whenever a new portal skin is created.

3.1.7.3.1. Change portlet icons

Each portlet can be represented by a unique icon that you can see in the portlet registry or page editor. This icon can be changed by adding an image to the directory of the portlet webapplication:

- `skin/DefaultSkin/portletIcons/icon_name.png`.

To use the icon correctly, it must be named after the portlet.

For example, the icon for an account portlet named `AccountPortlet` would be located at:

- `skin/DefaultSkin/portletIcons/AccountPortlet.png`



Note

You must use `skin/DefaultSkin/portletIcons/` for the directory to store the portlet icon regardless of what skin is going to be used.

3.1.7.4. How to create a new Portlet Specification CSS Classes

The portlet specification defines a set of default CSS classes that should be available for portlets. These classes are included as part of the portal skin. Please see the portlet specification for a list of the default classes that should be available.

For the default portal skin, the portlet specification CSS classes are defined in:

`eXoResources.war/skin/Portlet/Stylesheet.css`

3.1.8. Tips and Tricks

3.1.8.1. Easier CSS debugging

By default, CSS files are cached and their imports are merged into a single CSS file at the server side. This reduces the number of HTTP requests from the browser to the server.

The optimization code is quite simple as all the CSS files are parsed at the server startup time and all the `@import` and `url(...)` references are rewritten to support a single flat file. The result is stored in a cache directly used from the `ResourceRequestFilter`.

Although the optimization is useful for production environments, it may be easier to deactivate this optimization while debugging stylesheets. To do so, set the java system property `exo.product.developing` to `true`.

For example, the property can be passed as a JVM parameter with the `-D` option when running `GateIn`.

```
sh $JBOSS_HOME/bin/run.sh -Dexo.product.developing=true
```

1. Warning: This option may cause display bugs with certain browsers, such as Internet Explorer.

3.1.8.2. Some CSS techniques

It is recommended that you have some experiences with CSS before studying GateIn 3.1 CSS.

GateIn 3.1 relies heavily on CSS to create the layout and effects for the UI. Some common techniques for customizing GateIn 3.1 CSS are explained below.

3.1.8.2.1. Decorator pattern

The decorator is a pattern to create a contour or a curve around an area. To achieve this effect, you need to create 9 cells. The BODY is the central area for you to decorate. The other 8 cells are distributed around the BODY cell. You can use the width, height and background image properties to achieve any desired decoration effects.

TopLeft	TopCenter	TopRight
CenterLeft	BODY	CenterRight
BottomLeft	BottomCenter	BottomRight

```


<div class="Parent">
  <div class="TopLeft">
    <div class="TopRight">
      <div class="TopCenter"><span></span></div>
    </div>
  </div>
  <div class="CenterLeft">
    <div class="CenterRight">
      <div class="CenterCenter">BODY</div>
    </div>
  </div>
  <div class="BottomLeft">
    <div class="BottomRight">
      <div class="BottomCenter"><span></span></div>
    </div>
  </div>
</div>

```

```
<div>  
</div>
```

3.1.8.2.2. Left margin left pattern

Left margin left pattern is a technique to create 2 blocks side by side. The left block has a fixed size and the right block will take the rest of the available space. When the user resizes the browser, the added or removed space will be taken from the right block.



```
<div class="Parent">  
  <div style="float: left; width: 100px">  
  </div>  
  <div style="margin-left: 105px;">  
  <div>  
  <div style="clear: left"><span></span></div>  
</div>
```

3.2. Portal Lifecycle

3.2.1. Overview

This chapter describes the portal lifecycle from the application server start to its stop and how requests are handled.

3.2.2. Application Server start and stop

A portal instance is simply a web application deployed as a WAR in an application server. Portlets are also part of an enhanced WAR called a portlet application.

GateIn 3.1 does not require any particular setup for your portlet in most common scenarios and the `web.xml` file can remain without any GateIn 3.1 specific configuration.

During deployment, GateIn 3.1 will automatically and transparently inject a servlet into the portlet application to be able to interact with it. This feature is dependent on the underlying servlet container but will work out of the box on the proposed bundles.

3.2.3. The Command Servlet

The servlet is the main entry point for incoming requests, it also includes some init codes when the portal is launched. This servlet (`org.gatein.wci.command.CommandServlet`) is automatically added during deployment and mapped to `/tomcatgateinservlet`.

This is equivalent to adding the following to `web.xml`.



Note

As the servlet is already configured, this example only aims at providing information.

```
<servlet>
  <servlet-name>TomcatGateInServlet</servlet-name>
  <servlet-class>org.gatein.wci.command.CommandServlet</servlet-class>
  <load-on-startup>0</load-on-startup>
</servlet>

<servlet-mapping>
  <servlet-name>TomcatGateInServlet</servlet-name>
  <url-pattern>/tomcatgateinservlet</url-pattern>
</servlet-mapping>
```

It is possible to filter on the `CommandServlet` by filtering the URL pattern used by the Servlet mapping.

The example below would create a servlet filter that calculates the time of execution of a portlet request.

The filter class:

```
package org.example;

import java.io.IOException;

import javax.servlet.FilterChain;
```

```
import javax.servlet.FilterConfig;
import javax.servlet.ServletException;
import javax.servlet.ServletRequest;
import javax.servlet.ServletResponse;

public class MyFilter implements javax.servlet.Filter {

    public void doFilter(ServletRequest request, ServletResponse response,
        FilterChain chain) throws IOException, ServletException
    {
        long beforeTime = System.currentTimeMillis();
        chain.doFilter(request, response);
        long afterTime = System.currentTimeMillis();
        System.out.println("Time to execute the portlet request (in ms): " + (afterTime - beforeTime));
    }

    public void init(FilterConfig config) throws ServletException
    {
    }

    public void destroy()
    {
    }

}
```

The Java EE web application configuration file (`web.xml`) of the portlet on which we want to know the time to serve a portlet request. As mentioned above, GateIn 3.1 does not require anything special to be included, only the URL pattern to set has to be known.

```
<?xml version="1.0"?>
<web-app xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
    xsi:schemaLocation="http://java.sun.com/xml/ns/j2ee http://java.sun.com/xml/ns/j2ee/web-
app_2_4.xsd"
    version="2.5">

    <filter>
        <filter-name>MyFilter</filter-name>
        <filter-class>org.example.MyFilter</filter-class>
    </filter>

    <filter-mapping>
```

```

<filter-name>MyFilter</filter-name>
<url-pattern>/tomcatgateinservlet</url-pattern>
<dispatcher>INCLUDE</dispatcher>
</filter-mapping>

</web-app>

```



INCLUDE dispatcher

It is important to set `INCLUDE` as a dispatcher as the portal always hits the `CommandServlet` through a request dispatcher. Without this, the filter will not be triggered, unless the direct access to a resource, such as an image.

3.3. Default Portal Configuration

3.3.1. Overview

GateIn 3.1 default homepage URL is `http://{hostname}:{port}/portal/`. There may be multiple independent portals deployed in parallel at any given time, each of which has its root context (i.e.: `http://{hostname}:{port}/sample-portal/`). Each portal is internally composed of one or more 'portals'. It is required to have at least one such portal - the default one is called 'classic'. When accessing the default homepage URL of GateIn 3.1, you are automatically redirected to the 'classic' portal. The default portal performs another important task. When starting up GateIn 3.1 for the first time, its JCR database will be empty (that's where portals keep their runtime-configurable settings). It is the default portal used to detect this, and to trigger automatic data initialization.

3.3.2. Configuration

The following example configuration can be found at: `"02portal.war:/WEB-INF/conf/portal/portal-configuration.xml"`.

```

<component>
  <key>org.exoplatform.portal.config.UserPortalConfigService</key>
  <type>org.exoplatform.portal.config.UserPortalConfigService</type>
  <component-plugins>
    <component-plugin>
      <name>new.portal.config.user.listener</name>
      <set-method>initListener</set-method>
      <type>org.exoplatform.portal.config.NewPortalConfigListener</type>
      <description>this listener init the portal configuration</description>
      <init-params>

```

```
<value-param>
  <name>default.portal</name>
  <description>The default portal for checking db is empty or not</description>
  <value>classic</value>
</value-param>
...
</init-params>
</component-plugin>
</component-plugins>
</component>
```

In this example, the **classic** portal has been set as the default.



Note

Components, component-plugins, and init-params are explained in the Foundations chapter. For now, just note how the `NewPortalConfigListener` component-plugin is used to add configuration to `UserPortalConfigService`, which is designed in this way to allow other components to add configuration to it.

3.3.3. Tips

3.3.3.1. Delete Portals Definition by Configuration

In some cases, some portal definitions are defined but not used any more. If you want to delete them, you can add some configurations to *portal.war/WEB-INF/conf/portal/portal-configuration.xml*.

To delete a portal definition or a portal template definition, you need to define a component plug-in as the example below:

```
<external-component-plugins>
  <target-component>org.exoplatform.portal.config.UserPortalConfigService</target-
component>
  <component-plugin>
    <name>new.portal.config.user.listener</name>
    <set-method>deleteListenerElements</set-method>
    <type>org.exoplatform.portal.config.NewPortalConfigListener</type>
    <description>this listener delete some predefined portal and templates configuration</
description>
    <init-params>
      <object-param>
```



```

<name>site.templates.location</name>
<description>description</description>
<object type="org.exoplatform.portal.config.SiteConfigTemplates">
  <field name="portalTemplates">
    <collection type="java.util.HashSet">
      <value>
        <string>basic</string>
      </value>
      <value>
        <string>classic</string>
      </value>
    </collection>
  </field>
</object>
</object-param>
<object-param>
  <name>portal.configuration</name>
  <description>description</description>
  <object type="org.exoplatform.portal.config.NewPortalConfig">
    <field name="predefinedOwner">
      <collection type="java.util.HashSet">
        <value><string>classic</string></value>
      </collection>
    </field>
    <field name="ownerType"><string>portal</string></field>
  </object>
</object-param>
</init-params>
</component-plugin>
</external-component-plugins>

```

3.3.3.2. Set the info bar shown by default for portlet

You can set the info bar shown by default for portlets of a portal by adding a property for the *portal-config* configuration in the *portal.xml* file.

```

<properties>
  <entry key="showPortletInfo">1</entry>
</properties>

```

There are two values for "showPortletInfo": 0 and 1. If the value is 1, the info bar of portlets is shown by default. If the value is 0, it is not.

3.4. Portal Default Permission Configuration

3.4.1. Overview

The default permission configuration for the portal is defined through `org.exoplatform.portal.config.UserACL` component configuration in the file `02portal.war:/WEB-INF/conf/portal/portal-configuration.xml`.

It defines 8 permissions types:

`super.user`

The super-user as *root* has all the rights on the eXo Platform.

`portal.administrator.groups`

Any member of those groups are considered administrators. The default value is `/platform/administrators`.

`portal.administrator.mstype`

Any user with that membership type would be considered administrator or the associated group with the `manager` by default.

`portal.creator.groups`

This list defines all groups that will be able to manage the different portals. Members of this group also have the permission to create new portals. The format is `membership:/group/subgroup`.

`navigation.creator.membership.type`

Defines the membership type of group managers. The group managers have the permission to create and edit group pages and they can modify the group navigation.

`guests.group`

Any anonymous user automatically becomes a member of this group when they enter the public pages.

`mandatory.groups`

Groups that cannot be deleted.

`mandatory.mstypes`

Membership types that cannot be deleted.

```
<component>
  <key>org.exoplatform.portal.config.UserACL</key>
  <type>org.exoplatform.portal.config.UserACL</type>
```

```

<init-params>
  <value-param>
    <name>super.user</name>
    <description>administrator</description>
    <value>root</value>
  </value-param>

  <value-param>
    <name>portal.creator.groups</name>
    <description>groups with membership type have permission to manage portal</description>
    <value>*:/platform/administrators,*:/organization/management/executive-board</value>
  </value-param>

  <value-param>
    <name>navigation.creator.membership.type</name>
    <description>specific membership type have full permission with group navigation</
description>
    <value>manager</value>
  </value-param>
  <value-param>
    <name>guests.group</name>
    <description>guests group</description>
    <value>/platform/guests</value>
  </value-param>
  <value-param>
    <name>access.control.workspace</name>
    <description>groups with memberships that have the right to access the User Control
Workspace</description>
    <value>*:/platform/administrators,*:/organization/management/executive-board</value>
  </value-param>
</init-params>
</component>

```

3.4.2. Overwrite Portal Default Permissions

When creating the custom portals and portal extensions, it is possible to override the default configuration by using `org.exoplatform.portal.config.PortalACLPlugin`, configuring it as an external-plugin of `org.exoplatform.portal.config.UserACL` service:

```

<external-component-plugins>
  <target-component>org.exoplatform.portal.config.UserACL</target-component>
  <component-plugin>
    <name>addPortalACLPlugin</name>

```

```
<set-method>addPortalACLPlugin</set-method>
<type>org.exoplatform.portal.config.PortalACLPlugin</type>
<description>setting some permission for portal</description>
<init-params>
  <values-param>
    <name>access.control.workspace.roles</name>
    <value>*:/platform/administrators</value>
    <value>*:/organization/management/executive-board</value>
  </values-param>
  <values-param>
    <name>portal.creation.roles</name>
    <value>*:/platform/administrators</value>
    <value>*:/organization/management/executive-board</value>
  </values-param>
</init-params>
</component-plugin>
</external-component-plugins>
```

3.5. Portal Navigation Configuration

3.5.1. Overview

There are three navigation types available to portal users:

- [Section 3.5.2, “Portal Navigation”](#)
- [Section 3.5.3, “Group Navigation”](#)
- [Section 3.5.4, “User Navigation”](#)

These navigations are configured using the standard XML syntax in the file; "02portal.war:/WEB-INF/conf/portal/portal-configuration.xml".

```
<component>
  <key>org.exoplatform.portal.config.UserPortalConfigService</key>
  <type>org.exoplatform.portal.config.UserPortalConfigService</type>
  <component-plugins>
    <component-plugin>
      <name>new.portal.config.user.listener</name>
      <set-method>initListener</set-method>
      <type>org.exoplatform.portal.config.NewPortalConfigListener
    </type>
    <description>this listener init the portal configuration
  </description>
  <init-params>
```

```

<value-param>
  <name>default.portal</name>
  <description>The default portal for checking db is empty or not</description>
  <value>classic</value>
</value-param>
<value-param>
  <name>page.templates.location</name>
  <description>the path to the location that contains Page templates</description>
  <value>war:/conf/portal/template/pages</value>
</value-param>
<value-param>
  <name>override</name>
  <description>The flag parameter to decide if portal metadata is overridden on restarting
server
</description>
  <value>>false</value>
</value-param>
<object-param>
  <name>site.templates.location</name>
  <description>description</description>
  <object type="org.exoplatform.portal.config.SiteConfigTemplates">
    <field name="location">
      <string>war:/conf/portal</string>
    </field>
    <field name="portalTemplates">
      <collection type="java.util.HashSet">
        <value><string>basic</string></value>
        <value><string>classic</string></value>
      </collection>
    </field>
    <field name="groupTemplates">
      <collection type="java.util.HashSet">
        <value><string>group</string></value>
      </collection>
    </field>
    <field name="userTemplates">
      <collection type="java.util.HashSet">
        <value><string>user</string></value>
      </collection>
    </field>
  </object>
</object-param>
<object-param>
  <name>portal.configuration</name>

```

```
<description>description</description>
<object type="org.exoplatform.portal.config.NewPortalConfig">
  <field name="predefinedOwner">
    <collection type="java.util.HashSet">
      <value><string>classic</string></value>
    </collection>
  </field>
  <field name="ownerType">
    <string>portal</string>
  </field>
  <field name="templateLocation">
    <string>war:/conf/portal/</string>
  </field>
  <field name="importMode">
    <string>conserve</string>
  </field>
</object>
</object-param>
<object-param>
  <name>group.configuration</name>
  <description>description</description>
  <object type="org.exoplatform.portal.config.NewPortalConfig">
    <field name="predefinedOwner">
      <collection type="java.util.HashSet">
        <value><string>/platform/administrators</string></value>
        <value><string>/platform/users</string></value>
        <value><string>/platform/guests</string></value>
        <value><string>/organization/management/executive-board</string></value>
      </collection>
    </field>
    <field name="ownerType">
      <string>group</string>
    </field>
    <field name="templateLocation">
      <string>war:/conf/portal/</string>
    </field>
    <field name="importMode">
      <string>conserve</string>
    </field>
  </object>
</object-param>
<object-param>
  <name>user.configuration</name>
  <description>description</description>
```

```

<object type="org.exoplatform.portal.config.NewPortalConfig">
  <field name="predefinedOwner">
    <collection type="java.util.HashSet">
      <value><string>root</string></value>
      <value><string>john</string></value>
      <value><string>mary</string></value>
      <value><string>demo</string></value>
      <value><string>user</string></value>
    </collection>
  </field>
  <field name="ownerType">
    <string>user</string>
  </field>
  <field name="templateLocation">
    <string>war:/conf/portal</string>
  </field>
  <field name="importMode">
    <string>conserve</string>
  </field>
</object>
</object-param>
</init-params>
</component-plugin>
</component-plugins>
</component>

```

This XML configuration defines where in the portal's war to look for configuration, and which portals, groups, and user specific views to include in `portal/group/user` navigation. Those files will be used to create an initial navigation when the portal is launched in the first time. That information will then be stored in the JCR content repository, and can then be modified and managed from the portal UI.

Each portal, groups and users navigation is indicated by a configuration paragraph, for example:

```

<object-param>
  <name>portal.configuration</name>
  <description>description</description>
  <object type="org.exoplatform.portal.config.NewPortalConfig">

    <field name="predefinedOwner">
      <collection type="java.util.HashSet">
        <value><string>classic</string></value>
      </collection>
    </field>

```

1

```
<field name="ownerType">
  <string>portal</string>
</field>

<field name="templateLocation">
  <string>war:/conf/portal/</string>
</field>

<field name="importMode">
  <string>conserve</string>
</field>
</object>
</object-param>
```

- 1 *predefinedOwner* define the navigation owner, portal will look for the configuration files in folder with this name, if there is no suitable folder, a default portal will be created with name is this value.
- 2 *ownerType* define the type of portal navigation. It may be a portal, group or user
- 3 *templateLocation* the classpath where contains all portal configuration files
- 4 *importMode* The mode for navigation import. There are 4 types of import mode:
 - *conserve*: Import data when it does not exist, otherwise do nothing.
 - *insert*: Import data when it does not exist, otherwise performs a strategy that adds new data only.
 - *merge*: Import data when it does not exist, update data when it exists.
 - *rewrite*: Overwrite data whatsoever.

Base on these parameters, portal will look for the configuration files and create a relevant portal navigation, pages and data import strategy. The portal configuration files will be stored in folders with path look like `{templateLocation}/{ownerType}/{predefinedOwner}`, all navigations are defined in the `navigation.xml` file, pages are defined in `pages.xml` and portal configuration is defined in `{ownerType}.xml`. For example, with the above configuration, portal will look for all configuration files from `war:/conf/portal/portal/classic` path.

3.5.2. Portal Navigation

The portal navigation incorporates the pages that can be accessed even when the user is not logged in assuming the applicable permissions allow the public access). For example, several portal navigations are used when a company owns multiple trademarks, and sets up a website for each of them.

The **classic** portal is configured by four XML files in the `02portal.war:/WEB-INF/conf/portal/portal/classic` directory:

portal.xml

This file describes the layout and portlets that will be shown on all pages. The layout usually contains the banner, footer, menu and breadcrumbs portlets. GateIn 3.1 is extremely configurable as every view element (even the banner and footer) is a portlet.

```
<portal-config
  xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
  xsi:schemaLocation="http://www.gatein.org/xml/ns/gatein_objects_1_0 http://
www.gatein.org/xml/ns/gatein_objects_1_0"
  xmlns="http://www.gatein.org/xml/ns/gatein_objects_1_0">
  <portal-name>classic</portal-name>
  <locale>en</locale>
  <access-permissions>Everyone</access-permissions>
  <edit-permission>*:/platform/administrators</edit-permission>
  <properties>
    <entry key="sessionAlive">onDemand</entry>
    <entry key="showPortletInfo">1</entry>
  </properties>

  <portal-layout>
    <portlet-application>
      <portlet>
        <application-ref>web</application-ref>
        <portlet-ref>BannerPortlet</portlet-ref>
        <preferences>
          <preference>
            <name>template</name>
            <value>par:/groovy/groovy/webui/component/UIBannerPortlet.gtmpl</value>
            <read-only>false</read-only>
          </preference>
        </preferences>
      </portlet>
      <access-permissions>Everyone</access-permissions>
      <show-info-bar>false</show-info-bar>
    </portlet-application>

    <portlet-application>
      <portlet>
        <application-ref>web</application-ref>
        <portlet-ref>NavigationPortlet</portlet-ref>
      </portlet>
    </portlet-application>
  </portal-layout>
</portal-config>
```

```
<access-permissions>Everyone</access-permissions>
<show-info-bar>false</show-info-bar>
</portlet-application>

<portlet-application>
  <portlet>
    <application-ref>web</application-ref>
    <portlet-ref>BreadcrumbsPortlet</portlet-ref>
  </portlet>
  <access-permissions>Everyone</access-permissions>
  <show-info-bar>false</show-info-bar>
</portlet-application>

<page-body> </page-body>

<portlet-application>
  <portlet>
    <application-ref>web</application-ref>
    <portlet-ref>FooterPortlet</portlet-ref>
    <preferences>
      <preference>
        <name>template</name>
        <value>par:/groovy/groovy/webui/component/UIFooterPortlet.gtmpl</value>
        <read-only>false</read-only>
      </preference>
    </preferences>
  </portlet>
  <access-permissions>Everyone</access-permissions>
  <show-info-bar>false</show-info-bar>
</portlet-application>

</portal-layout>

</portal-config>
```

It is also possible to apply a nested container that can also contain portlets. Row, column or tab containers are then responsible for the layout of their child portlets.

Each application references a portlet using the id `portal#{portalName}:{portletWarName}/{portletName}/{uniqueId}`

Use the `page-body` tag to define where GateIn 3.1 should render the current page.

The defined **classic** portal is accessible to "Everyone" (at `/portal/public/classic`) but only members of the group `/platform/administrators` can edit it.

navigation.xml

This file defines all the navigation nodes of the portal. The syntax is simple using the nested node tags. Each node refers to a page defined in the `pages.xml` file (explained next).

If the administrator want to create node labels for each language, they will have to use `xml:lang` attribute in the label tag with value of `xml:lang` is the relevant locale.

Otherwise, if they want the node label is localized by resource bundle files, the `#{ . . . }` syntax will be used, the enclosed property name serves as a key that is automatically passed to the internationalization mechanism. Thus the literal property name is replaced by a localized value taken from the associated properties file matching the current locale.

For example:

```
<node-navigation
  xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
  xsi:schemaLocation="http://www.gatein.org/xml/ns/gatein_objects_1_2 http://
www.gatein.org/xml/ns/gatein_objects_1_2"
  xmlns="http://www.gatein.org/xml/ns/gatein_objects_1_2">
  <priority>1</priority>
  <page-nodes>
    <node>
      <name>home</name>
      <label xml:lang="en">Home</label>
      <page-reference>portal::classic::homepage</page-reference>
    </node>
    <node>
      <name>sitemap</name>
      <label xml:lang="en">SiteMap</label>
      <visibility>DISPLAYED</visibility>
      <page-reference>portal::classic::sitemap</page-reference>
    </node>
    .....
  </page-nodes>
</node-navigation>
```

This navigation tree can have multiple views inside portlets (such as the breadcrumbs portlet) that render the current view node, the site map or the menu portlets.

pages.xml

This configuration file structure is very similar to `portal.xml` and it can also contain container tags. Each application can decide whether to render the portlet border, the window state, the icons or portlet's mode.

```
<page-set
  xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
  xsi:schemaLocation="http://www.gatein.org/xml/ns/gatein_objects_1_0 http://
www.gatein.org/xml/ns/gatein_objects_1_0"
  xmlns="http://www.gatein.org/xml/ns/gatein_objects_1_0">

  <page>
    <name>homepage</name>
    <title>Home Page</title>
    <access-permissions>Everyone</access-permissions>
    <edit-permission>*:/platform/administrators</edit-permission>
    <portlet-application>
      <portlet>
        <application-ref>web</application-ref>
        <portlet-ref>HomePagePortlet</portlet-ref>
        <preferences>
          <preference>
            <name>template</name>
            <value>system:/templates/groovy/webui/component/UIHomePagePortlet.gtmpl</
value>
            <read-only>false</read-only>
          </preference>
        </preferences>
      </portlet>
      <title>Home Page portlet</title>
      <access-permissions>Everyone</access-permissions>
      <show-info-bar>false</show-info-bar>
      <show-application-state>false</show-application-state>
      <show-application-mode>false</show-application-mode>
    </portlet-application>
  </page>

  <page>
    <name>sitemap</name>
    <title>Site Map</title>
    <access-permissions>Everyone</access-permissions>
    <edit-permission>*:/platform/administrators</edit-permission>
    <portlet-application>
      <portlet>
        <application-ref>web</application-ref>
        <portlet-ref>SiteMapPortlet</portlet-ref>
      </portlet>
      <title>SiteMap</title>
```

```

    <access-permissions>Everyone</access-permissions>
    <show-info-bar>false</show-info-bar>
  </portlet-application>
</page>
.....
</page-set>

```

3.5.3. Group Navigation

Group navigations are dynamically added to the user navigation at login. This allows users to see the menu of all pages assigned to any groups they belong to.

The group navigation menu is configured by three XML files (`navigation.xml`, `pages.xml` and `portlet-preferences.xml`). The syntax used in these files is the same as those covered in [Section 3.5.2, “Portal Navigation”](#).

They are also located in the `{templateLocation}/{ownerType}/{predefinedOwner}` directory with `ownerType` is `group` and `predefinedOwner` is the path to the group. For example, `portal.war/WEB-INF/conf/portal/group/platform/administrators/`.

3.5.4. User Navigation

User navigation is the set of nodes and pages that are owned by the user. They are part of the user's dashboard.

Three files configure the user navigation (`navigation.xml`, `pages.xml` and `portlet-preferences.xml`). They are located in the `{templateLocation}/{ownerType}/{predefinedOwner}` directory with `ownerType` is `user` and `predefinedOwner` is username that want to create the navigation. For example, if administrator want to create navigation for user `root`, he has to locate the configuration files in `portal.war/WEB-INF/conf/portal/user/root`

3.6. Internationalization Configuration

3.6.1. Overview



Assumed Knowledge

GateIn 3.1 is fully configurable for internationalization; however, users should have a general knowledge of Internationalization in Java products before attempting these configurations.

Sun Java hosts a comprehensive guide to internationalize Java products at <http://java.sun.com/docs/books/tutorial/i18n/TOC.html>.

All GateIn 3.1 applications contain property files for various languages. They are packaged with the portlets applications in a `WEB-INF/classes/locale/` directory.

These files are located in the `classes` folder of the `WEB-INF` directory to be loaded by the `ClassLoader`.

All resource files are in a subfolder named `locale`.

For example, the translations for the *NavigationPortlet* are located in `web.war/WEB-INF/classes/locale/portlet/portal`.

```
NavigationPortlet_de.properties
NavigationPortlet_en.properties
NavigationPortlet_es.properties
NavigationPortlet_fr.properties
NavigationPortlet_nl.properties
NavigationPortlet_ru.properties
NavigationPortlet_uk.properties
NavigationPortlet_ar.xml
```

Those files contain typical `key=value` Java EE properties. For example, the French one:

```
javax.portlet.title=Portlet Navigation
```

There are also properties files in the portal itself. They form the **portal resource bundle**.

From a portlet, you can then access translations from the portlet itself or shared at the portal level, both are aggregated when you need them.



Translation in XML format

It is also possible to use a proprietary XML format to define translations. This is a more convenient way to translate a document for some languages, such as Japanese, Arabic or Russian. Property files have to be ASCII encoded, while the XML file can define its encoding. As a result, it is easier for you to read or edit a translation in XML instead of having to decode and encode the property file.

For more information, refer to [Section 3.8, "XML Resources Bundles"](#).

3.6.2. Locales configuration

Various languages are available in the portal package. The configuration below will define which languages shown in the "Change Language" section and made available to users.

The `02portal.war:/WEB-INF/conf/common/common-configuration.xml` file of your installation contains the following section:

```
<component>
  <key>org.exoplatform.services.resources.LocaleConfigService</key>
  <type>org.exoplatform.services.resources.impl.LocaleConfigServiceImpl</type>
  <init-params>
    <value-param>
      <name>locale.config.file</name>
      <value>war:/conf/common/locales-config.xml</value>
    </value-param>
  </init-params>
</component>
```

This configuration points to the locale configuration file.

The locale configuration file (`02portal.war:/WEB-INF/conf/common/locales-config.xml`) contains the following code:

```
<?xml version="1.0" encoding="UTF-8"?>
<locales-config>
  <locale-config>
    <locale>en</locale>
    <output-encoding>UTF-8</output-encoding>
    <input-encoding>UTF-8</input-encoding>
    <description>Default configuration for english locale</description>
  </locale-config>

  <locale-config>
    <locale>fr</locale>
    <output-encoding>UTF-8</output-encoding>
    <input-encoding>UTF-8</input-encoding>
    <description>Default configuration for the french locale</description>
  </locale-config>

  <locale-config>
    <locale>ar</locale>
    <output-encoding>UTF-8</output-encoding>
    <input-encoding>UTF-8</input-encoding>
    <description>Default configuration for the arabic locale</description>
```

```
<orientation>rt</orientation>
</locale-config>
</locales-config>
```

5

- 1 *locale* The locale has to be defined, such as <http://ftp.ics.uci.edu/pub/ietf-http-related-iso639.txt>. In this example, "ar" is Arabic.
- 2 *output-encoding* deals with the character encoding. It is recommended that **UTF-8** be used.
- 3 *input-encoding* In the Java implementation, the encoding parameters will be used for the request response stream. The input-encoding parameter will be used for requesting `setCharacterEncoding(..)`.
- 4 *description* Description for the language
- 5 *orientation* The default orientation of text and images is Left-To-Right. GateIn 3.1 supports **Right-To-Left** orientation. Modifying the text orientation is explained in [Section 3.7, "RTL \(Right To Left\) Framework"](#).

3.6.3. ResourceBundleService

The resource bundle service is configured in: `02portal.war:/WEB-INF/conf/common/common-configuration.xml`:

```
<component>
  <key>org.exoplatform.services.resources.ResourceBundleService</key>
  <type>org.exoplatform.services.resources.impl.SimpleResourceBundleService</type>
  <init-params>
    <values-param>
      <name>classpath.resources</name>
      <description>The resources that start with the following package name should be load from
file system</description>
      <value>locale.portlet</value>
    </values-param>
    <values-param>
      <name>init.resources</name>
      <description>Initiate the following resources during the first launch</description>
      <value>locale.portal.expression</value>
      <value>locale.portal.services</value>
      <value>locale.portal.webui</value>
      <value>locale.portal.custom</value>
      <value>locale.navigation.portal.classic</value>
      <value>locale.navigation.group.platform.administrators</value>
      <value>locale.navigation.group.platform.users</value>
```

1

2


```

<value>locale.navigation.group.platform.guests</value>
<value>locale.navigation.group.organization.management.executive-board</value>
</values-param>
<values-param>

<name>portal.resource.names</name>
<description>The properties files of the portal, those files will be merged
into one ResourceBundle properties </description>
<value>locale.portal.expression</value>
<value>locale.portal.services</value>
<value>locale.portal.webui</value>
<value>locale.portal.custom</value>
</values-param>
</init-params>
</component>

```

- 1 *classpath.resources* are discussed in the later section.
- 2 *init.resources* initiates resources related to portal, group, user resource bundle.
- 3 *portal.resource.names* defines all resources that belong to the *Portal Resource Bundle*.

These resources are merged into a single resource bundle which is accessible from anywhere in GateIn 3.1. All these keys are located in the same bundle, which is separated from the navigation resource bundles.

3.6.4. Navigation Resource Bundles

There is a resource bundle for each navigation. A navigation can exist for user, groups, and portal.

The previous example shows bundle definitions for the navigation of the classic portal and of four different groups. Each of these resource bundles occupies a different sphere, they are independent of each other and they are not included in the *portal.resource.names* parameter.

The properties for a group must be in the `WEB-INF/classes/locale/navigation/group/` folder. `/WEB-INF/classes/locale/navigation/group/organization/management/executive-board_en.properties`, for example.

The folder and file names must correspond to the group hierarchy. The group name "*executive-board*" is followed by the iso 639 code.

For each language defined in *LcalesConfig* must have a resource file defined. If the name of a group is changed the name of the folder and/or files of the correspondent navigation resource bundles must also be changed.

Content of `executive-board_en.properties`:

```
organization.title=Organization
organization.newstaff=New Staff
organization.management=Management
```

This resource bundle is only accessible for the navigation of the *organization.management.executive-board* group.

3.6.5. Portlets

Portlets are independent applications and deliver their own resource files.

All shipped portlet resources are located in the **locale/portlet** subfolder. The `ResourceBundleService` parameter **classpath.resources** defines this subfolder.

Procedure 3.1. Example

To add a Spanish translation to the *GadgetPortlet*.

1. Create the file `GadgetPortlet_es.properties` in: `WEB-INF/classes/locale/portlet/gadget/GadgetPortlet`.
2. In `portlet.xml`, add *Spanish* as a **supported-locale** ('es' is the 2 letters code for Spanish), the **resource-bundle** is already declared and is the same for all languages:

```
<supported-locale>en</supported-locale>
<supported-locale>es</supported-locale>
<resource-bundle>locale.portlet.gadget.GadgetPortlet</resource-bundle>
```

See the portlet specification for more details about the portlet internationalization.

3.6.5.1. Standard portlet resource keys

The portlet specifications define three standard keys: Title, Short Title and Keywords. Keywords are formatted as a comma-separated list of tags.

```
javax.portlet.title=Breadcrumbs Portlet
javax.portlet.short-title=Breadcrumbs
javax.portlet.keywords=Breadcrumbs, Breadcrumb
```

3.6.5.2. Debugging resource bundle usage


When translating an application, it can sometimes be difficult to find the right key for a given property.

Execute the portal in the **debug mode** and select the special language from the available languages,; **Magic locale**.

This feature translates a key to the same key value.

For example, the translated value for the key `"organization.title"` is simply the value `"organization.title"`. Selecting that language allows use of the portal and its applications with all the keys visible. This makes it easier to find out the correct key for a given label in the portal page.

3.6.6. Translating the language selection form



When choosing a language as on the screenshot above, the user is presented with a list of languages on the left side in the current chosen language and on the right side, the same language translated into its own language. Those texts are obtained from the JDK API `java.util.Locale.getDisplayedLanguage()` and `java.util.Locale.getDisplayedCountry()` (if needed) and all languages may not be translated and can also depend on the JVM currently used. It is still possible to override those values by editing the `locale.portal.webui` resource bundle, to do so edit the file `gatein.ear/02portal.war/WEB-INF/classes/locale/portal/webui_xx_yy.properties` where `xx_yy` represents the country code of the language in which you want to translate a particular language. In that file, add or modify a key such as `Locale.xx_yy` with the value being the translated string.

Example 3.1. Changing the displayed text for Traditional Chinese in French

First edit `gatein.ear/02portal.war/WEB-INF/classes/locale/portal/webui_fr.properties` where `fr` is the country code for French, and add the following key into it:

```
Locale.zh_TW=Chinois traditionnel
```

After a restart the language will be updated in the user interface when a user is trying to change the current language.

3.7. RTL (Right To Left) Framework

The text orientation depends on the current locale setting. The orientation is a Java 5 enum that provides a set of functionalities:

```
LT, // Western Europe
RT, // Middle East (Arabic, Hebrew)
TL, // Japanese, Chinese, Korean
TR; // Mongolian
public boolean isLT() { ... }
public boolean isRT() { ... }
public boolean isTL() { ... }
public boolean isTR() { ... }
```

The object defining the Orientation for the current request is the `UIPortalApplication`. However, it should be accessed at runtime using the `RequestContext` that delegates to the `UIPortalApplication`.

In case of `PortalRequestContext`, it directly delegates as the `PortalRequestContext` has a reference to the current `UIPortalApplication`.

In case of a different context, such as the `PortletRequestContext`, it delegates to the parent context given the fact that the root `RequestContext` is always a `PortalRequestContext`.

3.7.1. Groovy templates

Orientation is defined by implicit variables in the Groovy binding context:

Orientation

The current orientation as an Orientation

isLT

The value of orientation.isLT()

isRT

The value of orientation.isRT()

dir

The string 'ltr' if the orientation is LT or the string 'rtl' if the orientation is RT.

3.7.2. Stylesheet

The skin service handles stylesheet rewriting to accommodate the orientation. It works by appending -lt or -rt to the stylesheet name.

For instance: `/web/skin/portal/webui/component/UIFooterPortlet/DefaultStylesheet-rt.css` will return the same stylesheet as `/web/skin/portal/webui/component/UIFooterPortlet/DefaultStylesheet.css` but processed for the RT orientation. The `-lt` suffix is optional.

Stylesheet authors can annotate their stylesheet to create content that depends on the orientation.

Example 3.2.

In the example, we need to use the orientation to modify the float attribute that will make the horizontal tabs either float on left or on right:

```
float: left; /* orientation=lt */
float: right; /* orientation=rt */
font-weight: bold;
text-align: center;
white-space: nowrap;
```

The LT produced output will be:

```
float: left; /* orientation=lt */
font-weight: bold;
text-align: center;
white-space: nowrap;
```

The RT produced output will be:

```
float: right; /* orientation=rt */
font-weight: bold;
text-align: center;
white-space: nowrap;
```

Example 3.3.

In this example, you need to modify the padding according to the orientation:

```
color: white;
line-height: 24px;
padding: 0px 5px 0px 0px; /* orientation=lt */
padding: 0px 0px 0px 5px; /* >orientation=rt */
```

The LT produced output will be:

```
color: white;
line-height: 24px;
padding: 0px 5px 0px 0px; /* orientation=lt */
```

The RT produced output will be:

```
color: white;
line-height: 24px;
padding: 0px 0px 0px 5px; /* orientation=rt */
```

3.7.3. Images

Sometimes, it is necessary to create the RT version of an image that will be used from a template or from a stylesheet. However, symmetric images can be automatically generated avoiding the necessity to create a mirrored version of an image and furthermore avoiding maintenance cost.

The web resource filter uses the same naming pattern as the skin service. When an image ends with the -rt suffix, the portal will attempt to locate the original image and create a mirror of it.

For instance: requesting the image `/GateInResources/skin/DefaultSkin/webui/component/UITabSystem/UITabs/background/NormalTabStyle-rt.gif` returns a mirror of

the image `/GateInResources/skin/DefaultSkin/webui/component/UITabSystem/UITabs/background/NormalTabStyle.gif`.



Note

It is important to consider whether the image to be mirrored is symmetrical as this will impact its final appearance.

Here is an example combining stylesheet and images:

```
line-height: 24px;
background: url('background/NavigationTab.gif') no-repeat right top; /* orientation=lt */
background: url('background/NavigationTab-rt.gif') no-repeat left top; /* orientation=rt */
padding-right: 2px; /* orientation=lt */
padding-left: 2px; /* orientation=rt */
```

3.7.4. Client side JavaScript

The `eXo.core.I18n` object provides the following parameters for orientation:

`getOrientation()`

Return either the string `lt` or `rt`

`getDir()`

Return either the string `ltr` or `rtl`

`isLT()`

Return true for `LT`

`isRT()`

Return true of `RT`

3.8. XML Resources Bundles

3.8.1. Motivation

Resource bundles are usually stored in property files. However, as property files are plain files, issues with the encoding of the file may arise. The XML resource bundle format has been developed to provide an alternative to property files.

- The XML format declares the encoding of the file. This avoids use of the `native2ascii` program which can interfere with encoding.

- Property files generally use the ISO 8859-1 character encoding which does not cover the full unicode charset. As a result, languages, such as Arabic, would not be natively supported.
- Tooling for XML files is better supported than the tooling for Java property files; thus, the XML editor copes well with the file encoding.

3.8.2. XML format

The XML format is very simple and has been developed based on the *DRY* (Don't Repeat Yourself) principle. The resource bundle keys are hierarchically defined and we can leverage the hierarchic nature of the XML for that purpose. Here is an example of turning a property file into an XML resource bundle file:

```
UIAccountForm.tab.label.AccountInputSet = ...
UIAccountForm.tab.label.UIUserProfileInputSet = ...
UIAccountForm.label.Profile = ...
UIAccountForm.label.HomeInfo= ...
UIAccountForm.label.BusinessInfo= ...
UIAccountForm.label.password= ...
UIAccountForm.label.Confirmpassword= ...
UIAccountForm.label.email= ...
UIAccountForm.action.Reset= ...
```

```
<?xml version="1.0" encoding="UTF-8"?>
<bundle>
  <UIAccountForm>
    <tab>
      <label>
        <AccountInputSet>...</AccountInputSet>
        <UIUserProfileInputSet>...</UIUserProfileInputSet>
      </label>
    </tab>
    <label>
      <Profile>...</Profile>
      <HomeInfo>...</HomeInfo>
      <BusinessInfo>...</BusinessInfo>
      <password>...</password>
      <Confirmpassword>...</Confirmpassword>
      <email>...</email>
    </label>
    <action>
      <Reset>...</Reset>
    </action>
```



```
</UIAccountForm>
</bundle>
```

3.8.3. Portal support

To be loaded by the portal at runtime (actually the resource bundle service), the name of the file must be the same as a property file and it must use the **.xml** suffix.

For example, for the Account Portlet to be displayed in Arabic, the resource bundle would be **AccountPortlet_ar.xml** rather than **AccountPortlet_ar.properties**.

3.9. JavaScript Inter Application Communication

3.9.1. Overview

JavaScript Inter Application Communication is designed to allow applications within a page to exchange data. This library is made for broadcasting messages on topic.

It is based on 3 functions:

- Subscribe.
- Publish.
- Unsubscribe.

A subscription to a topic will receive any subtopic messages. For example, the application subscribed to `/eXo/application` will receive messages sent on the `/eXo/application/map` topic. A message sent on `/eXo` would not be received.

Subscription Topics

`/eXo`

This topic contains all the events generated by eXo Platform.

`/eXo/portal/notification`

A message sent on this topic will prompt a pop-up notification at the top right of the screen.

3.9.2. Library

The Inter Application Communication library is found in `01eXoResources.war:/javascript/eXo/core/Topic.js`

```
/**
 * publish is used to publish an event to the other subscribers to the given channels
```

```
* @param {Object} senderId is a string that identify the sender
* @param {String} topic is the topic that the message will be published
* @param {Object} message is the message that's going to be delivered to the subscribers to
the topic
*/
Topic.prototype.publish = function(/*Object*/ senderId, /*String*/ topicName, /*Object*/ message
) { ... }

/**
* isSubscribed is used to check if a function receive the events from a topic
* @param {String} topic The topic.
* @param {Function} func is the name of the function of obj to call when a message is received
on the topic
*/
Topic.prototype.isSubscribed = function(/*String*/ topic, /*Function*/ func) { ... }

/**
* subscribe is used to subscribe a callback to a topic
* @param {String} topic is the topic that will be listened
* @param {Function} func is the name of the function of obj to call when a message is received
on the topic
*
* func is a function that take a Object in parameter. the event received have this format:
* {senderId:senderId, message:message, topic: topic}
*
*/
Topic.prototype.subscribe = function(/*String*/ topic, /*Function*/ func) { ... }

/**
* unsubscribe is used to unsubscribe a callback to a topic
* @param {String} topic is the topic
* @param {Object} id is the id of the listener we want to unsubscribe
*/
Topic.prototype.unsubscribe = function(/*String*/ topic, /*Object*/ id) { ... }

Topic.prototype.initCometdBridge = function() { ... }
```

3.9.3. Syntax

The three messaging functions require particular objects and definitions in their syntax:

Subscribe

The `subscribe` function is used to subscribe a callback to a topic. It uses the following parameters:

topic

The topic that will be listened for.

func

The name of the object function to call when a message is received on the topic. It has to be a function that takes an Object parameter. The event received will have this format:

```
{
  senderId:senderId,
  message:message,
  topic: topic
}
```

Publish

The `publish` function is used to publish an event to the other subscribed applications through the given channels. Its parameters are:

senderId

This is a string that identifies the sender.

topicName

The topic that the message will be published.

message

This is the message body to be delivered to the subscribers to the topic.

Unsubscribe

The `unsubscribe` function is used to unsubscribe a callback to a topic. The required parameters are:

topic

The topic from which will be unsubscribed.

id

This is the context object.

3.9.4. Example of Javascript events usage

```
<%@ taglib uri="http://java.sun.com/portlet" prefix="portlet" %>
<portlet:defineObjects/>
<div>
  <p>
    Received messages:
    <div id="received_<portlet:namespace/>">

  </div>
```

```
</p>

<p>
  Send message:
      <input type="text" id="msg_<portlet:namespace/>"/> <a href="#"
onclick="send_<portlet:namespace/>();">send</a>
</p>
</div>

<script type="text/javascript">

Function.prototype.bind = function(object) {
  var method = this;
  return function() {
    method.apply(object, arguments);
  }
}

function send_<portlet:namespace/>() {
  var msg = document.getElementById("msg_<portlet:namespace/>").value;
  eXo.core.Topic.publish("<portlet:namespace/>", "/demo", msg);
}

function Listener_<portlet:namespace/>(){

}

Listener_<portlet:namespace/>.prototype.receiveMsg = function(event) {
  document.getElementById("received_<portlet:namespace/>").innerHTML =
    document.getElementById("received_<portlet:namespace/>").innerHTML + "<br />* " +
    event.senderId + ": " + event.message;
}

function init_<portlet:namespace/>() {
  var listener_<portlet:namespace/> = new Listener_<portlet:namespace/>();
  eXo.core.Topic.subscribe("/demo", listener_<portlet:namespace/>
>.receiveMsg.bind(listener_<portlet:namespace/>));
}

init_<portlet:namespace/>();
</script>
```

3.10. Upload Component

3.10.1. Upload Service

The service is defined by the class: `org.exoplatform.upload.UploadService`;

This can be configured with the following xml code:

```
<component>
  <type>org.exoplatform.upload.UploadService</type>
  <init-params>
    <value-param>
      <name>upload.limit.size</name>
      <description>Maximum size of the file to upload in MB</description>
      <value>10</value>
    </value-param>
  </init-params>
</component>
```

This code allows for a default upload size limit for the service to be configured. The value unit is in MegaBytes.

This limit will be used by default by all applications if no application-specific limit is set. Setting a different limit for applications is discussed in a later section.

If the value is set to *0*, the upload size is unlimited.

Procedure 3.2. How to use the upload component

1. Create an object type `org.exoplatform.webui.form.UIFormUploadInput`.

Two constructors are available for this:

```
public UIFormUploadInput(String name, String bindingExpression)
```

or:

```
public UIFormUploadInput(String name, String bindingExpression, int limit)
```

This is an example using the second form:

```
PortletRequestContext                pcontext                =
(PortletRequestContext)WebuiRequestContext.getCurrentInstance();
PortletPreferences portletPref = pcontext.getRequest().getPreferences();
int limitMB = Integer.parseInt(portletPref.getValue("uploadFileSizeLimitMB", "").trim());
UIFormUploadInput uiInput = new UIFormUploadInput("upload", "upload", limitMB);
```

2. To obtain the limit from the `xml` configuration, this piece of code can be added to the either `portlet.xml` or `portlet-preferences.xml`:

```
<preference>
  <name>uploadFileSizeLimitMB</name>
  <value>30</value>
  <read-only>false</read-only>
</preference>
```

Again, the `0` value means an unlimited upload size, and the value unit is set in MegaBytes.

3. Use the `getUploadDataAsStream()` method to get the uploaded data:

```
UIFormUploadInput input = (UIFormUploadInput)uiForm.getUIInput("upload");
InputStream inputStream = input.getUploadDataAsStream();
...
jcrData.setValue(inputStream);
```

4. The upload service stores a temporary file on the file system during the upload process. When the upload is finished, the service must be cleaned to:

1. Delete the temporary file.
2. Delete the classes used for the upload.

Use the `removeUpload()` method defined in the upload service to purge the file:

```
UploadService uploadService = uiForm.getApplicationComponent(UploadService.class);
UIFormUploadInput uiChild = uiForm.getChild(UIFormUploadInput.class);
uploadService.removeUpload(uiChild.getUploadId());
```



Saving the uploaded file

Ensure the file is saved **before** the service is cleaned.

3.11. Deactivation of the Ajax Loading Mask Layer

3.11.1. Purpose

The loading mask layer is deployed after an ajax-call. It aims at blocking the GUI to prevent further user actions until the the ajax-request has been completed.

However, the mask layer may need to be deactivated in instances where the portal requires user instructions before the previous instructions have been carried out.

Procedure 3.3. How to deactivate the ajax-loading mask

1. Generate a script to make an asynchronous ajax-call. Use the `uicomponent.doAsync()` method rather than the `uicomponent.event()` method.

For example:

```
<a href="<%=uicomponent.doAsync(action, beanId, params)%>" alt="">Asynchronous</a>
```

2. The `doAsync()` method automatically adds the following new parameter to the parameters list; `asyncparam = new Parameter(AJAX ASYNC,"true");` (AJAX ASYNC == "ajax async")

This request is asynchronous and the ajax-loading mask will not deployed.



Note

An asynchronous request can still be made using the `uicomponent.event()`. When using this method, the `asyncparam` must be added manually.

The GUI will be blocked to ensure that the user can only request one action at one time and while the request seems to be synchronous, all ajax requests are always asynchronous. For further information, refer to [Section 3.11.2, "Synchronous issue"](#).

3.11.2. Synchronous issue

Most web browsers support ajax requests in two modes: *Synchronous* and *Asynchronous*. This mode is specified with a boolean `bAsync` parameter.

```
var bAsync = false; // Synchronous
request.open(instance.method, instance.url, bAsync);
```

However, to work with browsers that do not support the *Synchronous* requests, `bAsync` is always set to true (Ajax request will always be asynchronous).

```
// Asynchronous request
request.open(instance.method, instance.url, true);
```

3.12. JavaScript Configuration

Managing JavaScript in an application like GateIn 3.1 is a critical part of the configuration work. Configuring the scripts correctly will result in the faster response time from the portal.

Every portlet can have its own JavaScript code but in many cases, it is more convenient to reuse some existing shared libraries. For that reason, GateIn 3.1 has a mechanism to easily register the libraries that will be loaded when every page is rendered.

To do so, every WAR deployed in GateIn 3.1 can register the `.js` files with the **gatein-resources.xml** configuration file.

The example code snippet below is found in the **gatein-resources.xml** in the **eXoResources.war** file.

```
<javascript>
  <param>
    <js-module>eXo</js-module>
    <js-path>/javascript/eXo.js</js-path>
    <js-priority>0</js-priority>
  </param>
</javascript>

<!-- CORE Javascripts -->
<javascript>
  <param>
    <js-module>eXo.core.Utils</js-module>
    <js-path>/javascript/eXo/core/Util.js</js-path>
    <js-priority>1</js-priority>
  </param>
  <param>
    <js-module>eXo.core.DOMUtil</js-module>
    <js-path>/javascript/eXo/core/DOMUtil.js</js-path>
```



```

    <js-priority>1</js-priority>
  </param>
  <param>
    <js-module>eXo.core.Browser</js-module>
    <js-path>/javascript/eXo/core/Browser.js</js-path>
    <js-priority>2</js-priority>
  </param>
  <param>
    <js-module>eXo.core.MouseEventManager</js-module>
    <js-path>/javascript/eXo/core/EventManager.js</js-path>
  </param>
  <param>
    <js-module>eXo.core.UIMaskLayer</js-module>
    <js-path>/javascript/eXo/core/UIMaskLayer.js</js-path>
  </param>
  <param>
    <js-module>eXo.core.Skin</js-module>
    <js-path>/javascript/eXo/core/Skin.js</js-path>
  </param>
  <param>
    <js-module>eXo.core.DragDrop</js-module>
    <js-path>/javascript/eXo/core/DragDrop.js</js-path>
  </param>
  <param>
    <js-module>eXo.core.DragDrop2</js-module>
    <js-path>/javascript/eXo/core/DragDrop2.js</js-path>
  </param>
</javascript>

```

Note that registered JavaScript files will be merged into a single `merged.js` file when the server loads. This reduces the number of HTTP calls as shown in the homepage source code:

```
<script type="text/javascript" src="/portal/javascript/merged.js"></script>
```

Although this optimization is useful for a production environment, it may be easier to deactivate this optimization while debugging JavaScript problems.

To do this, set the Java system property `exo.product.developing` to `true`. GateIn provides two startup scripts that define this property in `gatein-dev.sh` (for Linux, Mac) and `gatein-dev.bat` (for Windows).

To generate the `merged.js` file, set this property to `false`. If the property is not set, the default value is `false`.

The property can be passed as a JVM parameter with the `-D` option in your `GateIn.sh` or `GateIn.bat` startup script.

Every JavaScript file is associated with a module name which acts as a namespace.

Inside the associated JavaScript files, the eXo JavaScript objects are exposed as global variables named after the module.

For example:

```
eXo.core.DragDrop = new DragDrop();
```

It is also possible to use the `eXo.require()` method to lazy load and evaluate some JavaScript codes. This is quite useful for the portlet or gadget applications that will use this JavaScript only once. Otherwise, if the library is reusable in several places, it is better to define it in the **gatein-resources.xml** file.

Portlet development

4.1. Portlet Primer

4.1.1. JSR-168 and JSR-286 overview

The Java Community Process (JCP) uses Java Specification Requests (JSRs) to define proposed specifications and technologies designed for the Java platform.

The Portlet Specifications aim at defining portlets that can be used by any [JSR-168 \(Portlet 1.0\)](http://www.jcp.org/en/jsr/detail?id=168) [http://www.jcp.org/en/jsr/detail?id=168] or [JSR-286 \(Portlet 2.0\)](http://www.jcp.org/en/jsr/detail?id=286) [http://www.jcp.org/en/jsr/detail?id=286] portlet container.

Most Java EE (Enterprise Edition) portals include at least one compliant portlet container, and GateIn 3.1 is no exception. In fact, GateIn 3.1 includes a container that supports both versions.


This chapter gives a brief overview of the Portlet Specifications, but portlet developers are strongly encouraged to read the [JSR-286 Portlet Specification](http://www.jcp.org/en/jsr/detail?id=286) [http://www.jcp.org/en/jsr/detail?id=286] .

GateIn 3.1 is fully JSR-286 compliant. Any JSR-168 or JSR-286 portlet operates as it is mandated by the respective specifications inside the portal.

4.1.1.1. Portal Pages

A portal can be considered as a series of web pages with different *areas* within them. Those areas contain different *windows* and each *window* contains portlet:

The diagram below visually represents this nesting:



4.1.1.2. Rendering Modes

A portlet can have different view modes. Three modes are defined by the JSR-286 specification:

View

Generate the markup reflecting the current state of the portlet.

Edit

Allow you to customize the behavior of the portlet.

Help

Provide information to the user as to how to use the portlet.

4.1.1.3. Window States

Window states are an indicator of how much page space a portlet consumes on any given page. The three states defined by the JSR-168 specification are:

Normal

A portlet shares this page with other portlets.

Minimized

A portlet may show very little information, or none at all.

Maximized

A portlet may be the only portlet displayed on this page.

4.1.2. Tutorials

The tutorials contained in this chapter are targeted towards portlet developers. It is also recommended that developers read and understand the [JSR-286 Portlet Specification](http://www.jcp.org/en/jsr/detail?id=286) [http://www.jcp.org/en/jsr/detail?id=286] .



Maven

This example is using Maven to compile and build the web archive. Maven versions can be downloaded from [maven.apache.org](http://maven.apache.org/download.html) [http://maven.apache.org/download.html]

4.1.2.1. Deploying your first Portlet

This section describes how to deploy a portlet in GateIn 3.1. A sample portlet called `SimplestHelloWorld` is located in the `examples` directory at the root of your GateIn 3.1 binary package. This sample is used in the following examples.


4.1.2.1.1. Compiling

To compile and package the application:

1. Navigate to the `SimplestHelloWorld` directory and execute:

```
mvn package
```

2. If the compile is successfully packaged, the result will be available in: `SimplestHelloWorld/target/SimplestHelloWorld-0.0.1.war` .
3. Copy the package file into `JBOSS_HOME/server/default/deploy`.
4. Start the JBoss Application Server (if it is not already running).
5. Create a new portal page and add the portlet to it.



4.1.2.1.2. Package Structure

Like other Java EE applications, GateIn 3.1 portlets are packaged in the .war files. A typical portlet .war file can include servlets, resource bundles, images, HTML, JavaServer Pages (JSP), and other static or dynamic files.

The following is an example of the directory structure of the `SimplestHelloWorld` portlet:

```
|-- SimplestHelloWorld-0.0.1.war
|  |-- WEB-INF
|    |-- classes
|      |-- org
|        |-- gatein
|          |-- portal
|            |-- examples
|              |-- portlets
|                |-- SimplestHelloWorldPortlet.class ①
|              |-- portlet.xml ②
|            |-- web.xml ③
```

- ① The compiled Java class implementing *javax.portlet.Portlet* (through *javax.portlet.GenericPortlet*)
- ② This is the mandatory descriptor files for portlets. It is used during deployment.
- ③ This is the mandatory descriptor for web applications.

4.1.2.1.3. Portlet Class

Below is the `SimplestHelloWorldPortlet/src/main/java/org/gatein/portal/examples/portlets/SimplestHelloWorldPortlet.java` Java source:

```
package org.gatein.portal.examples.portlets;

import java.io.IOException;
import java.io.PrintWriter;

import javax.portlet.GenericPortlet;
import javax.portlet.RenderRequest;
import javax.portlet.RenderResponse;

public class SimplestHelloWorldPortlet extends GenericPortlet
{
    public void doView(RenderRequest request,
                       RenderResponse response) throws IOException
    {
        PrintWriter writer = response.getWriter();
        writer.write("Hello World !");
        writer.close();
    }
}
```

- 1 All portlets must implement the `javax.portlet.Portlet` interface. The portlet API provides a convenient implementation of this interface.

The `javax.portlet.Portlet` interface uses the `javax.portlet.GenericPortlet` class which implements the `Portlet render` method to dispatch to abstract mode-specific methods. This makes it easier to support the standard portlet modes.

`Portlet render` also provides a default implementation for the `processAction`, `init` and `destroy` methods. It is recommended to extend `GenericPortlet` for most cases.

- 2 If only the `view` mode is required, only the `doView` method needs to be implemented. The `GenericPortletrender` implementation calls our implementation when the `view` mode is requested.
- 3 Use the `RenderResponse` to obtain a writer to be used to produce content.
- 4 Write the markup to display.
- 5 Close the writer.



Markup Fragments

Portlets are responsible for generating markup fragments, as they are included on a page and are surrounded by other portlets. This means that a portlet outputting HTML must not output any markup that cannot be found in a `<body>` element.

4.1.2.1.4. Application Descriptors

GateIn 3.1 requires certain descriptors to be included in a portlet WAR file. These descriptors are defined by the Java EE (`web.xml`) and Portlet Specification (`portlet.xml`).

Below is an example of the `SimplestHelloWorldPortlet/WEB-INF/portlet.xml` file. This file must adhere to its definition in the JSR-286 Portlet Specification. More than one portlet application may be defined in this file:

```
<portlet-app xmlns="http://java.sun.com/xml/ns/portlet/portlet-app_2_0.xsd"
  xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
  xsi:schemaLocation="http://java.sun.com/xml/ns/portlet/portlet-app_2_0.xsd
    http://java.sun.com/xml/ns/portlet/portlet-app_2_0.xsd"
  version="2.0">
  <portlet>

    <portlet-name>SimplestHelloWorldPortlet</portlet-name>           ①

    <portlet-class>                                                    ②
      org.gatein.portal.examples.portlets.SimplestHelloWorldPortlet
    </portlet-class>

    <supports>                                                         ③
      <mime-type>text/html</mime-type>
    </supports>

    <portlet-info>                                                     ④
      <title>Simplest Hello World Portlet</title>
    </portlet-info>
  </portlet>
</portlet-app>
```

- ① Define the portlet name. It does not have to be the class name.
- ② The Fully Qualified Name (FQN) of your portlet class must be declared here.

- 3 The `<supports>` element declares all of the markup types that a portlet supports in the render method. This is accomplished via the `<mime-type>` element, which is required for every portlet.

The declared MIME types must match the capability of the portlet. It allows administrators to pair which modes and window states are supported for each markup type.

This does not have to be declared as all portlets must support the `view` portlet mode.


Use the `<mime-type>` element to define which markup type the portlet supports. In the example above, this is `text/html`. This section tells the portal to only output HTML.

- 4 When rendered, the portlet's title is displayed as the header in the portlet window, unless it is overridden programmatically. In the example above, the title would be `Simplest Hello World Portlet`.

4.1.2.2. JavaServer Pages Portlet Example

This section discusses:

1. Add more features to the previous example.
 2. Use a JSP page to render the markup.
 3. Use the portlet tag library to generate links to the portlet in different ways.
 4. Use the other standard portlet modes.
-
1. The example used in this section can be found in the `JSPHelloUser` directory.
 2. Execute `mvn package` in this directory.
 3. Copy `JSPHelloUser/target/JSPHelloUser-0.0.1.war` to the `deploy` directory of JBoss Application Server.
 4. Select the new `JSPHelloUser` tab in your portal.



Note

The `EDIT` button only appears with logged-in users, which is not the case in the screenshot.

4.1.2.2.1. Package Structure

The package structure in this tutorial does not much differ from the previous example, with the exception of adding some JSP files detailed later.

The JSPHelloUser portlet contains the mandatory portlet application descriptors. The following is an example of the directory structure of the JSPHelloUser portlet:

```
JSPHelloUser-0.0.1.war
|-- META-INF
| |-- MANIFEST.MF
|-- WEB-INF
| |-- classes
| | `-- org
| |   |-- gatein
| |   |-- portal
| |   |-- examples
| |   `-- portlets
```

```
| |          |-- JSPHelloUserPortlet.class
| |-- portlet.xml
| |-- web.xml
|-- jsp
|   |-- edit.jsp
|   |-- hello.jsp
|   |-- help.jsp
|   |-- welcome.jsp
```

4.1.2.2.2. Portlet Class

The code below is from the `JSPHelloUser/src/main/java/org/gatein/portal/examples/portlets/JSPHelloUserPortlet.java` Java source. It is split in different pieces.

```
package org.gatein.portal.examples.portlets;

import java.io.IOException;

import javax.portlet.ActionRequest;
import javax.portlet.ActionResponse;
import javax.portlet.GenericPortlet;
import javax.portlet.PortletException;
import javax.portlet.PortletRequestDispatcher;
import javax.portlet.RenderRequest;
import javax.portlet.RenderResponse;
import javax.portlet.UnavailableException;

public class JSPHelloUserPortlet extends GenericPortlet
{
    public void doView(RenderRequest request, RenderResponse response)
        throws PortletException, IOException 1
    {
        String sYourName = (String) request.getParameter("yourname");

        if (sYourName != null) 2
        {
            request.setAttribute("yourname", sYourName);
            PortletRequestDispatcher prd =

                getPortletContext().getRequestDispatcher("/jsp/hello.jsp"); 3

            prd.include(request, response); 4
        }
    }
}
```

```
else
{
    PortletRequestDispatcher prd = getPortletContext().getRequestDispatcher("/jsp/
welcome.jsp");
    prd.include(request, response);
}
}
...
```

- ❶ Override the *doView* method (as in the first tutorial).
- ❷ This entry attempts to obtain the value of the render parameter named `yourname`. If defined, it should redirect to the `hello.jsp` JSP page or to the `welcome.jsp` JSP page.
- ❸ Get a request dispatcher on a file located within the web archive.
- ❹ Perform the inclusion of the markup obtained from the JSP.

Like the `VIEW` portlet mode, the specification defines two other modes; `EDIT` and `HELP`.

These modes need to be defined in the `portlet.xml` descriptor. This enables the corresponding buttons on the portlet's window.

The generic portlet that is inherited dispatches different views to the methods: `doView`, `doHelp` and `doEdit`.

```
...
protected void doHelp(RenderRequest rRequest, RenderResponse rResponse) throws
PortletException, IOException,
    UnavailableException
{
    rResponse.setContentType("text/html");
    PortletRequestDispatcher prd = getPortletContext().getRequestDispatcher("/jsp/help.jsp");
    prd.include(rRequest, rResponse);
}

protected void doEdit(RenderRequest rRequest, RenderResponse rResponse) throws
PortletException, IOException,
    UnavailableException
{
    rResponse.setContentType("text/html");
    PortletRequestDispatcher prd = getPortletContext().getRequestDispatcher("/jsp/edit.jsp");
    prd.include(rRequest, rResponse);
}
...
```

Portlet calls happen in one or two phases: when the portlet is rendered and when the portlet is actioned *and then* rendered.

An action phase is a phase where containing some state changes. The render phase will have access to render parameters that will be passed each time the portlet is refreshed (with the exception of caching capabilities).

The code to be executed during an action has to be implemented in the *processAction* method of the portlet.

```
...
    public void processAction(ActionRequest aRequest, ActionResponse aResp1onse) throws
PortletException, IOException,
    UnavailableException
    {
        String sYourname = (String) aRequest.getParameter("yourname");2
        aResponse.setRenderParameter("yourname", sYourname);3
    }
...
```

- ¹ *processAction* is the method from *GenericPortlet* to override for the *action* phase.
- ² Here the parameter is retrieved through an *action URL*.
- ³ The value of *yourname* is kept to make it available in the rendering phase. The previous line simply copies action parameters to a render parameter for this example.

4.1.2.2.3. JSP files and the Portlet Tag Library

The *help.jsp* and *edit.jsp* files are very simple. Note that CSS styles are used as defined in the portlet specification. This ensures that the portlet will render successfully within the theme and across portal vendors.

```
<div class="portlet-section-header">Help mode</div>
<div class="portlet-section-body">This is the help mode where you can find useful information.</div>
```

```
<div class="portlet-section-header">Edit mode</div>
<div class="portlet-section-body">This is the edit mode where you can change your portlet preferences.</div>
```

The landing page contains the links and form to call the portlet:

```
<%@ taglib uri="http://java.sun.com/portlet" prefix="portlet" %> 1

<div class="portlet-section-header">Welcome !</div>

<br/>

<div class="portlet-font">Welcome on the JSP Hello User portlet,
my name is GateIn Portal. What's yours ?</div>

<br/>

<div class="portlet-font">Method 1: We simply pass the parameter to the render phase:<br/>
<a href="<portlet:renderURL><portlet:param name="yourname" value="John Doe"/> 2
    </portlet:renderURL>">John Doe</a></div>

<br/>

<div class="portlet-font">Method 2: We pass the parameter to the render phase, using valid XML:
Please check the source code to see the difference with Method 1.

<portlet:renderURL var="myRenderURL"> 3
    <portlet:param name="yourname" value='John Doe' />
</portlet:renderURL>
<br/>

<a href="<%= myRenderURL %>">John Doe</a></div> 4

<br/>


<div class="portlet-font">Method 3: We use a form:<br/>

<portlet:actionURL var="myActionURL"/> 5

<form action="<%= myActionURL %>" method="POST"> 6
    <span class="portlet-form-field-label">Name:</span>
    <input class="portlet-form-input-field" type="text" name="yourname"/>
    <input class="portlet-form-button" type="Submit"/>
</form>
</div>
```

- ① The portlet taglib which needs to be declared.
- ② The first method shown here is the simplest one. `portlet:renderURL` will create a URL that calls the render phase of the current portlet and append the result at the place of the markup (within a tag). A parameter is also added directly to the URL.
- ③ In this method, the `var` attribute is used. This avoids having one XML tag within another. Instead of printing the url, the `portlet:renderURL` tag will store the result in the referenced variable (`myRenderURL`).
- ④ The variable `myRenderURL` is used like any other JSP variable.
- ⑤ The third method mixes the form submission and action request. Again, a temporary variable is used to put the created URL into.
- ⑥ The action URL is used in the HTML form.

In the third method, the action phase is triggered first, then the render phase is triggered, which outputs some content back to the web browser based on the available render parameters.



4.1.2.2.4. JSF example using the JBoss Portlet Bridge

To write a portlet using JSF, it is required to have a 'bridge'. This software allows developers to write a portlet application as if it was a JSF application. The bridge then negotiates the interactions between the two layers.

An example of the JBoss Portlet Bridge is available in `examples/JSFHelloUser`. The configuration is slightly different from a JSP application. This example can be used as a base to configure instead of creating a new application.

As in any JSF application, the file `faces-config.xml` is required. It must contain the following information:

```
<faces-config>
...
<application>
  <view-handler>org.jboss.portletbridge.application.PortletViewHandler</view-handler>
  <state-manager>org.jboss.portletbridge.application.PortletStateManager</state-manager>
</application>
...
</faces-config>
```

The portlet bridge libraries must be available and are usually bundled with the `WEB-INF/lib` directory of the web archive.

The other differences as compared to a regular portlet application can be found in the portlet descriptor. All details about it can be found in the JSR-301 specification that the JBoss Portlet Bridge implements.

```
<?xml version="1.0" encoding="UTF-8"?>
<portlet-app xmlns="http://java.sun.com/xml/ns/portlet/portlet-app_2_0.xsd"
  xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
  xsi:schemaLocation="http://java.sun.com/xml/ns/portlet/portlet-app_2_0.xsd
    http://java.sun.com/xml/ns/portlet/portlet-app_2_0.xsd"
  version="2.0">
  <portlet>
    <portlet-name>JSFHelloUserPortlet</portlet-name>

    <portlet-class>javax.portlet.faces.GenericFacesPortlet</portlet-class> ①
    <supports>
      <mime-type>text/html</mime-type>
      <portlet-mode>view</portlet-mode>
      <portlet-mode>edit</portlet-mode>
      <portlet-mode>help</portlet-mode>
    </supports>
    <portlet-info>
      <title>JSF Hello User Portlet</title>
    </portlet-info>

    <init-param>
      <name>javax.portlet.faces.defaultViewId.view</name> ②
      <value>/jsf/welcome.jsp</value>
    </init-param>

    <init-param>
      <name>javax.portlet.faces.defaultViewId.edit</name> ③
      <value>/jsf/edit.jsp</value>
    </init-param>

    <init-param>
      <name>javax.portlet.faces.defaultViewId.help</name> ④
      <value>/jsf/help.jsp</value>
    </init-param>

  </portlet>
```



```
</portlet-app>
```

- ① All JSF portlets define `javax.portlet.faces.GenericFacesPortlet` as the portlet class. This class is part of the JBoss Portlet Bridge.
- ② This is a mandatory parameter to define what's the default page to display.
- ③ This parameter defines which page to display on the 'edit' mode.
- ④ This parameter defines which page to display on the 'help' mode.

4.2. Global portlet.xml file

4.2.1. Global portlet.xml usecase

The Portlet Specification introduces `PortletFilter` as a standard approach to extend the behaviors of portlet objects. For example, a filter can transform the content of portlet requests and portlet responses. According to the Portlet Specification, normally there are three steps in setting up a portlet filter:

1. Implement a `PortletFilter` object
2. Define the filter in portlet application deployment descriptor
3. Define the filter mapping in portlet definitions

Two first steps are quite simple and easy to be done, however, at the step 3, developers/administrators need to replicate the filter mapping in many portlet definitions, that makes work error and tedious in several use cases. The global portlet feature is designed to compensate such limitation.

4.2.2. Global metadata

The Global metadata is declared in the *portlet.xml* file conforming with Portlet 2.0 's XSD.

```
<portlet-app version="1.0" xmlns="http://java.sun.com/xml/ns/portlet/portlet-app_2_0.xsd"
  xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
  xsi:schemaLocation="http://java.sun.com/xml/ns/portlet/portlet-app_2_0.xsd http://
java.sun.com/xml/ns/portlet/portlet-app_2_0.xsd">

</portlet-app>
```

4.2.2.1. Location

The path to the global *portlet.xml* is value of *gatein.portlet.config* in the *configuration.properties* file and varied by hosting application servers.

For Tomcat: *TOMCAT_HOME/gatein/conf/portlet.xml*

For JBoss: *JBOSS_HOME/server/default/conf/gatein/portlet.xml*

4.2.2.2. Global metadata elements

The global *portlet.xml* file conforms to the schema of the portlet deployment descriptor defined in the Portlet Specification with some restrictions. In this file, the following elements are supported:

1. Portlet Filter
2. Portlet Mode
3. Window State

4.2.2.2.1. Portlet filter

Portlet filter mappings declared in the global *portlet.xml* file are applied across portlet applications. With the XML configuration below, the filter `ApplicationMonitoringFilter` involves in request handling on any deployed portlet.

```
<filter>
  <filter-name>org.exoplatform.portal.application.ApplicationMonitoringFilter</filter-name>
  <filter-class>org.exoplatform.portal.application.ApplicationMonitoringFilter</filter-class>
  <lifecycle>ACTION_PHASE</lifecycle>
  <lifecycle>RENDER_PHASE</lifecycle>
  <lifecycle>EVENT_PHASE</lifecycle>
  <lifecycle>RESOURCE_PHASE</lifecycle>
</filter>
```

Application Monitoring Filter supports four lifecycle phases as the order below: *ACTION_PHASE*/ *EVENT_PHASE*/ *RENDER_PHASE*/ *RESOURCE_PHASE* and records statistic information on deployed portlets. The filter alternates actual monitoring mechanism in WebUI Framework.

4.2.2.2.2. Portlet Mode and Window State

The global *portlet.xml* file is considered as an alternative place to declare custom Portlet Modes and Window States.

Gadget development

5.1. Gadgets


A gadget is a mini web application, embedded in a web page and running on an application server platform. These small applications help users perform various tasks.

GateIn 3.1 supports gadgets, such as Todo, Calendar, Calculator, Weather Forecasts and RSS Reader.

Default Gadgets:


Calendar

The calendar gadget allows you to switch easily between daily, monthly and yearly views. Also, this gadget is customizable to match your portal's theme.




ToDo

This application helps you organize your day and work group. It is designed to keep track of your tasks in a convenient and transparent way. Tasks can be highlighted with different colors.



Calculator

This mini-application lets you perform the most basic arithmetic operations and can be themed to match the rest of your portal.



RSS Reader

An RSS reader, or aggregator collects content from various, user-specified feed sources and displays them in one location. This content can include, but is not limited to, news headlines,

blog posts or email. The RSS Reader gadget displays this content in a single window on your Portal page.

More Gadgets

Further gadgets can be obtained from the [Google Gadget](http://www.google.com/ig/directory?synd=open) [http://www.google.com/ig/directory?synd=open] site. GateIn 3.1 is compatible with most of the gadgets available here.



Important

The following sections require more textual information.

5.1.1. Existing Gadgets

Administration ▾

Categories Portlet Gadget

Add a remote gadget + Create a new gadget

Gadget Details

Gadget name: Calculator

Description: This simple and useful calculator lets you perform most of the basic arithmetic operations.

View URL: <http://localhost:8080/rest/jcr/repository/portal-system/production/app:gadgets/app:Calculator/app:data/app:resources/Calculator.xml>

Edit URL: <http://localhost:8080/rest/private/jcr/repository/portal-system/production/app:gadgets/app:Calculator/app:data/app:resources/Calculator.xml>

Reference: <http://www.exoplatform.org>

Categories: Gadgets

5.1.2. Create a new Gadget

Administration ▾

Categories Portlet Gadget

Add a remote gadget + Create a new gadget


Name: *

Source: `<?xml version="1.0" encoding="UTF-8"?><Module><ModulePrefs title="hello world example" description="The hello world gadget."/><Content type="html"> <![CDATA[Hello, world!]]></Content></Module>`

Save Cancel


5.1.3. Remote Gadget

This is the reference to a remote gadget (stock one).




5.1.4. Gadget Importing

After referencing the gadget successfully, import it into the local repository.




5.1.5. Gadget Web Editing

Modify it from the Web where the Gadget was imported:




5.1.6. Gadget IDE Editing

Edit it from your IDE thanks to the WebDAV protocol:



5.1.7. Dashboard Viewing

View it from the Dashboard when you drag and drop the Gadget from listing to the dashboard.



5.2. Set up a Gadget Server

5.2.1. Virtual servers for gadget rendering

GateIn 3.1 recommends using two virtual hosts for security. If the gadget is running on a different domain other than the container (the website that 'contains' the app), it is unable to interfere with the portal by modifying the code or cookies.

An example would hosting the portal from **http://www.sample.com** and the gadgets from **http://www.samplemodules.com**.

To do this, configure a parameter called *gadgets.hostName*. The value is the *path/to/gadgetServer* in *GadgetRegistryService*:

```
<component>
  <key>org.exoplatform.application.gadget.GadgetRegistryService</key>
  <type>org.exoplatform.application.gadget.jcr.GadgetRegistryServiceImpl</type>
  <init-params>
    <value-param>
      <name>gadgets.hostName</name>
      <description>Gadget server url</description>
      <value>http://localhost:8080/GateInGadgetServer/gadgets/</value>
    </value-param>
  </init-params>
</component>
```

It is also possible to have multiple rendering servers. This helps to balance the rendering load across multiple servers.

When deploying on the same server, ensure the gadget initiates before anything that calls it (for example; the webapp `GateInGadgets` which uses `org.exoplatform.application.gadget.GadgetRegister`).

5.2.2. Configuration

5.2.2.1. Security key

A file called **key.txt** has to be generated for every installation of GateIn 3.1 to be secure. This file contains a secret key used to encrypt the security token used for the user authentication.

In the Linux systems, this file can be generated with:

```
dd if=/dev/random bs=32 count=1 | openssl base64 > /tmp/key.txt
```


5.2.2.2. Gadget proxy and concat configuration

These servers have to be on the same domain as the gadget server. You can configure the container in `eXoGadgetServer: /WEB-INF/classes/containers/default/container.js`.

```
"gadgets.content-rewrite" : {  
  "include-urls": ".*",  
  "exclude-urls": "",  
  "include-tags": ["link", "script", "embed", "img", "style"],  
  "expires": "86400",  
  "proxy-url": "http://localhost:8080/eXoGadgetServer/gadgets/proxy?url=",  
  "concat-url": "http://localhost:8080/eXoGadgetServer/gadgets/concat?"  
},
```

5.2.2.3. Proxy

To allow external gadgets when the server is behind a proxy, add the following code to the beginning of the JVM:

```
-Dhttp.proxyHost=proxyhostURL -Dhttp.proxyPort=proxyPortNumber -  
Dhttp.proxyUser=someUserName -Dhttp.proxyPassword=somePassword
```


Authentication and Identity

6.1. Predefined User Configuration

6.1.1. Overview

To specify the initial Organization configuration, the content of `02portal.war:/WEB-INF/conf/organization/organization-configuration.xml` should be edited. This file uses the portal XML configuration schema. It lists several configuration plugins.

6.1.2. Plugin for adding users, groups and membership types

The `org.exoplatform.services.organization.OrganizationDatabaseInitializer` plugin of type `org.exoplatform.services.organization.OrganizationDatabaseInitializer` is used to specify the list of membership types/groups/users to be created.

The **checkDatabaseAlgorithm** initialization parameter determines how the database update is performed.

If its value is set to **entry**, it means that each user, group and membership listed in the configuration is checked each time GateIn 3.1 is started. If the entry does not exist in the database yet, it is created. If the **checkDatabaseAlgorithm** parameter value is set to **empty**, the configuration data will be updated to the database only if the database is empty.

6.1.3. Membership types

The predefined membership types are specified in the **membershipType** field of the **OrganizationConfig** plugin parameter.



Note

See `02portal.war:/WEB-INF/conf/organization/organization-configuration.xml` for the full content.

```
<field name="membershipType">
  <collection type="java.util.ArrayList">
    <value>
      <object type="org.exoplatform.services.organization.OrganizationConfig$MembershipType">
        <field name="type">
          <string>member</string>
        </field>
        <field name="description">
          <string>member membership type</string>
        </field>
      </object>
    </value>
  </collection>
</field>
```

```
</field>
</object>
</value>
<value>
  <object type="org.exoplatform.services.organization.OrganizationConfig$MembershipType">
    <field name="type">
      <string>owner</string>
    </field>
    <field name="description">
      <string>owner membership type</string>
    </field>
  </object>
</value>
<value>
  <object type="org.exoplatform.services.organization.OrganizationConfig$MembershipType">
    <field name="type">
      <string>validator</string>
    </field>
    <field name="description">
      <string>validator membership type</string>
    </field>
  </object>
</value>
</collection>
</field>
```

6.1.4. Groups

The predefined groups are specified in the **group** field of the **OrganizationConfig** plugin parameter.

```
<field name="group">
  <collection type="java.util.ArrayList">
    <value>
      <object type="org.exoplatform.services.organization.OrganizationConfig$Group">
        <field name="name">
          <string>portal</string>
        </field>
        <field name="parentId">
          <string></string>
        </field>
        <field name="type">
          <string>hierachy</string>
        </field>
      </object>
    </value>
  </collection>
</field>
```

```

    </field>
    <field name="description">
      <string>the /portal group</string>
    </field>
  </object>
</value>
<value>
  <object type="org.exoplatform.services.organization.OrganizationConfig$Group">
    <field name="name">
      <string>community</string>
    </field>
    <field name="parentId">
      <string>/portal</string>
    </field>
    <field name="type">
      <string>hierachy</string>
    </field>
    <field name="description">
      <string>the /portal/community group</string>
    </field>
  </object>
</value>
...
</collection>
</field>

```

6.1.5. Users

The predefined users are specified in the **membershipType** field of the **OrganizationConfig** plugin parameter.

```

<field name="user">
  <collection type="java.util.ArrayList">
    <value>
      <object type="org.exoplatform.services.organization.OrganizationConfig$User">
        <field name="userName"><string>root</string></field>
        <field name="password"><string>exo</string></field>
        <field name="firstName"><string>root</string></field>
        <field name="lastName"><string>root</string></field>
        <field name="email"><string>exoadmin@localhost</string></field>
        <field name="groups"><string>member:/admin,member:/user,owner:/portal/admin</string></field>
      </object>
    </value>
  </collection>
</field>

```

```
</value>
<value>
  <object type="org.exoplatform.services.organization.OrganizationConfig$User">
    <field name="userName"><string>exo</string></field>
    <field name="password"><string>exo</string></field>
    <field name="firstName"><string>site</string></field>
    <field name="lastName"><string>site</string></field>
    <field name="email"><string>exo@localhost</string></field>
    <field name="groups"><string>member:/user</string></field>
  </object>
</value>
...
</collection>
</field>
```

6.1.6. Plugin for monitoring user creation

The plugin of type `org.exoplatform.services.organization.impl.NewUserEventListener` specifies which groups all the newly created users should become members of. It specifies the groups and the memberships to use (while the group is just a set of users, a membership type represents a user's role within a group). It also specifies a list of users that should not be processed (i.e. administrative users like 'root').



Note

The terms 'membership' and 'membership type' refer to the same thing, and are used interchangeably.

```
<component-plugin>
  <name>new.user.event.listener</name>
  <set-method>addListenerPlugin</set-method>
  <type>org.exoplatform.services.organization.impl.NewUserEventListener</type>
  <description>this listener assign group and membership to a new created user</description>
  <init-params>
    <object-param>
      <name>configuration</name>
      <description>description</description>
      <object type="org.exoplatform.services.organization.impl.NewUserConfig">
        <field name="group">
          <collection type="java.util.ArrayList">
            <value>
              <object type="org.exoplatform.services.organization.impl.NewUserConfig$JoinGroup">
```

```

        <field name="groupId"><string>/user</string></field>
        <field name="membership"><string>member</string></field>
    </object>
</value>
</collection>
</field>
<field name="ignoredUser">
    <collection type="java.util.HashSet">
        <value><string>exo</string></value>
        <value><string>root</string></value>
        <value><string>company</string></value>
        <value><string>community</string></value>
    </collection>
</field>
</object>
</object-param>
</init-params>
</component-plugin>

```

6.2. Authentication Token Configuration

6.2.1. What is Token Service?

Token Service is used in authentication.

The token system prevents user account information being sent in the clear text mode within inbound requests. This increases authentication security.

The token service allows administrators to create, delete, retrieve and clean tokens as required. The service also defines a validity period of any given token. The token becomes invalid once this period expires.

6.2.2. Implementing the Token Service API

All token services used in the GateIn 3.1 authentication must be implemented by subclassing an **AbstractTokenService** abstract class. The following **AbstractTokenService** methods represent the contract between authentication runtime, and a token service implementation.

```

public Token getToken(String id) throws PathNotFoundException, RepositoryException;
public Token deleteToken(String id) throws PathNotFoundException, RepositoryException;
public String[] getAllTokens();
public long getNumberTokens() throws Exception;

```

```
public String createToken(Credentials credentials) throws
IllegalArgumentException,NullPointerException;
public Credentials validateToken(String tokenKey, boolean remove) throws
NullPointerException;
```

6.2.3. Configuring token services

The token services configuration includes specifying the token validity period. The token service is configured as a portal component (in the portal scope, as opposed to the root scope - more about that in Foundations chapter).

In the example below, *CookieTokenService* is a subclass of **AbstractTokenService**, so it has a property which specifies the validity period of the token.

The token service will initialize this validity property by looking for an *init-param* named **service.configuration**.

This property must have three values.

```
<component>
  <key>org.exoplatform.web.security.security.CookieTokenService</key>
  <type>org.exoplatform.web.security.security.CookieTokenService</type>
  <init-params>
    <values-param>
      <name>service.configuration</name>

      <value>jcr-token</value>           1
      <value>7</value>                   2
      <value>DAY</value>                 3
    </values-param>
  </init-params>
</component>
```

- 1 Service name
- 2 Amount of time
- 3 Unit of time

In this case, the service name is **jcr-token** and the token expiration time is one week.

GateIn 3.1 supports *four* time units:

1. *SECOND*

2. *MINUTE*

3. *HOURL*

4. *DAY*

6.3. PicketLink IDM integration

GateIn 3.1 uses the PicketLink IDM component to keep the necessary identity information, such as users, groups, memberships. While legacy interfaces are still used (`org.exoplatform.services.organization`) for identity management, there is a wrapper implementation that delegates to the PicketLink IDM framework.

This section does not provide information about PicketLink IDM and its configuration. Please refer to the appropriate project documentation (<http://jboss.org/picketlink/IDM.html>) for further information.



Note

It is important to fully understand the concepts behind this framework design before changing the default configuration.

The identity model represented in '`org.exoplatform.services.organization`' interfaces and the one used in **PicketLink IDM** have some major differences.

The `org.exoplatform.services.organization` interface stores and manages information of users, groups or memberships, user profiles, relationships and retrieval. The management of `org.exoplatform.services.organization` interface is divided into many layers, such as model object, data access object and authentication.

For example: **PicketLink IDM** provides greater abstraction. It is possible for groups in **IDM** framework to form memberships with many parents (which requires recursive ID translation), while the GateIn model allows only pure tree-like membership structures.

Additionally, the GateIn *membership* concept needs to be translated into the IDM *Role* concept. Therefore, the **PicketLink IDM** model is used in a limited way. All these translations are applied by the integration layer.

6.3.1. Configuration files

The main configuration file is **idm-configuration.xml**:

```
<configuration xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
                xsi:schemaLocation="http://www.exoplatform.org/xml/ns/kernel_1_0.xsd http://
www.exoplatform.org/xml/ns/kernel_1_0.xsd"
                xmlns="http://www.exoplatform.org/xml/ns/kernel_1_0.xsd">
```

```

<component>
  <key>org.exoplatform.services.organization.idm.PicketLinkIDMService</key>
  <type>org.exoplatform.services.organization.idm.PicketLinkIDMServiceImpl</type>
  <init-params>
    <value-param>
      <name>config</name>
      <value>war:/conf/organization/idm-config.xml</value>
    </value-param>
    <value-param>
      <name>portalRealm</name>
      <value>realm${container.name.suffix}</value>
    </value-param>
  </init-params>
</component>

<component>
  <key>org.exoplatform.services.organization.OrganizationService</key>
  <type>org.exoplatform.services.organization.idm.PicketLinkIDMOrganizationServiceImpl</type>
  <init-params>
    <object-param>
      <name>configuration</name>
      <object type="org.exoplatform.services.organization.idm.Config">
        <field name="useParentIdAsGroupType">
          <boolean>true</boolean>
        </field>

        <field name="forceMembershipOfMappedTypes">
          <boolean>true</boolean>
        </field>

        <field name="pathSeparator">
          <string>.</string>
        </field>

        <field name="rootGroupName">
          <string>GTN_ROOT_GROUP</string>
        </field>

        <field name="groupTypeMappings">
          <map type="java.util.HashMap">
            <entry>

```

```

    <key><string>.</string></key>
    <value><string>root_type</string></value>
  </entry>

  <!-- Sample mapping -->
  <!--
  <entry>
    <key><string>/platform/*</string></key>
    <value><string>platform_type</string></value>
  </entry>
  <entry>
    <key><string>/organization/*</string></key>
    <value><string>organization_type</string></value>
  </entry>
  -->

</map>
</field>

<field name="associationMembershipType">
  <string>member</string>
</field>

<field name="ignoreMappedMembershipType">
  <boolean>false</boolean>
</field>
</object>
</object-param>
</init-params>

</component>

</configuration>

```

- 1 The **org.exoplatform.services.organization.idm.PicketLinkIDMServiceImpl** service has the following options:

config

(value-param)

PicketLink IDM configuration file

hibernate.properties
(properties-param)

A list of hibernate properties used to create SessionFactory that will be injected to JBoss Identity IDM configuration registry.

hibernate.annotations
A list of annotated classes that will be added to Hibernate configuration.

hibernate.mappings
A list of .xml files that will be added to the hibernate configuration as mapping files.

jndiName
(value-param)

If the 'config' parameter is not provided, this parameter will be used to perform the JNDI lookup for IdentitySessionFactory.

portalRealm
(value-param)

The realm name that should be used to obtain the proper IdentitySession. The default is 'PortalRealm'.

2 The **org.exoplatform.services.organization.idm.PicketLinkIDMOrganizationServiceImpl** key is a main endpoint implementing **org.exoplatform.services.organization.OrganizationService** and is dependant on **org.exoplatform.services.organization.idm.PicketLinkIDMService**

org.exoplatform.services.organization.idm.PicketLinkIDMOrganizationServiceImpl service has the following options defined as fields of object-param of type **org.exoplatform.services.organization.idm.Config**:

defaultGroupType
The name of the PicketLink IDM GroupType that will be used to store groups. The default is 'GTN_GROUP_TYPE'.

rootGroupName
The name of the PicketLink IDM Group that will be used as a root parent. The default is 'GTN_ROOT_GROUP'

passwordAsAttribute
This parameter specifies if a password should be stored using the PicketLink IDM Credential object or as a plain attribute. The default value is set to false.

useParentIdAsGroupType

This parameter stores the parent ID path as a group type in PicketLink IDM for any IDs not mapped with a specific type in 'groupTypeMappings'. If this option is set to false, and no mappings are provided under 'groupTypeMappings', only one group with the given name can exist in the GateIn 3.1 group tree.

pathSeparator

When 'useParentIdAsGroupType' is set to true, this value will be used to replace all "/" characters in IDs. The "/" character is not allowed in the group type name in PicketLink IDM.

associationMembershipType

If this option is used, each Membership created with MembershipType that is equal to the value specified here, will be stored in PicketLink IDM as the simple Group-User association.

groupTypeMappings

This parameter maps groups added with GateIn 3.1 API as children of a given group ID, and stores them with a given group type name in PicketLink IDM.

If the parent ID ends with "/*", all child groups will have the mapped group type. Otherwise, only direct (first level) children will use this type.

This can be leveraged by LDAP if the LDAP DN is configured in PicketLink IDM to only store a specific group type. This will then store the given branch in the GateIn 3.1 group tree, while all other groups will remain in the database.

forceMembershipOfMappedTypes

Groups stored in PicketLink IDM with a type mapped in 'groupTypeMappings' will automatically be members under the mapped parent. The Group relationships linked by the PicketLink IDM group association will not be necessary.

This parameter can be set to false if all groups are added via GateIn 3.1 APIs. This may be useful with the LDAP configuration when being set to true, it will make every entry added to LDAP appear in GateIn 3.1. This, however, is not true for entries added via GateIn 3.1 management UI.

ignoreMappedMembershipType

If "associationMembershipType" option is used, and this option is set to true, Membership with MembershipType configured to be stored as PicketLink IDM association will not be stored as PicketLink IDM Role.

Additionally, **JBossIDMOrganizationServiceImpl** uses those defaults to perform identity management operations.

- GateIn 3.1 User interface properties fields are persisted in JBoss Identity IDM using those attributes names: firstName, lastName, email, createDate, lastLoginTime, organizationId, password (if password is configured to be stored as attribute).
- GateIn 3.1 Group interface properties fields are persisted in JBoss Identity IDM using those attributes names: label, description.
- GateIn 3.1 MembershipType interface properties fields are persisted in JBoss Identity IDM using those RoleType properties: description, owner, create_date, modified_date.


A sample **PicketLink IDM** configuration file is shown below. To understand all the options it contains, please refer to the PicketLink IDM Reference Guide.

```
<jboss-identity xmlns="urn:jboss:identity:idm:config:v1_0_beta"
  xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
  xsi:schemaLocation="urn:jboss:identity:idm:config:v1_0_alpha identity-config.xsd">
  <realms>
    <realm>
      <id>PortalRealm</id>
      <repository-id-ref>PortalRepository</repository-id-ref>
      <identity-type-mappings>
        <user-mapping>USER</user-mapping>
      </identity-type-mappings>
    </realm>
  </realms>
  <repositories>
    <repository>
      <id>PortalRepository</id>
      <class>org.jboss.identity.idm.impl.repository.WrapperIdentityStoreRepository</class>
      <external-config/>
      <default-identity-store-id>HibernateStore</default-identity-store-id>
      <default-attribute-store-id>HibernateStore</default-attribute-store-id>
    </repository>
  </repositories>
  <stores>
    <attribute-stores/>
    <identity-stores>
      <identity-store>
        <id>HibernateStore</id>
        <class>org.jboss.identity.idm.impl.store.hibernate.HibernateIdentityStoreImpl</class>
        <external-config/>
        <supported-relationship-types>
          <relationship-type>JBoss_IDENTITY_MEMBERSHIP</relationship-type>
        </supported-relationship-types>
      </identity-store>
    </identity-stores>
  </stores>
</jboss-identity>
```

```
<relationship-type>JBOSS_IDENTITY_ROLE</relationship-type>
</supported-relationship-types>
<supported-identity-object-types>
  <identity-object-type>
    <name>USER</name>
    <relationships/>
    <credentials>
      <credential-type>PASSWORD</credential-type>
    </credentials>
    <attributes/>
    <options/>
  </identity-object-type>
</supported-identity-object-types>
<options>
  <option>
    <name>hibernateSessionFactoryRegistryName</name>
    <value>hibernateSessionFactory</value>
  </option>
  <option>
    <name>allowNotDefinedIdentityObjectTypes</name>
    <value>true</value>
  </option>
  <option>
    <name>populateRelationshipTypes</name>
    <value>true</value>
  </option>
  <option>
    <name>populateIdentityObjectTypes</name>
    <value>true</value>
  </option>
  <option>
    <name>allowNotDefinedAttributes</name>
    <value>true</value>
  </option>
  <option>
    <name>isRealmAware</name>
    <value>true</value>
  </option>
</options>
</identity-store>
</identity-stores>
</stores>
</jboss-identity>
```

6.4. Organization API

The `exo.platform.services.organization` package has five main components: user, user profile, group, membership type and membership. There is an additional component that serves as an entry point into Organization API - `OrganizationService` component that provides the handling functionality for the five components.



The `User` component contains basic information about the user, such as username, password, first name, last name, and email. The `User Profile` component contains extra information about a user, such as user's personal information, and business information. You can also add additional information about a user if your application requires it. The `Group` component contains a group graph. The `Membership Type` component contains a list of predefined membership types. Finally, the `Membership` component connects a `User`, a `Group` and a `Membership Type`.

A user can have one or more memberships within a group, for example: the user A can have two memberships: 'member' and 'admin' in the group /user. A user belongs to a group if he has at least one membership in that group.

Exposing the Organization API to developers who have access to the handler objects provided by the OrganizationService component. These handler objects are used to manage each of the five components, including UserHandler, UserProfileHandler, GroupHandler, MembershipTypeHandler, and MembershipHandler.

The five central API components are really designed like persistent entities, and handlers are really specified like data access objects (DAO).

Organization API simply describes a contract, meaning it is not a concrete implementation. The described components are interfaces, allowing different concrete implementations. Practically, it means that you can replace the existing implementation with a different one.

6.5. Accessing User Profile

The following code retrieves the details for a logged-in user:

```
// Alternative context: WebuiRequestContext context =
WebuiRequestContext.getCurrentInstance() ;
PortalRequestContext context = PortalRequestContext.getCurrentInstance() ;
// Get the id of the user logged
String userId = context.getRemoteUser();
// Request the information from OrganizationService:
OrganizationService orgService = getApplicationComponent(OrganizationService.class) ;
if (userId != null)
{
    User user = orgService.getUserHandler().findUserByName(userId) ;
    if (user != null)
    {
        String firstName = user.getFirstName();
        String lastName = user.getLastName();
        String email = user.getEmail();
    }
}
```

Below are two alternatives for retrieving the Organization Service:

```
OrganizationService service = (OrganizationService)

ExoContainerContext.getCurrentContainer().getComponentInstanceOfType(OrganizationService.class);
```

```
OrganizationService service = (OrganizationService)
PortalContainer.getInstance().getComponentInstanceOfType(OrganizationService.class);
```

6.6. Single-Sign-On (SSO)

6.6.1. Overview

GateIn 3.1 provides some forms of Single-Sign-On (SSO) as an integration and aggregation platform.

When logging into the portal, users gain access to many systems through portlets using a single identity. In many cases, the portal infrastructure must be integrated with other SSO enabled systems. There are many different Identity Management solutions available. In most cases, each SSO framework provides a unique way to plug into a Java EE application.

6.6.1.1. Prerequisites

In this tutorial, the SSO server is installed in a Tomcat installation. Tomcat can be obtained from <http://tomcat.apache.org>.

All the packages required for setup can be found in a zip file located at: <https://repository.jboss.org/nexus/content/groups/public/org/gatein/sso/sso-packaging/1.0.1-GA/sso-packaging-1.0.1-GA.zip>. In this document, \$GATEIN_SSO_HOME is called as the directory where the file is extracted.

It is recommended that you should not run any portal extensions that could override the data when manipulating the `gatein.ear` file directly.

Remove `$JBOSS_HOME/server/default/deploy/gatein-sample-extension.ear` and `$JBOSS_HOME/server/default/deploy/gatein-sample-portal.ear` which are packaged with GateIn 3.1 by default.

6.6.2. Central Authentication Service (CAS)

This Single-Sign-On plugin enables the seamless integration between GateIn 3.1 and the CAS Single-Sign-On Framework. Details about CAS can be found [here](http://www.ja-sig.org/products/cas/) [http://www.ja-sig.org/products/cas/].

The integration consists of two steps: installing/configuring a CAS server and setting up the portal to use the CAS server.

6.6.2.1. CAS server

First, set up the server to authenticate against the portal login module. In this example, the CAS server is installed on Tomcat.

6.6.2.1.1. Obtaining CAS

CAS can be downloaded from <http://www.jasig.org/cas/download>.

Extract the downloaded file into a suitable location. This location will be referred to as `$CAS_HOME` in the following example.

6.6.2.1.2. Modifying the CAS server

To configure the web archive as desired, the simplest way is to make the necessary changes directly in the CAS codebase.



Note

To complete these instructions, and perform the final build step, you will need the Apache Maven 2. You can get it [here](http://maven.apache.org/download.html) [http://maven.apache.org/download.html].

First, change the default authentication handler with the one provided by GateIn 3.1.

The CAS Server Plugin makes secure authentication callbacks to a RESTful service installed on the remote GateIn 3.1 server to authenticate a user.

In order for the plugin to function correctly, it needs to be properly configured to connect to this service. This configuration is done via the `cas.war/WEB-INF/deployerConfigContext.xml` file.

1. Open `CAS_HOME/cas-server-webapp/src/main/webapp/WEB-INF/deployerConfigContext.xml`
2. Replace:

```
<!--
  | Whereas CredentialsToPrincipalResolvers identify who it is some Credentials might
  | authenticate,
  | AuthenticationHandlers actually authenticate credentials. Here e declare the
  | AuthenticationHandlers that
  | authenticate the Principals that the CredentialsToPrincipalResolvers identified. CAS will
  | try these handlers in turn
  | until it finds one that both supports the Credentials presented and succeeds in
  | authenticating.
  +-->
<property name="authenticationHandlers">
  <list>
    <!--
      | This is the authentication handler that authenticates services by means of callback via
      | SSL, thereby validating
      | a server side SSL certificate.
```

```

+-->
<bean
class="org.jasig.cas.authentication.handler.support.HttpBasedServiceCredentialsAuthenticationHandler"
p:httpClient-ref="httpClient" />
<!--
| This is the authentication handler declaration that every CAS deployer will need to
change before deploying CAS
| into production. The default SimpleTestUsernamePasswordAuthenticationHandler
authenticates UsernamePasswordCredentials
| where the username equals the password. You will need to replace this with an
AuthenticationHandler that implements your
| local authentication strategy. You might accomplish this by coding a new such handler
and declaring
| edu.someschool.its.cas.MySpecialHandler here, or you might use one of the handlers
provided in the adaptors modules.
+-->
<bean

/>
</list>
</property>

```

With the following (Make sure to set the host, port and context with the values corresponding to your portal). Also available in `GATEIN_SSO_HOME/cas/plugin/WEB-INF/deployerConfigContext.xml`.

```

<!--
| Whereas CredentialsToPrincipalResolvers identify who it is some Credentials might
authenticate,
| AuthenticationHandlers actually authenticate credentials. Here we declare the
AuthenticationHandlers that
| authenticate the Principals that the CredentialsToPrincipalResolvers identified. CAS will
try these handlers in turn
| until it finds one that both supports the Credentials presented and succeeds in
authenticating.
+-->
<property name="authenticationHandlers">
<list>
<!--
| This is the authentication handler that authenticates services by means of callback via
SSL, thereby validating
| a server side SSL certificate.

```

```

+-->
<bean
class="org.jasig.cas.authentication.handler.support.HttpBasedServiceCredentialsAuthenticationHandler"
  p:httpClient-ref="httpClient" />
<!--
  | This is the authentication handler declaration that every CAS deployer will need to
  | change before deploying CAS
  | into production. The default SimpleTestUsernamePasswordAuthenticationHandler
  | authenticates UsernamePasswordCredentials
  | where the username equals the password. You will need to replace this with an
  | AuthenticationHandler that implements your
  | local authentication strategy. You might accomplish this by coding a new such handler
  | and declaring
  | edu.someschool.its.cas.MySpecialHandler here, or you might use one of the handlers
  | provided in the adaptors modules.
+-->
<!-- Integrates with the GateIn Authentication Service to perform authentication -->
<!--
  | Note: Modify the Plugin Configuration based on the actual information of a GateIn
  | instance.
  | The instance can be anywhere on the internet...Not necessarily on localhost where
  | CAS is running
+-->
<bean class="org.gatein.sso.cas.plugin.AuthenticationPlugin">
  <property name="gateInHost"><value>localhost</value></property>
  <property name="gateInPort"><value>8080</value></property>
  <property name="gateInContext"><value>portal</value></property>
</bean>
</list>
</property>

```

3. Copy `GATEIN_SSO_HOME/cas/plugin/WEB-INF/lib/sso-cas-plugin-<VERSION>.jar` and `GATEIN_SSO_HOME/cas/plugin/WEB-INF/lib/commons-httpclient-<VERSION>.jar` into the `CAS_HOME/cas-server-webapp/src/main/webapp/WEB-INF/lib` created directory.
4. Get an installation of Tomcat and extract it into a suitable location (which will be called `TOMCAT_HOME` for these instructions).

Change the default port to avoid a conflict with the default GateIn 3.1 (for testing purposes). Edit `TOMCAT_HOME/conf/server.xml` and replace the 8080 port with 8888.



Note

If GateIn 3.1 is running on the same machine as Tomcat, other ports need to be changed in addition to 8080 to avoid port conflicts. They can be changed to any free port. For example, you can change admin port from 8005 to 8805, and AJP port from 8009 to 8809.

5. Go to `CAS_HOME/cas-server-webapp` and execute the command:

```
mvn install
```

6. Copy `CAS_HOME/cas-server-webapp/target/cas.war` into `TOMCAT_HOME/webapps`.

Tomcat should start and be accessible at <http://localhost:8888/cas>. At this stage, the login will not be available.

6.6.2.2. Set up the CAS client

1. Copy all libraries from `GATEIN_SSO_HOME/cas/gatein.ear/lib` into `JBoss_HOME/server/default/deploy/gatein.ear/lib` (Or in Tomcat, into `$GATEIN_HOME/lib`)
2. • In JBoss AS, edit `gatein.ear/META-INF/gatein-jboss-beans.xml` and uncomment on this section:

```
<authentication>
```

```
<login-module code="org.gatein.sso.agent.login.SSOLoginModule" flag="required">
</login-module>
    <login-module    code="org.exoplatform.services.security.j2ee.JbossLoginModule"
flag="required">
    <module-option name="portalContainerName">portal</module-option>
    <module-option name="realmName">gatein-domain</module-option>
    </login-module>
</authentication>
```

- In Tomcat, edit `GATEIN_HOME/conf/jaas.conf`, uncomment on this section and comment other parts:

```
org.gatein.sso.agent.login.SSOLoginModule required;
org.exoplatform.services.security.j2ee.TomcatLoginModule required
portalContainerName=portal
realmName=gatein-domain;
```

3. The installation can be tested at this point:

1. Start (or restart) GateIn 3.1, and (assuming the CAS server on Tomcat is running) direct your browser to <http://localhost:8888/cas>.
2. Login with the username `root` and the password `gtin` (or any account created through the portal).

6.6.2.3. Redirect to CAS

To utilize the Central Authentication Service, GateIn 3.1 needs to redirect all user authentication to the CAS server.

Information about where the CAS is hosted must be properly configured within the GateIn 3.1 instance. The required configuration is done by modifying three files:

- In the `gatein.ear/web.war/groovy/groovy/webui/component/UIBannerPortlet.gtmpl` file, modify the 'Sign In' link as follows:

```
<!--
<a class="Login" onclick="$signInAction"><%= _ctx.appRes("UILoginForm.label.Signin") %></
a>
-->
```

```
<a class="Login" href="/portal/sso"><%= _ctx.appRes("UILoginForm.label.Signin")%></a>
```

- In the `gatein.ear/web.war/groovy/portal/webui/component/UILogoPortlet.gtmpl` file, modify the 'Sign In' link as follows:

```
<!--  
<a onclick="$signInAction"><%= _ctx.appRes("UILogoPortlet.action.signin")%></a>  
-->  
<a href="/portal/sso"><%= _ctx.appRes("UILogoPortlet.action.signin")%></a>
```

- Replace the entire contents of `gatein.ear/02portal.war/login/jsp/login.jsp` with:

```
<html>  
<head>  
  <script type="text/javascript">  
    window.location = '/portal/sso';  
  </script>  
</head>  
<body>  
</body>  
</html>
```

- Add the following filters at the top of the filter chain in `gatein.ear/02portal.war/WEB-INF/web.xml`:

```
<filter>  
  <filter-name>LoginRedirectFilter</filter-name>  
  <filter-class>org.gatein.sso.agent.filter.LoginRedirectFilter</filter-class>  
  <init-param>  
    <!-- This should point to your SSO authentication server -->  
  
    <param-name>LOGIN_URL</param-name>  
  <!--  
    If casRenewTicket param value of InitiateLoginServlet is: not specified or false
```



```

-->
    <param-value>http://localhost:8888/cas/login?service=http://localhost:8080/portal/private/
classic</param-value>
    <!--
        If casRenewTicket param value of InitiateLoginServlet is : true
    -->
    <!--
    <param-value>http://localhost:8888/cas/login?service=http://localhost:8080/portal/private
    /classic&renew=true</param-value>
    -->
</init-param>
</filter>
<filter>
    <filter-name>CASLogoutFilter</filter-name>
    <filter-class>org.gatein.sso.agent.filter.CASLogoutFilter</filter-class>
    <init-param>
        <!-- This should point to your JOSSO authentication server -->

        <param-name>LOGOUT_URL</param-name>
        <param-value>http://localhost:8888/cas/logout</param-value>

    </init-param>
</filter>

<!-- Mapping the filters at the very top of the filter chain -->
<filter-mapping>
    <filter-name>LoginRedirectFilter</filter-name>
    <url-pattern>/*</url-pattern>
</filter-mapping>
<filter-mapping>
    <filter-name>CASLogoutFilter</filter-name>
    <url-pattern>/*</url-pattern>
</filter-mapping>

```

- Replace the `InitiateLoginServlet` declaration in `gatein.ear/02portal.war/WEB-INF/web.xml` with:

```

<servlet>
    <servlet-name>InitiateLoginServlet</servlet-name>
    <servlet-class>org.gatein.sso.agent.GenericSSOAgent</servlet-class>
    <init-param>
        <param-name>ssoServerUrl</param-name>

```

```
<param-value>http://localhost:8888/cas</param-value>
</init-param>
<init-param>
  <param-name>casRenewTicket</param-name>
  <param-value>false</param-value>
</init-param>
</servlet>
```

Once these changes have been made, all links to the user authentication pages will redirect to the CAS centralized authentication form.

6.6.3. JOSSO

This Single-Sign-On plugin enables the seamless integration between GateIn 3.1 and the JOSSO Single-Sign-On Framework. Details about JOSSO can be found [here](http://www.josso.org) [http://www.josso.org].

Setting up this integration consists of two steps: installing/configuring a JOSSO server, and setting up the portal to use the JOSSO server.

6.6.3.1. JOSSO server

This section describes how to set up the JOSSO server to authenticate against the GateIn 3.1 login module.

In this example, the JOSSO server will be installed on Tomcat.

6.6.3.1.1. Obtaining JOSSO

JOSSO can be downloaded from <http://sourceforge.net/projects/josso/files/>. Use the package that embeds Apache Tomcat.

Once downloaded, extract the package into what will be called `JOSSO_HOME` in this example.



Warning

The steps described later are only correct in case of JOSSO v.1.8.1.

6.6.3.1.2. Modifying the JOSSO server

1. Copy the files from `GATEIN_SSO_HOME/josso/plugin` into the Tomcat directory (`JOSSO_HOME`).

This action should replace or add the following files to the `JOSSO_HOME/webapps/josso/WEB-INF/lib` directory:

- JOSSO_HOME/lib/josso-gateway-config.xml
- JOSSO_HOME/lib/josso-gateway-gatein-stores.xml

and

- JOSSO_HOME/webapps/josso/WEB-INF/classes/gatein.properties

2. Edit TOMCAT_HOME/conf/server.xml and replace the 8080 port with 8888 to change the default Tomcat port and avoid a conflict with the default GateIn 3.1 port (for testing purposes).



Port Conflicts

If GateIn 3.1 is running on the same machine as Tomcat, other ports need to be changed in addition to 8080 to avoid port conflicts. They can be changed to any free port. For example, you can change the admin port from 8005 to 8805, and AJP port from 8009 to 8809.

3. Tomcat should now start and allow access to <http://localhost:8888/josso/signon/login.do>; but at this stage, login will not be available.



User Login

Please sign in. Enter your username and password.

Username:

Password:

☐ Remember Me:

Login

[Forgot your Username or Password?](#)

? Help

Need help ? JOSSO is an open source JEE / J2EE and Spring-based SSO infrastructure aimed to provide a solution for centralized, platform neutral, user authentication and authorization. For more information visit <http://www.josso.org>.

6.6.3.2. Set up the JOSSO client

1. Copy the library files from GATEIN_SSO_HOME/josso/gatein.ear/lib into gatein.ear/lib (or into GATEIN_HOME/lib if GateIn 3.1 is running in Tomcat)

2. Copy the file `GATEIN_SSO_HOME/josso/gatein.ear/portal.war/WEB-INF/classes/josso-agent-config.xml` into `gatein.ear/02portal.war/WEB-INF/classes` (or into `GATEIN_HOME/webapps/portal.war/WEB-INF/classes`, or `GATEIN_HOME/conf` if GateIn 3.1 is running in Tomcat)
3.
 - In JBoss AS, edit `gatein.ear/META-INF/gatein-jboss-beans.xml` and uncomment on this section:

```
<authentication>
  <login-module code="org.gatein.sso.agent.login.SSOLoginModule" flag="required">
  </login-module>
    <login-module code="org.exoplatform.services.security.j2ee.JbossLoginModule"
flag="required">
    <module-option name="portalContainerName">portal</module-option>
    <module-option name="realmName">gatein-domain</module-option>
  </login-module>
</authentication>
```

- In Tomcat, edit `GATEIN_HOME/conf/jaas.conf`, uncomment on this section and comment other parts:

```
org.gatein.sso.agent.login.SSOLoginModule required;
org.exoplatform.services.security.j2ee.TomcatLoginModule requiredtm
portalContainerName=portal
realmName=gatein-domain;
```

4. The installation can be tested at this point.
 1. Start (or restart) GateIn 3.1, and (assuming the JOSSO server on Tomcat is running) direct your browser to <http://localhost:8888/josso/signon/login.do>.
 2. Login with the username `root` and the password `gtm` or any account created through the portal.

6.6.3.3. Set up the portal to redirect to JOSSO

The next part of the process redirects all user authentication to the JOSSO server.

Information about where the JOSSO server is hosted must be properly configured within the GateIn 3.1 instance. The required configuration is done by modifying four files:

- In the `gatein.ear/web.war/groovy/groovy/webui/component/UIBannerPortlet.gtml` file, modify the 'Sign In' link as follows:

```
<!--
<a class="Login" onclick="$signInAction"><%= _ctx.appRes("UILoginForm.label.Signin")%></a>
-->
<a class="Login" href="/portal/sso"><%= _ctx.appRes("UILoginForm.label.Signin")%></a>
```

- In the `gatein.ear/web.war/groovy/portal/webui/component/UILogoPortlet.gtmpl` file, modify the 'Sign In' link as follows:

```
<!--
<a onclick="$signInAction"><%= _ctx.appRes("UILogoPortlet.action.signin")%></a>
-->
<a href="/portal/sso"><%= _ctx.appRes("UILogoPortlet.action.signin")%></a>
```

- Replace the entire contents of `gatein.ear/02portal.war/login/jsp/login.jsp` with:

```
<html>
<head>
  <script type="text/javascript">
    window.location = '/portal/sso';
  </script>
</head>
<body>
</body>
</html>
```

- Add the following filters at the top of the filter chain in `gatein.ear/02portal.war/WEB-INF/web.xml`:

```
<filter>
```

```
<filter-name>LoginRedirectFilter</filter-name>
<filter-class>org.gatein.sso.agent.filter.LoginRedirectFilter</filter-class>
<init-param>
<!-- This should point to your SSO authentication server -->

<param-name>LOGIN_URL</param-name>
<param-value>http://localhost:8888/josso/signon/login.do?josso_back_to=http://localhost:8080/
portal
/private/classic</param-value>
</init-param>
</filter>
<filter>
<filter-name>JOSSOLogoutFilter</filter-name>
<filter-class>org.gatein.sso.agent.filter.JOSSOLogoutFilter</filter-class>

<init-param>
<!-- This should point to your JOSSO authentication server -->

<param-name>LOGOUT_URL</param-name>

<param-value>http://localhost:8888/josso/signon/logout.do</param-value>

</init-param>
</filter>

<!-- filters should be placed at the very top of the filter chain -->
<filter-mapping>
<filter-name>LoginRedirectFilter</filter-name>
<url-pattern>/*</url-pattern>
</filter-mapping>
<filter-mapping>
<filter-name>JOSSOLogoutFilter</filter-name>
<url-pattern>/*</url-pattern>
</filter-mapping>
```

- Replace the `InitiateLoginServlet` declaration in `gatein.ear/02portal.war/WEB-INF/web.xml` with:

```
<servlet>
<servlet-name>InitiateLoginServlet</servlet-name>
<servlet-class>org.gatein.sso.agent.GenericSSOAgent</servlet-class>
<init-param>
```

```
<param-name>ssoServerUrl</param-name>
<param-value>http://localhost:8888/josso/signon/login.do</param-value>
</init-param>
</servlet>
```

- Remove the `PortalLoginController` servlet declaration and mapping in `gatein.ear/02portal.war/WEB-INF/web.xml`

From now on, all links redirecting to the user authentication pages will redirect to the JOSSO centralized authentication form.

6.6.4. OpenSSO - The Open Web SSO project

This Single-Sign-On plugin enables the seamless integration between GateIn 3.1 and the OpenSSO Single Sign On Framework. Details about OpenSSO can be found [here](https://opensso.dev.java.net/) [https://opensso.dev.java.net/].

Setting up this integration consists of two steps: installing/configuring an OpenSSO server, and setting up the portal to use the OpenSSO server.

6.6.4.1. OpenSSO server

This section details the setup of OpenSSO server to authenticate against the GateIn 3.1 login module.

In this example, the OpenSSO server will be installed on Tomcat.

6.6.4.1.1. Obtaining OpenSSO

OpenSSO can be downloaded from http://download.oracle.com/otn/nt/middleware/11g/oracle_opensso_80U2.zip.

Once downloaded, extract the package into a suitable location. This location will be referred to as `OPENSZO_HOME` in this example.

6.6.4.1.2. Modifying the OpenSSO server

To configure the web server as desired, it is simpler to directly modify the sources.

The first step is to add the GateIn 3.1 Authentication Plugin:

The plugin makes secure authentication callbacks to a RESTful service installed on the remote GateIn 3.1 server to authenticate a user.

In order for the plugin to function correctly, it needs to be properly configured to connect to this service. This configuration is done via the `opensso.war/config/auth/default/AuthenticationPlugin.xml` file.

1. Obtain a copy of Tomcat and extract it into a suitable location (this location will be referred to as `TOMCAT_HOME` in this example).
2. Change the default port to avoid a conflict with the default GateIn 3.1 port (for testing purposes) by editing `TOMCAT_HOME/conf/server.xml` and replacing the 8080 port with 8888.



Note

If GateIn 3.1 is running on the same machine as Tomcat, other ports need to be changed in addition to 8080 to avoid port conflicts. They can be changed to any free port. For example, you can change the admin port from 8005 to 8805, and AJP port from 8009 to 8809.

3. Ensure the `TOMCAT_HOME/webapps/opensso/config/auth/default/AuthenticationPlugin.xml` file looks like this:

```
<?xml version='1.0' encoding="UTF-8"?>


<!DOCTYPE ModuleProperties PUBLIC "-//iPlanet//Authentication Module Properties XML
Interface 1.0 DTD//EN"
    "jar://com/sun/identity/authentication/Auth_Module_Properties.dtd">

<ModuleProperties moduleName="AuthenticationPlugin" version="1.0" >
  <Callbacks length="2" order="1" timeout="60"
    header="GateIn OpenSSO Login" >
    <NameCallback>
      <Prompt>
        Username
      </Prompt>
    </NameCallback>
    <PasswordCallback echoPassword="false" >
      <Prompt>
        Password
      </Prompt>
    </PasswordCallback>
  </Callbacks>
</ModuleProperties>
```

4. Copy `GATEIN_SSO_HOME/opensso/plugin/WEB-INF/lib/sso-opensso-plugin-
<VERSION>.jar`, `GATEIN_SSO_HOME/opensso/plugin/WEB-INF/lib/commons-
httpclient-<VERSION>.jar`, and `GATEIN_SSO_HOME/opensso/plugin/WEB-INF/lib/`

commons-logging-<VERSION>.jar into the Tomcat directory at TOMCAT_HOME/webapps/opensso/WEB-INF/lib.

5. Copy GATEIN_SSO_HOME/opensso/plugin/WEB-INF/classes/gatein.properties into TOMCAT_HOME/webapps/opensso/WEB-INF/classes.
6. Tomcat should start and be able to access <http://localhost:8888/opensso/UI/Login?realm=gatein>. Login will not be available at this point.



Configure the "gatein" realm:

1. Direct your browser to <http://localhost:8888/opensso>.
2. Create the default configuration.
3. Login as an admin and then go to the "Configuration" tab -> "Authentication" -> "Core" link -> add a new value and fill in the class name "org.gatein.sso.opensso.plugin.AuthenticationPlugin". This step is really important. If not, AuthenticationPlugin is not available among other the OpenSSO authentication modules.
4. Go to the "Access control" tab and create the new realm called "gatein".
5. Go to the "gatein" realm and click the "Authentication" tab. At the bottom of the "Authentication chaining" section, click "IdapService". Here, change the selection from "Datastore", which is the default module in the authentication chain, to "AuthenticationPlugin". This enables the

authentication of "gatein" realm by using the GateIn REST service instead of the OpenSSO LDAP server.

6. Go to "Advanced properties" and change UserProfile from "Required" to "Dynamic". This step is needed because GateIn 3.1 users are not in the OpenSSO Datastore (LDAP server), so their profiles can not be obtained if "Required" is active. By using "Dynamic", all new users are automatically created in the OpenSSO datastore after successful authentication.
7. Increase the user privileges to allow the REST access. Go to "Access control" -> Top level realm -> "Privileges" tab -> All authenticated users, and check the last two checkboxes:
 - Read and write access only for policy properties.
 - Read and write access to all realm and policy properties.
8. Do the same for the "gatein" realm.

Also, instead of configuring OpenSSO manually as above, you can refer to the available configuration files [here](https://repository.jboss.org/nexus/content/groups/public/org/gatein/sso/sso-packaging/1.0.1-GA/sso-packaging-1.0.1-GA.zip) [https://repository.jboss.org/nexus/content/groups/public/org/gatein/sso/sso-packaging/1.0.1-GA/sso-packaging-1.0.1-GA.zip].

6.6.4.2. Set up the OpenSSO client.

1. Copy all libraries from `GATEIN_SSO_HOME/opensso/gatein.ear/lib` into `JBOSS_HOME/server/default/deploy/gatein.ear/lib` (Or, in Tomcat, into `GATEIN_HOME/lib`)
2. • In JBoss AS, edit `gatein.ear/META-INF/gatein-jboss-beans.xml` and uncomment on this section

```
<authentication>
  <login-module code="org.gatein.sso.agent.login.SSOLoginModule" flag="required">
  </login-module>
    <login-module code="org.exoplatform.services.security.j2ee.JbossLoginModule"
    flag="required">
      <module-option name="portalContainerName">portal</module-option>
      <module-option name="realmName">gatein-domain</module-option>
    </login-module>
  </authentication>
```

- If you are running GateIn 3.1 in Tomcat, edit `$GATEIN_HOME/conf/jaas.conf`, uncomment on this section and comment other parts:

```
org.gatein.sso.agent.login.SSOLoginModule required;
org.exoplatform.services.security.j2ee.TomcatLoginModule required
```

```
portalContainerName=portal
realmName=gatein-domain;
```

At this point, the installation can be tested:

1. Access GateIn 3.1 by going to <http://localhost:8888/opensso/UI/Login?realm=gatein> (assuming that the OpenSSO server using Tomcat is still running).
2. Login with the username `root` and the password `gtm` or any account created through the portal.

6.6.4.3. Set up the portal to redirect to OpenSSO

The next part of the process is to redirect all user authentication to the OpenSSO server.

Information about where the OpenSSO server is hosted must be properly configured within the Enterprise Portal Platform instance. The required configuration is done by modifying three files:

- In the `gatein.ear/web.war/groovy/groovy/webui/component/UIBannerPortlet.gtmpl` file, modify the 'Sign In' link as follows:

```
<!--
<a class="Login" onclick="$signInAction"><%=_ctx.appRes("UILoginForm.label.Signin")%></a>
-->
<a class="Login" href="/portal/sso"><%=_ctx.appRes("UILoginForm.label.Signin")%></a>
```

- In the `gatein.ear/web.war/groovy/portal/webui/component/UILogoPortlet.gtmpl` file, modify the 'Sign In' link as follows:

```
<!--
<a onclick="$signInAction"><%=_ctx.appRes("UILogoPortlet.action.signin")%></a>
-->
<a href="/portal/sso"><%=_ctx.appRes("UILogoPortlet.action.signin")%></a>
```

- Replace the entire contents of `gatein.ear/02portal.war/login/jsp/login.jsp` with:

```
<html>
<head>
  <script type="text/javascript">
    window.location = '/portal/sso';
  </script>
</head>
<body>
</body>
</html>
```

- Add the following filters at the top of the filter chain in `gatein.ear/02portal.war/WEB-INF/web.xml`:

```
<filter>
  <filter-name>LoginRedirectFilter</filter-name>
  <filter-class>org.gatein.sso.agent.filter.LoginRedirectFilter</filter-class>
  <init-param>
    <!-- This should point to your SSO authentication server -->

    <param-name>LOGIN_URL</param-name>
    <param-value>http://localhost:8888/opensso/UI/Login?realm=gatein&goto=http://
localhost:8080
/portal/private/classic</param-value>
  </init-param>
</filter>
<filter>
  <filter-name>OpenSSOLogoutFilter</filter-name>

  <filter-class>org.gatein.sso.agent.filter.OpenSSOLogoutFilter</filter-class>

  <init-param>
    <!-- This should point to your OpenSSO authentication server -->

    <param-name>LOGOUT_URL</param-name>

    <param-value>http://localhost:8888/opensso/UI/Logout</param-value>

  </init-param>
</filter>
```

```

<!-- place the filters at the top of the filter chain -->
<filter-mapping>
  <filter-name>LoginRedirectFilter</filter-name>
  <url-pattern>/*</url-pattern>
</filter-mapping>
<filter-mapping>
  <filter-name>OpenSSOLogoutFilter</filter-name>
  <url-pattern>/*</url-pattern>
</filter-mapping>

```

- Replace the `InitiateLoginServlet` declaration in `gatein.ear/02portal.war/WEB-INF/web.xml` with:

```

<servlet>
  <servlet-name>InitiateLoginServlet</servlet-name>
  <servlet-class>org.gatein.sso.agent.GenericSSOAgent</servlet-class>
  <init-param>
    <param-name>ssoServerUrl</param-name>
    <param-value>http://localhost:8888/opensso</param-value>
  </init-param>
  <init-param>
    <param-name>ssoCookieName</param-name>
    <param-value>iPlanetDirectoryPro</param-value>
  </init-param>
</servlet>

```

From now on, all links redirecting to the user authentication pages will redirect to the OpenSSO centralized authentication form.

6.6.5. SPNEGO

SPNEGO (Simple and Protected GSSAPI Negotiation Mechanism) is used to authenticate transparently through the web browser after the user has been authenticated when logging in.

See the following typical usecase:

1. The user logs into the desktop, such as a Windows machine.
2. The desktop login is governed by the Active Directory domain.
3. Next, the user opens the browser (IE/Firefox) to access a web application (that uses JBoss Negotiation) hosted on JBoss EPP.
4. The Browser transfers the desktop sign-on information to the web application.

5. JBoss EAP/AS uses the background GSS messages with the Active Directory (or any Kerberos server) to validate the user.
6. The User has a seamless SSO into the web application.

6.6.5.1. SPNEGO Server Configuration



Note

Information stated here only describes basic steps for you to configure the SPNEGO server. If you are already familiar with SPNEGO, jump to the [Section 6.6.5.2, "GateIn 3.1 Configuration"](#) to see how to integrate SPNEGO with GateIn.

1. Correct the setup of network on the machine. For example, if you are using the "server.local.network" domain as your machine where Kerberos and GateIn 3.1 are located, add the line containing the machine's IP address to the **/etc/host** file.

```
192.168.1.88 server.local.network
```



Note

It is not recommended you use loopback addresses.

2. Install Kerberos with these packages: `krb5-admin-server`, `krb5-kdc`, `krb5-config`, `krb5-user`, `krb5-clients`, and `krb5-rsh-server`.
3. Edit the Kerberos configuration file at **/etc/krb5.config**, including:

- Uncomment on these lines:

```
default_tgs_enctypes = des3-hmac-sha1
default_tkt_enctypes = des3-hmac-sha1
permitted_enctypes = des3-hmac-sha1
```

- Add **local.network** as a default realm and it is also added to the list of realms and remove the remains of realms. The content looks like:

```
[libdefaults]
    default_realm = LOCAL.NETWORK

# The following krb5.conf variables are only for MIT Kerberos.
    krb4_config = /etc/krb.conf
    krb4_realms = /etc/krb.realms
    kdc_timesync = 1
    ccache_type = 4
    forwardable = true
    proxiable = true

# The following encryption type specification will be used by MIT Kerberos
# if uncommented. In general, the defaults in the MIT Kerberos code are
# correct and overriding these specifications only serves to disable new
# encryption types as they are added, creating interoperability problems.
#
# This is the only time when you might need to uncomment these lines and change
# the enctype is if you have local software that will break on ticket
# caches containing ticket encryption types it doesn't know about (such as
# old versions of Sun Java).

    default_tgs_enctypes = des3-hmac-sha1
    default_tkt_enctypes = des3-hmac-sha1
    permitted_enctypes = des3-hmac-sha1

# The following libdefaults parameters are only for Heimdal Kerberos.
    v4_instance_resolve = false
    v4_name_convert = {
        host = {
            rcmd = host
            ftp = ftp
        }
        plain = {
            something = something-else
        }
    }
    fcc-mit-ticketflags = true

[realms]
    LOCAL.NETWORK = {
        kdc = server.local.network
        admin_server = server.local.network
```

```
}

[domain_realm]
.local.network = LOCAL.NETWORK
local.network = LOCAL.NETWORK

[login]
krb4_convert = true
krb4_get_tickets = false
```

4. Edit the KDC configuraton file at **/etc/krb5kdc/kdc.conf** that looks like.

```
[kdcdefaults]
kdc_ports = 750,88

[realms]
LOCAL.NETWORK = {
    database_name = /home/gatein/krb5kdc/principal
    admin_keytab = FILE:/home/gatein/krb5kdc/kadm5.keytab
    acl_file = /home/gatein/krb5kdc/kadm5.acl
    key_stash_file = /home/gatein/krb5kdc/stash
    kdc_ports = 750,88
    max_life = 10h 0m 0s
    max_renewable_life = 7d 0h 0m 0s
    master_key_type = des3-hmac-sha1
    supported_encetypes = aes256-cts:normal arcfour-hmac:normal des3-hmac-sha1:normal
des-cbc-crc:normal des:normal des:v4 des:norealm des:onlyrealm des:afs3
    default_principal_flags = +preauth
}

[logging]
kdc = FILE:/home/gatein/krb5logs/kdc.log
admin_server = FILE:/home/gatein/krb5logs/kadmin.log
```

- Create krb5kdc and krb5logs directory for Kerberos database as shown in the configuration file above.
- Next, create a KDC database using the following command.


```
sudo krb5_newrealm
```

- Start the KDC and Kerberos admin servers using these commands:

```
sudo /etc/init.d/krb5-kdc restart  
sudo /etc/init.d/krb-admin-server restart
```

5. Add Principals and create Keys.

- Start an interactive 'kadmin' session and create the necessary Principals.

```
sudo kadmin.local
```

- Add the GateIn 3.1 machine and keytab file that need to be authenticated.

```
addprinc -randkey HTTP/server.local.network@LOCAL.NETWORK  
ktadd HTTP/server.local.network@LOCAL.NETWORK
```

- Add the default GateIn 3.1 user accounts and enter the password for each created user that will be authenticated.

```
addprinc john  
addprinc demo  
addprinc root
```

6. Test your changed setup by using the command.

```
kinit -A demo
```

- If the setup works well, you are required to enter the password created for this user in Step 5.

- If you want to login with another user, use this command.

```
kdestroy
```

6.6.5.2. GateIn 3.1 Configuration

GateIn 3.1 uses JBoss Negotiation to enable SPNEGO-based desktop SSO for the portal. Here are the steps to integrate SPNEGO with GateIn 3.1.

1. Activate the Host authentication under the **conf/login-config.xml** file adding the following host login module:

```
<application-policy>

<authentication>

<login-module>

<module-option>true</module-option>

<module-option>true</module-option>

<module-option>HTTP/server.local.network@LOCAL.NETWORK</module-option>

<module-option>/etc/krb5.keytab</module-option>

<module-option>true</module-option>

<module-option>true</module-option>

</login-module>

</authentication>

</application-policy>
```

The 'keyTab' value should point to the keytab file that was generated by the kadmin kerberos tool. See the [Section 6.6.5.1, “SPNEGO Server Configuration”](#) section for more details.

2. Extend the core authentication mechanisms to support SPNEGO under **deployers/jbossweb.deployer/META-INF/war-deployers-jboss-beans.xml** by adding the 'SPNEGO' authenticators property.

```
<deployment xmlns="urn:jboss:bean-deployer:2.0">
<property name="authenticators">
    <map class="java.util.Properties" keyClass="java.lang.String"
valueClass="java.lang.String">
        <entry>
            <key>BASIC</key>
            <value>org.apache.catalina.authenticator.BasicAuthenticator</value>
        </entry>
        <entry>
            <key>CLIENT-CERT</key>
            <value>org.apache.catalina.authenticator.SSLAuthenticator</value>
        </entry>
        <entry>
            <key>DIGEST</key>
            <value>org.apache.catalina.authenticator.DigestAuthenticator</value>
        </entry>
        <entry>
            <key>FORM</key>
            <value>org.apache.catalina.authenticator.FormAuthenticator</value>
        </entry>
        <entry>
            <key>NONE</key>
            <value>org.apache.catalina.authenticator.NonLoginAuthenticator</value>
        </entry>

        <!-- Add this entry -->
        <entry>
            <key>SPNEGO</key>
            <value>org.jboss.security.negotiation.NegotiationAuthenticator</value>
        </entry>
    </map>
</property>
```

3. Add the GateIn 3.1 SSO module binaries by copying **\$GATEIN_SSO_HOME/spnego/gatein.ear/lib/sso-agent.jar**, and **\$GATEIN_SSO_HOME/spnego/gatein.ear/lib/sso-spnego.jar** to the **deploy/gatein.ear/lib** directory.
4. Modify the **deploy/gatein.ear/META-INF/gatein-jboss-beans.xml** file as below, then comment on other parts.

```
<login-module code="org.gatein.sso.spnego.SPNEGOLoginModule" flag="required">
  <module-option name="password-stacking">useFirstPass</module-option>
  <module-option name="serverSecurityDomain">host</module-option>
</login-module>
<login-module code="org.gatein.sso.agent.login.SPNEGORolesModule" flag="required">
  <module-option name="password-stacking">useFirstPass</module-option>
  <module-option name="portalContainerName">portal</module-option>
  <module-option name="realmName">gatein-domain</module-option>
</login-module>
```

5. Modify **gatein.ear/02portal.war/WEB-INF/web.xml** as below.

```
<!--
<login-config>
  <auth-method>FORM</auth-method>
  <realm-name>gatein-domain</realm-name>
  <form-login-config>
    <form-login-page>/initiatellogin</form-login-page>
    <form-error-page>/errorlogin</form-error-page>
  </form-login-config>
</login-config>
-->

<login-config>
  <auth-method>SPNEGO</auth-method>
  <realm-name>SPNEGO</realm-name>
</login-config>
```

This integrates SPNEGO support into the Portal web archive by switching the authentication mechanism from the default "FORM"-based to "SPNEGO"-based authentication.

6. Integrate the request pre-processing needed for SPNEGO via filters by adding the following filters to the **web.xml** at the top of the Filter chain.

```

<filter>
  <filter-name>LoginRedirectFilter</filter-name>
  <filter-class>org.gatein.sso.agent.filter.LoginRedirectFilter</filter-class>
  <init-param>
    <!-- This should point to your SSO authentication server -->
    <param-name>LOGIN_URL</param-name>
    <param-value>/portal/private/classic</param-value>
  </init-param>
</filter>
<filter>
  <filter-name>SPNEGOFilter</filter-name>
  <filter-class>org.gatein.sso.agent.filter.SPNEGOFilter</filter-class>
</filter>
<filter-mapping>
  <filter-name>LoginRedirectFilter</filter-name>
  <url-pattern>/*</url-pattern>
</filter-mapping>
<filter-mapping>
  <filter-name>SPNEGOFilter</filter-name>
  <url-pattern>/*</url-pattern>
</filter-mapping>

```

7. Start the GateIn 3.1 portal using the command below.

```

sudo          ./run.sh          -Djava.security.krb5.realm=LOCAL.NETWORK          -
Djava.security.krb5.kdc=server.local.network -c PROFILE -b server.local.network

```

The PROFILE parameter in the above command should be replaced with the server profile modified in the above configuration. For example, if you are configuring the default profile, your command will be.

```

sudo          ./run.sh          -Djava.security.krb5.realm=LOCAL.NETWORK          -
Djava.security.krb5.kdc=server.local.network -c default -b server.local.network

```

8. Login to Kerberos with the command.

```

kinit -A demo

```

You should be able to click the 'Sign In' link on the GateIn 3.1 portal and the 'demo' user from the GateIn 3.1 portal should be automatically logged in.

6.6.5.3. Clients

After performing all configurations above, you need to enable the **Negotiate authentication** of Firefox in clients so that clients could be authenticated by GateIn 3.1 as follows:

1. Start Firefox, then enter the command: **about:config** into the address field.
2. Enter **network.negotiate-auth** and set the value as below:

```
network.negotiate-auth.allow-proxies = true
network.negotiate-auth.delegation-uris = .local.network
network.negotiate-auth.gsslib (no-value)
network.negotiate-auth.trusted-uris = .local.network
network.negotiate-auth.using-native-gsslib = true
```

Web Services for Remote Portlets (WSRP)

7.1. Introduction

The Web Services for Remote Portlets specification defines a web service interface for accessing and interacting with presentation-oriented web services. It has been produced through the efforts of the Web Services for Remote Portlets (WSRP) OASIS Technical Committee. It is based on the requirements gathered and on the concrete proposals made to the committee.

Scenarios motivating the WSRP functionality include:

- Content hosts, such as portal servers, providing Portlets as presentation-oriented web services that can be used by aggregation engines.
- Aggregating frameworks, including portal servers, consuming presentation-oriented web services offered by content providers and integrating them into the framework.

More information on WSRP can be found on the [official website for WSRP](http://www.oasis-open.org/committees/tc_home.php?wg_abbrev=wsrp) [http://www.oasis-open.org/committees/tc_home.php?wg_abbrev=wsrp]. It is suggested that you read the [primer](http://www.oasis-open.org/committees/download.php/10539/wsrp-primer-1.0.html) [http://www.oasis-open.org/committees/download.php/10539/wsrp-primer-1.0.html] for a good, and albeit technical overview of WSRP.

7.2. Level of support in GateIn 3.1

The WSRP Technical Committee defined [WSRP Use Profiles](http://www.oasis-open.org/committees/download.php/3073) [http://www.oasis-open.org/committees/download.php/3073] to help with the WSRP interoperability. You can refer to terms defined in that document in this section.

GateIn provides a Simple level of support for our WSRP Producer except that out-of-band registration is not currently handled. eXo Platform supports the in-band registration and persistent local state (which are defined at the Complex level).

On the Consumer side, GateIn provides a Medium level of support for WSRP, except that eXo Platform only handles the HTML markup (as GateIn itself does not handle other markup types). eXo Platform supports the explicit portlet cloning and provides the full support the PortletManagement interface.

As far as caching goes, eXo Platform has Level 1 Producer and Consumer. eXo Platform supports the Cookie handling properly on the Consumer and our Producer that requires initialization of cookies. eXo Platform does not support custom window states or modes. However, eXo Platform supports CSS on both the Producer (though it's more a function of the portlets than inherent Producer capability) and Consumer.

While eXo Platform provides a complete implementation of WSRP 1.0, you need to go through the [Conformance statements](http://www.oasis-open.org/committees/download.php/6018) [http://www.oasis-open.org/committees/download.php/6018] and perform more interoperability testing (an area that needs to be better supported by the WSRP Technical Committee and Community at large).



Note

As of version 3.1 of GateIn, WSRP is only activated and supported when GateIn is deployed on the JBoss Application Server.

7.3. Deploying GateIn's WSRP services

GateIn provides a complete support of WSRP 1.0 standard interfaces and offers services to both consumers and producers. The WSRP support is provided by the following files, assuming `$GATEIN_HOME` is where GateIn has been installed, `$WSRP_VERSION` (at the time of the writing, it was 1.1.0-GA) is the version of the WSRP component and `$PORTAL_VERSION` (at the time of the writing, it was 3.0.1-GA) is the current GateIn version:

- `$GATEIN_HOME/wsrp-admin-gui.war`, which contains the WSRP Configuration portlet with which you can configure consumers to access remote servers and how the WSRP producer is configured.
- `$GATEIN_HOME/wsrp-producer.war`, which contains the WSRP producer web application.
- `$GATEIN_HOME/lib/wsrp-common-$WSRP_VERSION.jar`, which contains common classes needed by the different WSRP libraries.
- `$GATEIN_HOME/lib/wsrp-consumer-$WSRP_VERSION.jar`, which contains the WSRP consumer.
- `$GATEIN_HOME/lib/wsrp-integration-api-$WSRP_VERSION.jar`, which contains the API classes needed to integrate the WSRP component into portals.
- `$GATEIN_HOME/lib/wsrp-producer-lib-$WSRP_VERSION.jar`, which contains the classes needed by the WSRP producer.
- `$GATEIN_HOME/lib/wsrp-wsrp1-ws-$WSRP_VERSION.jar`, which contains the generated JAX-WS classes for WSRP v.1.
- `$GATEIN_HOME/lib/wsrp-wsrp2-ws-$WSRP_VERSION.jar`, which contains the generated JAX-WS classes for WSRP version 2.
- `$GATEIN_HOME/lib/gatein.portal.component.wsrp-$PORTAL_VERSION.jar`, which contains the code to integrate the WSRP service into GateIn.

If you are not going to use WSRP in GateIn, you can remove `$GATEIN_HOME/lib/gatein.portal.component.wsrp-$PORTAL_VERSION.jar` from your GateIn distribution to easily

If you consider the WSRP use when running GateIn on a non-default port or hostname deactivate the [WSRP support](http://community.jboss.org/wiki/WSRPservice removalprocedure) [http://community.jboss.org/wiki/WSRPservice removalprocedure]. Of course, if you want to trim your installation, you can also remove all the files mentioned above.

7.3.1. If you consider the WSRP use when running GateIn on a non-default port or hostname

JBoss WS (the web service stack that GateIn uses), you need to pay attention to details of updating the port and host name used in WSDL. See the [JBoss WS user guide on that subject](http://community.jboss.org/wiki/JBossWS-UserGuide#Configuration) [http://community.jboss.org/wiki/JBossWS-UserGuide#Configuration] for more details.

Of course, if you have modified the host name and port on which your server runs, you will need to update the configuration for the consumer used to consume GateIn's 'self' producer. Please refer to the [???](#) to learn how to do so.

7.3.2. Considerations to use WSRP with SSL

It is possible to use WSRP over SSL for secure exchange of data. Please refer to the [instructions](http://community.jboss.org/wiki/ConfiguringWSRPforuseoverSSL) [http://community.jboss.org/wiki/ConfiguringWSRPforuseoverSSL] on how to do from [GateIn's wiki](http://community.jboss.org/wiki/GateIn) [http://community.jboss.org/wiki/GateIn].

7.4. Making a portlet remotable



Note

Only JSR-286 (Portlet 2.0) portlets can be made remotable as the mechanism to expose a portlet to WSRP relies on the JSR-286-only functionality.

GateIn does **NOT** expose local portlets for consumption by remote WSRP consumers by default. To make a portlet remotely available, it must be made "remotable" by marking it as such in the associated `portlet.xml`. This is accomplished by using a specific `org.gatein.pc.remotable container-runtime-option`. Setting its value to `true` makes the portlet available for the remote consumption, while setting its value to `false` will not publish it remotely. As specifying the remotable status for a portlet is optional, you do not need to do anything if you do not need your portlet to be available remotely.

In the following example, the "BasicPortlet" portlet is specified as being remotable.

Example 7.1.

```
<?xml version="1.0" standalone="yes"?>
<portlet-app xmlns="http://java.sun.com/xml/ns/portlet/portlet-app_2_0.xsd"
  xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
```

```
        xsi:schemaLocation="http://java.sun.com/xml/ns/portlet/portlet-app_2_0.xsd http://
java.sun.com/xml/ns/portlet/portlet-app_2_0.xsd"
        version="2.0">
<portlet-app>
  <portlet>
    <portlet-name>BasicPortlet</portlet-name>

    ...

    <container-runtime-option>
      <name>org.gatein.pc.remotable</name>
      <value>true</value>
    </container-runtime-option>
  </portlet>
</portlet-app>
```

It is also possible to specify that all the portlets declared within a given portlet application to be remotable by default. This is done by specifying the `container-runtime-option` at the `portlet-app` element level. Individual portlets can override that value to not be remotely exposed. Let's look at an example:

Example 7.2.

```
<?xml version="1.0" standalone="yes"?>
<portlet-app xmlns="http://java.sun.com/xml/ns/portlet/portlet-app_2_0.xsd"
  xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
  xsi:schemaLocation="http://java.sun.com/xml/ns/portlet/portlet-app_2_0.xsd http://
java.sun.com/xml/ns/portlet/portlet-app_2_0.xsd"
  version="2.0">
<portlet-app>

  <portlet>
    <portlet-name>RemotelyExposedPortlet</portlet-name>
    ...
  </portlet>
  <portlet>
    <portlet-name>NotRemotelyExposedPortlet</portlet-name>
    ...
    <container-runtime-option>
      <name>org.gatein.pc.remotable</name>
      <value>false</value>
    </container-runtime-option>
```

```

</portlet>

<container-runtime-option>
  <name>org.gatein.pc.remotable</name>
  <value>true</value>
</container-runtime-option>
</portlet-app>

```

In the example above, two portlets are defined. The `org.gatein.pc.remotable` `container-runtime-option` is set to `true` at the `portlet-app` level, meaning that all portlets defined in this particular portlet application are exposed remotely by GateIn's WSRP producer. Note, however, that it is possible to override the default behavior: specifying a value for the `org.gatein.pc.remotable` `container-runtime-option` at the `portlet` level will take precedence over the default. In the example above, the `RemotelyExposedPortlet` inherits the `remotable` status defined at the `portlet-app` level since it does not specify a value for the `org.gatein.pc.remotable` `container-runtime-option`. The `NotRemotelyExposedPortlet`, however, overrides the default behavior and is not remotely exposed. Note that in the absence of a top-level `org.gatein.pc.remotable` `container-runtime-option` value set to `true`, portlets are NOT remotely exposed.

7.5. Consuming GateIn's WSRP portlets from a remote Consumer

WSRP Consumers vary a lot as far as how they are configured. Most of them require you to specify the URL for the Producer's WSDL definition. Please refer to your Consumer's documentation for specific instructions. For instructions on how to do so in GateIn, please refer to [???](#).

GateIn's Producer is automatically set up when you deploy a portal instance with the WSRP service. You can access the WSDL file at `http://{hostname}:{port}/wsrp-producer/v2/MarkupService?wsdl`. If you wish to use only the WSRP 1 compliant version of the producer, please use the WSDL file found at `http://{hostname}:{port}/wsrp-producer/v1/MarkupService?wsdl`. The default hostname is `localhost` and the default port is `8080`.

7.6. Consuming remote WSRP portlets in GateIn

7.6.1. Overview

To consume the WSRP portlets exposed by a remote producer, GateIn's WSRP consumer needs to know how to access that remote producer. One can configure access to a remote producer using the WSRP Producer descriptors. Alternatively, a portlet is provided to configure the remote producers.

Once a remote producer has been configured, the portlets that it exposes are then available in the Application Registry to be added to categories and then to pages.

As a way to test the WSRP producer service and to check that the portlets that you want to expose remotely are correctly published via WSRP, a default consumer named `self`, that consumes the portlets exposed by GateIn's producer, has been configured.

7.6.2. Configuring a remote producer walk-through

Let's work through the steps of defining access to a remote producer so that its portlets can be consumed within GateIn. You need to configure access to the Oracle's public WSRP producer. First, examine how to do so using the configuration portlet and then show how the same result can be accomplished with a producer descriptor, though it is far easier to do so via the configuration portlet.



Note

Some WSRP producers do not support the chunked encoding that is activated by default by JBoss WS. If your producer does not support the chunked encoding, your consumer will not be able to properly connect to the producer. This will manifest itself with the following error: Caused by: `org.jboss.ws.WSException: Invalid HTTP server response [503] - Service Unavailable`. Please see the GateIn's [wiki page](http://community.jboss.org/wiki/Workaroundwhenchunkedencodingisnotsupported) [<http://community.jboss.org/wiki/Workaroundwhenchunkedencodingisnotsupported>] for more details.

7.6.2.1. Using the configuration portlet

GateIn provides a portlet to configure access (among other functions) to remote WSRP Producers graphically. However, it is not installed by default, so the first thing you need to do is to install the WSRP configuration portlet using the Application Registry.

Use the usual procedure to log in as a Portal administrator and go to the Application Registry. With the default installment, you can just go to <http://localhost:8080/portal/login?initialURI=%2Fportal%2Fprivate%2Fclassic%2FwsrpConfigurationp&username=root&password=gtn> [<http://localhost:8080/portal/login?initialURI=%2Fportal%2Fprivate%2Fclassic%2FwsrpConfiguration&username=root&password=gtn>]

You should see a screen similar to:

Consumer [status: active , inactive, (refresh needed)]	Actions
self (inactive) (refresh needed)	Configure Refresh Activate Delete

Reload consumers

This screen presents all the configured Consumers associated with their status and possible actions on them. A Consumer can be active or inactive. Activating a Consumer means that it is ready to act as a portlet provider. Also, note that a Consumer can be marked as required refreshing, meaning that the information held about it might not be up to date and refreshing it from the remote Producer might be a good idea. This can happen for several reasons: the service description for that remote Producer has not been fetched yet, the cached version has expired or modifications have been made to the configuration that could potentially invalidate it; thus, it is required to validate the information again.



Note

The WSRP configuration did not use to be installed by default in previous versions of GateIn. We include here the legacy instructions on how to install this portlet in case you ever need to re-install it.

Use the usual procedure to log in as a Portal administrator and go to the Application Registry. With the default install, you can just go to

<http://localhost:8080/portal/login?initialURI=%2Fportal%2Fprivate%2Fclassic%2Fadministration%2Fregistry&username=root&password=admin>

[<http://localhost:8080/portal/login?initialURI=%2Fportal%2Fprivate%2Fclassic%2Fadministration%2Fregistry&username=root&password=admin>]

Add the WSRP Configuration portlet to the Administration category. If you use the Import Applications functionality, the WSRP Configuration portlet will be automatically added to the Administration category.

Now that the portlet is added to a category, it can be added to a page and used. We recommend adding it to the same page as the Application Registry as operations relating to WSRP and adding portlets to categories are somewhat related as we will see. Go ahead and add the WSRP Configuration portlet to the page using the standard procedure.

Next, you need create a new Consumer called `oracle`. Type "oracle" in the "Create a consumer named:" field, then click "Create consumer":

Create a consumer named:

You should now see a form allowing you to enter/modify the information about the Consumer. Set the cache expiration value to 300 seconds, leave the default timeout value for web services (WS) operations and enter the WSDL URL for the producer in the text field and press the "Refresh & Save" button:

Consumer 'oracle' configuration inactive (refresh needed)	
Producer id:	<input type="text" value="oracle"/>
Cache expiration:	<input type="text" value="300"/> (seconds before expiration)
Timeout for WS operations:	<input type="text" value="10000"/> (milliseconds before timeout)
Producer WSDL URL:	<input type="text" value="http://portalstandards.oracle.com/portletapp/portlets?WSDL"/>
<input type="button" value="Refresh & Save"/> <input type="button" value="Cancel"/>	


This will retrieve the service description associated with the Producer which WSRP interface is described by the WSDL file found at the URL you just entered. In this case, querying the service description will allow us to learn that the Producer requires registration but did not request any registration property:

✓ Refresh was successful.

Consumer 'oracle' configuration active	
Producer id:	<input type="text" value="oracle"/>
Cache expiration:	<input type="text" value="300"/> (seconds before expiration)
Timeout for WS operations:	<input type="text" value="10000"/> (milliseconds before timeout)
Producer WSDL URL:	<input type="text" value="http://portalstandards.oracle.com/portletapp/portlets?WSDL"/>
Registration information:	<div>Current registration information:</div> <div>Registration is indicated as required without registration properties.</div>
Registration context:	Handle:C:148.87.122.191:3fa5ac:1274c6b80c7:1de6 <input type="button" value="Erase local registration"/>
<input type="button" value="Refresh & Save"/> <input type="button" value="Cancel"/>	

The Consumer for the `oracle` Producer should now be available as a portlet provider and be ready to be used.

Now, assuming that the producer required a value for an `email` registration property, GateIn's WSRP consumer would have informed you that you were missing some information:

 **Error: Refresh failed (probably because the registration information was not valid).**

Consumer 'self' configuration inactive

Producer id:

Cache expiration: (seconds before expiration)

Timeout for WS operations: (milliseconds before timeout)

Producer WSDL URL:

Registration information:

Current registration information:

Name	Description	Value
email	A valid contact email.	<input type="text"/>

Error:
Missing value



Note

At this point, there is no automated way to learn about which possible values (if any) are expected by the remote Producer. Sometimes, the possible values will be indicated in the registration property description but this is not always the case. Please refer to the specific Producer's documentation.

If you entered "example@example.com" as the value for the registration property and press "Save & Refresh" once more, you would have seen something similar to:

 **Refresh was successful.**

Consumer 'self' configuration active

Producer id:

Cache expiration: (seconds before expiration)

Timeout for WS operations: (milliseconds before timeout)

Producer WSDL URL:

Registration information:

Current registration information:

Name	Description	Value
email	A valid contact email.	<input type="text" value="example@example.com"/>

Registration context:

7.6.2.2. Using XML

While it is recommended that you use the WSRP Configuration portlet to configure Consumers, eXo Platform provides an alternative way to configure consumers by editing the .xml file located at `$GATEIN_HOME/lib/wsrp-consumer-$WSRP_VERSION.jar/conf/wsrp-consumers-config.xml`.


```
<?xml version='1.0' encoding='UTF-8' ?>
<deployments xmlns="http://www.gatein.org/xml/ns/gatein_wsrp_consumer_1_0"
  xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
  xsi:schemaLocation="http://www.gatein.org/xml/ns/gatein_wsrp_consumer_1_0 http://
www.jboss.org/portal/xsd/gatein_wsrp_consumer_1_0.xsd">
  <deployment>
    <wsrp-producer id="self" expiration-cache="300" ws-timeout="30000">
      <endpoint-wsdl-url>http://localhost:8080/wsrp-producer/v2/MarkupService?wsdl</endpoint-
wsdl-url>
      <registration-data>
        <property>
          <name>email</name>
          <lang>en</lang>
          <value>example@example.com</value>
        </property>
      </registration-data>
    </wsrp-producer>
  </deployment>
  <deployment>
    <wsrp-producer id="oracle" expiration-cache="300">
      <endpoint-wsdl-url>http://portalstandards.oracle.com/portletapp/portlets?WSDL</endpoint-
wsdl-url>
    </wsrp-producer>
  </deployment>
</deployments>
```

The file as shown above specifies access to two producers: `self`, which consumes GateIn's own WSRP producer albeit in a version that assumes that the producer requires a value for an `email` registration property, and `oracle`, which consumes Oracle's public producer, both in configurations as shown in the walk-through above.

We will look at the details of the meaning of elements later on.


7.6.2.3. Adding remote portlets to categories

If we go back to the Application Registry and examine the available portlets by clicking the Portlet link, you will now be able to see the remote portlets after clicking the REMOTE tab in the left column:



These portlets are available to be used. For example, the regular portlets can be used in categories and added to pages. If you use the Import Applications functionality, they will also be automatically imported into categories based on the keywords they define.

More specifically, if you want to add the WSRP portlet to a category, you can access these portlets by selecting `wsrp` in the Application Type drop-down menu:



7.6.3. Configuring access to remote producers via XML

While it is recommended that you use the WSRP Configuration portlet to configure Consumers, eXo Platform provides an alternative way to configure consumers by editing the XML file located at `$GATEIN_HOME/lib/wsrp-consumer-$WSRP_VERSION.jar/conf/wsrp-consumers-config.xml`.



Note

An XML Schema defining which elements are available to configure Consumers via XML can be found in `$GATEIN_HOME/lib/wsrp-integration-api-$WSRP_VERSION.jar/xsd/gatein_wsrp_consumer_1_0.xsd`



Note

It is important to note how the XML consumers configuration file is processed. It is the first time the WSRP service starts and the associated information is then put under control of JCR (Java Content Repository). The subsequent launches of the WSRP service will use the JCR-stored information for all producers that are already known to GateIn. More specifically, the `wsrp-consumers-config.xml` file is scanned for producer identifiers. Any identifier that is already known will be by-passed and the JCR information associated with this remote producer will be used. The information defined at the XML level is only processed for producer definition for which no information is already present in JCR. Therefore, if you wish to delete a producer configuration, you need to delete the associated information in the database (this can be accomplished using the configuration portlet as shown in [Section 7.6.2.1, "Using the configuration portlet"](#)) AND remove the associated information in `wsrp-consumers-config.xml` (if such information exists) as the producer will be re-created the next time the WSRP is launched if that information is not removed.

7.6.3.1. Required configuration information

Now, look at which information needs to be provided to configure access to a remote producer.

First, you need to provide an identifier for the producer we are configuring so that you can refer to it afterwards. This is accomplished via the mandatory `id` attribute of the `<wsrp-producer>` element.

GateIn also needs to learn about the remote producer's end-points to be able to connect to the remote web services and perform WSRP invocations. This is accomplished by specifying the URL for the WSDL description for the remote WSRP service, using the `<endpoint-wsdl-url>` element.

Both the `id` attribute and `<endpoint-wsdl-url>` elements are required for a functional remote producer configuration.

7.6.3.2. Optional configuration

It is also possible to provide additional configuration. In some cases, the additional configuration might be important to establish a proper connection to the remote producer.

One such optional configuration concerns caching. To prevent useless roundtrips between the local consumer and the remote producer, it is possible to cache some of the information sent

by the producer (such as the list of offered portlets) for a given duration. The rate at which the information is refreshed is defined by the `expiration-cache` attribute of the `<wsrp-producer>` element which specifies the refreshing period in seconds. For example, providing a value of 120 for `expiration-cache` means that the producer information will not be refreshed for 2 minutes after it has been somehow accessed. If no value is provided, GateIn will always access the remote producer regardless of whether the remote information has changed or not. Since, in most instances, the information provided by the producer does not change often. It is recommended that you use this caching facility to minimize the bandwidth usage.

It is also possible to define a timeout after which the WS operations are considered as failed. This is helpful to avoid blocking the WSRP service, waiting forever on the service that does not answer. Use the `ws-timeout` attribute of the `<wsrp-producer>` element to specify how many milliseconds the WSRP service will wait for a response from the remote producer before timing out and giving up.

Additionally, some producers require consumers to register with them before authorizing them to access their offered portlets. If you know that information beforehand, you can provide the required registration information in the producer configuration so that the consumer can register with the remote producer when required.



Note

At this time, though, only simple String properties are supported and it is not possible to configure the complex registration data. This should, however, be sufficient for most cases.

Registration configuration is done via the `<registration-data>` element. Since GateIn can generate the mandatory information for you, if the remote producer does not require any registration properties, you only need to provide an empty `<registration-data>` element. Values for the registration properties required by the remote producer can be provided via the `<property>` elements. See the example below for more details. Additionally, you can override the default consumer name automatically provided by GateIn via the `<consumer-name>` element. If you select to provide a consumer name, please remember that this should uniquely identify your consumer.

7.6.4. Examples

Here is the configuration of the `selfv1` and `selfv2` consumers as found in `$GATEIN_HOME/lib/wsrp-consumer-$WSRP_VERSION.jar/conf/wsrp-consumers-config.xml` with a cache expiring every 500 seconds and with a 50 second timeout for web service operations.

Example 7.3.

```
<?xml version='1.0' encoding='UTF-8' ?>
```

```
<deployments xmlns="http://www.gatein.org/xml/ns/gatein_wsrp_consumer_1_0"
  xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
  xsi:schemaLocation="http://www.gatein.org/xml/ns/gatein_wsrp_consumer_1_0 http://
www.jboss.org/portal/xsd/gatein_wsrp_consumer_1_0.xsd">
  <deployment>
    <wsrp-producer id="selfv1" expiration-cache="500" ws-timeout="50000">
      <endpoint-wsdl-url>http://localhost:8080/wsrp-producer/MarkupService?wsdl</endpoint-
wsdl-url>
      <registration-data/>
    </wsrp-producer>
  </deployment>
  <deployment>
    <wsrp-producer id="selfv2" expiration-cache="500" ws-timeout="50000">
      <endpoint-wsdl-url>http://localhost:8080/wsrp-producer/v2/MarkupService?wsdl</endpoint-
wsdl-url>
      <registration-data/>
    </wsrp-producer>
  </deployment>
</deployments>
```

Here is an example of a WSRP descriptor with registration data and cache expiring every minute:

Example 7.4.

```
<?xml version='1.0' encoding='UTF-8' ?>
<deployments xmlns="http://www.gatein.org/xml/ns/gatein_wsrp_consumer_1_0"
  xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
  xsi:schemaLocation="http://www.gatein.org/xml/ns/gatein_wsrp_consumer_1_0 http://
www.jboss.org/portal/xsd/gatein_wsrp_consumer_1_0.xsd">
<deployments>
  <deployment>
    <wsrp-producer id="AnotherProducer" expiration-cache="60">
      <endpoint-wsdl-url>http://example.com/producer/producer?WSDL</endpoint-wsdl-url>
      <registration-data>
        <property>
          <name>property name</name>
          <lang>en</lang>
          <value>property value</value>
        </property>
      </registration-data>
    </wsrp-producer>
```

```
</deployment>
</deployments>
```

7.7. Consumers maintenance

7.7.1. Modifying a currently held registration

7.7.1.1. Registration modification for service upgrade

Producers often offer several levels of service depending on consumers' subscription levels (for example). This is implemented at the WSRP level with the registration concept: producers can assert which level of service to provide to consumers based on the values of given registration properties.

There might also be cases where you just want to update the registration information because it has changed. For example, the producer required you to provide a valid email and the previously email address is not valid anymore and needs to be updated.

It is therefore sometimes necessary to modify the registration that concretizes the service agreement between a consumer and a producer. Let's take the example of the producer requiring an email you configured in [Section 7.6.2.1, "Using the configuration portlet"](#). If you recall, the producer was requiring registration and required a value to be provided for the `email` property.

Suppose that you want to update the email address that you provided to the remote producer. To do so, you need to tell the producer that our registration data have been modified. Let's see how to do this. In case that you want to configure access to the producer as previously described, please go to the configuration screen for the `self` producer and modify the value of `email` to `foo@example.com` instead of `example@example.com`:

Current registration information:

Name	Description	Value
email	A valid email.	<input type="text" value="foo@example.com"/>

Now, click "Update properties" to save the change. A "Modify registration" button should now appear to let you send the new data to the remote producer:

Current registration information:

Name	Description	Value
email	A valid email.	<input type="text" value="foo@example.com"/>

Click this new button and, if everything went well and your updated registration has been accepted by the remote producer, you should see something similar to:

- ✔ Successfully modified registration!
- ✔ Refresh was successful.

Consumer 'self' configuration active

Producer id:

Cache expiration: (seconds before expiration)

Timeout for WS operations: (milliseconds before timeout)

Producer WSDL URL:

Registration information:

Current registration information:

Name	Description	Value
email	A valid email.	<input type="text" value="foo@example.com"/>

Update properties

Registration context: Handle:07d57d29c0a801325a0da57a96c12a32

Erase local registration

Refresh & Save

Cancel

7.7.1.2. Registration modification on producer error

It can also happen that a producer administrator decided to change its requirement for registered consumers. In this case, invoking operations on the producer will be failed with an `OperationFailedFault`. GateIn will attempt to help you in this situation. Let's walk through an example using the `self` producer. Let's assume that registration is requiring a valid value for an `email` registration property (as we have seen so far). If you go to the configuration screen for this producer, you should see:

Consumer 'self' configuration active

Producer id:

Cache expiration: (seconds before expiration)

Timeout for WS operations: (milliseconds before timeout)

Producer WSDL URL:

Registration information:

Current registration information:

Name	Description	Value
email	A valid email.	<input type="text" value="foo@example.com"/>

Update properties

Registration context: Handle:07d57d29c0a801325a0da57a96c12a32

Erase local registration

Refresh & Save

Cancel

Now suppose that the administrator of the producer also requires a value to be provided for a `name` registration property. We will actually see how to perform this operation in GateIn when we examine how to configure GateIn's producer in [Section 7.8, "Configuring GateIn's WSRP Producer"](#). Operations with this producer will now be failed. If you suspect that a registration modification is required, you should go to the configuration screen for this remote producer and refresh the information held by the consumer by pressing "Refresh & Save":

Error: Either local or remote information has been changed, you should modify your registration with the remote producer. The new local information will be saved but your current registration data will be used until you successfully modify the registration with the producer.

Consumer 'self' configuration
inactive (refresh needed)

Producer id:
Cache expiration:
Timeout for WS operations:
Producer WSDL URL:
Registration information:

(seconds before expiration)
 (milliseconds before timeout)

Current registration information:

Name	Description	Value
email	A valid email.	<input type="text" value="foo@example.com"/>

Expected registration information:

Name	Description	Value
email	A valid email.	<input type="text" value="foo@example.com"/>
name	A contact name.	<input type="text"/>

Missing value

Registration context:

Handle: 07d57d29c0a801325a0da57a96c12a32

As you can see, the configuration screen now shows the currently held registration information and the expected information from the producer. Enter a value for the `name` property and then click "Modify registration". If all went on well and the producer accepted your new registration data, you should see something similar to:

- ✓ Successfully modified registration!
- ✓ Refresh was successful.

Consumer 'self' configuration active

Producer id:
Cache expiration:
Timeout for WS operations:
Producer WSDL URL:
Registration information:

(seconds before expiration)
 (milliseconds before timeout)

Current registration information:

Name	Description	Value
email	A valid email.	<input type="text" value="foo@example.com"/>
name	A contact name.	<input type="text" value="Foo Bar"/>

Registration context: Handle:07d57d29c0a801325a0da57a96c12a32



Note

As of WSRP 1, it is rather difficult to ascertain what caused an `OperationFailedFault` as it is the generic exception returned by producers if something did not quite happen as expected during a method invocation. This means that `OperationFailedFault` can be caused by several different reasons, one of them being a request to modify the registration data. Please take a look at the log files to see if you can gather more information as to what happened. WSRP 2 introduces an exception that is specific to a request to modify registrations, thus reducing the ambiguity that currently exists.

7.7.2. Consumer operations

Several operations are available from the consumer list view of the WSRP configuration portlet:

Create a consumer named:

Consumer [status: active , inactive, (refresh needed)]	Actions
self (active)	<input type="button" value="Configure"/> <input type="button" value="Refresh"/> <input type="button" value="Deactivate"/> <input type="button" value="Deregister"/> <input type="button" value="Delete"/>

The available operations are:

- Configure: displays the consumer details and allows user to edit them.

- Refresh: forces the consumer to retrieve the service description from the remote producer to refresh the local information (offered portlets, registration information).
- Activate/Deactivate: activates/deactivates a consumer, governing whether it will be available to provide portlets and receive portlet invocations.
- Register/Deregister: registers/deregisters a consumer based on whether the registration is required and/or acquired
- Delete: destroys the consumer, after deregistering it if it was registered.
- Export: exports some or all of the consumer's portlets to be able to later import them in a different context
- Import: imports some or all of previously exported portlets

**Note**

Import/Export functionalities are only available to WSRP 2 consumers. Import functionality is only available if portlets had previously been exported.

7.7.3. Importing and exporting portlets

Import and export are new functionalities added in WSRP 2. Exporting a portlet allows a consumer to get an opaque representation of the portlet which can then be used by the corresponding import operation to reconstitute it. It is mostly used in migration scenarios during batch operations. Since GateIn does not currently support automated migration of portal data, the functionality that we provide as part of WSRP 2 is necessarily less complete than it could be with full portal support.

The import/export implementation in GateIn 3.1 allows users to export portlets from a given consumer. These portlets can then be used to replace existing content on pages. This is accomplished by assigning previously exported portlets to replace the content displayed by windows on the portal's pages. Let us walk through an example to make things clearer.

Clicking the "Export" action for a given consumer will display the list of portlets currently made available by this specific consumer. An example of such a list is shown below:

Once portlets have been selected, they can be exported by clicking the "Export" button thus making them available for later import:

You can re-import the portlets directly by pressing the "Use for import" button or, on the Consumers list page, using the "Import" action for a given consumer. Let's assume that you used that second option and that you currently have several available sets of previously exported portlets to import from. After clicking the action link, you should see a screen similar to the one below:

As you can see this screen presents the list of available exports with available operations for each.

- View: displays the export details as previously seen when the export was first performed
- Delete: deletes the selected export, asking you for confirmation first
- Use for import: selects the export to import portlets from

Once you have selected an export to import from, you will see a screen similar to the one below:

The screen displays the list of available exported portlets for the previously selected export. You can select which portlet you want to import by checking the checkbox next to its name. Next, you need to select the content of which window the imported portlet will replace. This process is done in three steps. Let's assume in this example that you have the following page called `page1` and containing two windows called `NetUnity WSRP 2 Interop - Cache Markup (remote)` and `/samples-remotecontroller-portlet.RemoteControl (remote)` as shown below:

In this example, we want to replace the content of the `/samples-remotecontroller-portlet.RemoteControl (remote)` by the content of the `/ajaxPortlet.JSFAJAXPortlet` portlet that we previously exported. To do so, we will check the checkbox next to the `/ajaxPortlet.JSFAJAXPortlet` portlet name to indicate that we want to import its data and then select the `page1` in the list of available pages. The screen will then refresh to display the list of available windows on that page, similar to the one seen below:

Note that, at this point, we still need to select the window which content we want to replace before being able to complete the import operation. Let's select the `/samples-remotecontroller-portlet.RemoteControl (remote)` window, at which point the "Import" button will become enabled, indicating that we now have all the necessary data to perform the import. If all goes well, pressing that button should result in a screen similar to the one below:

If you now take a look at the `page1` page, you should now see that the content `/samples-remotecontroller-portlet.RemoteControl (remote)` window has been replaced by the content of the `/ajaxPortlet.JSFAJAXPortlet` imported portlet and the window renamed appropriately:

7.7.4. Erasing local registration data

There are rare cases where it might be required to erase the local information without being able to deregister first. This is the case when a consumer is registered with a producer that has been modified by its administrator to not require the registration anymore. If that ever was to happen

(most likely, it will not), you can erase the local registration information from the consumer so that it can resume interacting with the remote producer. To do so, click the "Erase local registration" button next to the registration context information on the consumer configuration screen:

Registration context:

Handle:07d57d29c0a801325a0da57a96c12a32

Erase local registration

Warning: This operation is dangerous as it can result in inability to interact with the remote producer if invoked when not required. A warning screen will be displayed to give you a chance to change your mind:



Delete local registration for 'self' consumer?

Warning: You are about to delete the local registration information for the 'self' consumer! This is only needed if this consumer had previously registered with the remote producer and this producer has been modified to not require registration anymore. Only erase local registration information if you experience errors with the producer due to this particular situation. Erasing local registration when not required might lead to inability to work with this producer anymore.

Are you sure you want to proceed?

Erase local registration

Cancel

7.8. Configuring GateIn's WSRP Producer

7.8.1. Overview

You can configure the behavior of Portal's WSRP Producer by using the WSRP administration interface, which is the preferred way, or by editing the `$GATEIN_HOME/wsrp-producer.war/WEB-INF/conf/producer/config.xml` file. Several aspects can be modified with respects to whether the registration is required for consumers to access the Producer's services. An XML Schema for the configuration format is available at `$GATEIN_HOME/lib/wsrp-integration-api-$WSRP_VERSION.jar/xsd/gatein-wsrp-producer_1_0.xsd`.

7.8.2. Default configuration

The default producer configuration requires consumers to register with it before providing access to its services but does not require any specific registration properties (apart from what is

mandated by the WSRP standard). It does, however, require consumers to be registered before sending them a full service description. This means that our WSRP producer will not provide the list of offered portlets and other capabilities to unregistered consumers. The producer also uses the default `RegistrationPolicy` paired with the default `RegistrationPropertyValidator`. You need to look into property validators in greater detail later in [Section 7.8.3, "Registration configuration"](#). This allows you to customize how Portal's WSRP Producer decides whether a given registration property is valid or not.

GateIn provides a web interface to configure the producer's behavior. You can access it by clicking the "Producer Configuration" tab of the "WSRP" page of the "admin" portal. Here's what you should see with the default configuration:

☒ Access to full service description requires consumers to be registered.

☒ Use strict WSRP compliance.

☒ Requires registration. Modifying this information will trigger invalidation of consumer registrations.

Registration policy class name:

Registration property validator class name:

Registration properties Add property

No specified required registration properties.

As expected, you can specify whether or not the producer will send the full service description to unregistered consumers, and, if it requires registration, which `RegistrationPolicy` to use (and, if needed, which `RegistrationPropertyValidator`), along with required registration property description for which consumers must provide acceptable values to register successfully.

7.8.3. Registration configuration

To require consumers to register with the Portal's producer before interacting with it, you need to configure the Portal's behavior with respect to registration. Registration is optional, as registration properties. The producer can require registration without passing any registration properties in case of the default configuration. Let's configure our producer starting with a blank state:

☐ Access to full service description requires consumers to be registered.

☒ Use strict WSRP compliance.

☐ Requires registration. Modifying this information will trigger invalidation of consumer registrations.

eXo Platform will allow unregistered consumers to see the list of offered portlets, so the first checkbox ("Access to full service description requires consumers to be registered") is unchecked. You will, however, specify that consumers will need to be registered to be able to interact with our producer. Check the second checkbox ("Requires registration. Modifying this information will trigger invalidation of consumer registrations."). The screen should now refresh and display:

Consumers Configuration Producer Configuration

☒ Access to full service description requires consumers to be registered.

☒ Use strict WSRP compliance.

☒ Requires registration. Modifying this information will trigger invalidation of consumer registrations.

Registration policy class name:

Registration property validator class name:

Registration properties Add property

No specified required registration properties.

Save Cancel

You can specify the fully-qualified name for your `RegistrationPolicy` and `RegistrationPropertyValidator` there. We will keep the default value. See [Section 7.8.3.1, “Customization of Registration handling behavior”](#) for more details. Let's add, however, a registration property called `email`. Click "Add property" and enter the appropriate information in the fields, providing a description for the registration property that can be used by consumers to figure out its purpose:

☐ Access to full service description requires consumers to be registered.

☒ Use strict WSRP compliance.

☒ Requires registration. Modifying this information will trigger invalidation of consumer registrations.

Registration policy class name:

Registration property validator class name:

Registration properties Add property

Name	Type	Label	Hint	Action
email	xsd:string	A valid contact email.	A valid contact email.	Remove

Save Cancel

Press "Save" to record your modifications.



Note

At this time, only String (xsd:string) properties are supported. If your application requires more complex properties, please let us know.



Note

If consumers are already registered with the producer, modifying the configuration of required registration information will trigger the invalidation of held registrations, requiring consumers to modify their registration before being able to access the producer again. We saw the consumer side of that process in [Section 7.7.1.2, “Registration modification on producer error”](#).

7.8.3.1. Customization of Registration handling behavior

Registration handling behavior can be customized by users to suit their Producer needs. This is accomplished by providing an implementation of the `RegistrationPolicy` interface. This interface defines methods that are called by Portal's Registration service so that decisions can be made appropriately. A default registration policy that provides basic behavior is provided and should be enough for most user needs.

While the default registration policy provides the default behavior for most registration-related aspects, there is still one aspect that requires configuration: whether a given value for a registration property is acceptable by the WSRP Producer. This is accomplished by plugging a `RegistrationPropertyValidator` in the default registration policy. This allows you to define their own validation mechanism.

Please refer to the Javadoc™ for `org.jboss.portal.registration.RegistrationPolicy` and `org.jboss.portal.registration.policies.RegistrationPropertyValidator` for more details on what is expected of each method.

Defining a registration policy is required for the producer to be correctly configured. This is accomplished by specifying the qualified class name of the registration policy. Since we anticipate that most users will use the default registration policy, it is possible to provide the class name of your custom property validator instead of customizing the default registration policy behavior. Note that property validators are only used by the default policy.



Note

Since the policy or the validator are defined via their class name and dynamically loaded, it is important that you make sure that the identified class is available to the application server. One way to accomplish that is to deploy your policy implementation as the JAR file in your AS instance deploy directory. Note also that, since both policies and validators are dynamically instantiated, they must provide a default, no-argument constructor.

7.8.4. WSRP validation mode

The lack of conformance kit and the wording of the WSRP specification leaves room for differing interpretations, resulting in interoperability issues. It is therefore possible to encounter issues when using consumers from different vendors. We have experienced such issues and have introduced a way to relax the validation that our WSRP producer performs on the data provided by consumers to help with interoperability by accepting data that would normally be invalid. Note that we only relax our validation algorithm on aspects of the specification that are deemed harmless, such as invalid language codes.

By default, the WSRP producer is configured in the strict mode. If you experience issues with a given consumer, you might want to try to relax the validation mode. This is accomplished by unchecking the "Use strict WSRP compliance." checkbox on the Producer configuration screen.

Advanced Development


8.1. Foundations

8.1.1. GateIn Kernel

GateIn 3.1 is built as a set of services on top of the dependency injection kernel. The kernel provides configuration, lifecycle handling, component scopes, and some core services.

Service components exist in two scopes. The first scope is represented by **RootContainer** - it contains services that exist independently of any portal, and can be accessed by all portals.

The second scope is portal-private in the form of **PortalContainer**. Each portal lives in an instance of PortalContainer. This scope contains services that are common for a set of portals, and services which should not be shared by all portals.



Whenever a specific service is looked up through PortalContainer, and the service is not available, the lookup is delegated further up to RootContainer. We can therefore have the default instance of a certain component in RootContainer, and portal specific instances in some or all PortalContainers which override the default instance.

Whenever your portal application has to be integrated more closely with GateIn services, the way to do it is by looking up these services through PortalContainer. Be careful though - only officially documented services should be accessed this way, and used according to documentation, as most of the services are an implementation detail of GateIn, and subject to change without notice.

8.1.2. Configuring services

GateIn Kernel uses the dependency injection to create services based on the **configuration.xml** configuration files. The location of the configuration files determines if services are placed into the RootContainer scope, or into the PortalContainer scope. All configuration.xml files located at **conf/configuration.xml** in the classpath (any directory, or any jar in the classpath) will have their services configured at the RootContainer scope. All configuration.xml files located at **conf/portal/configuration.xml** in the classpath will have their services configured at the PortalContainer scope. Additionally, **portal extensions** can contain configuration in **WEB-INF/conf/configuration.xml**, and will also have their services configured at the PortalContainer scope.



Note

Portal extensions are described later.

8.1.3. Configuration syntax

8.1.3.1. Components

A service component is defined in the **configuration.xml** file by using **<component>** element.

There is only one required information when defining a service - the service implementation class, specified using **<type>**

Every component has a **<key>** that identifies it. If not explicitly set, a key defaults to the value of **<type>**. If the key is loaded as a class, the Class or String object will be used as a key.

The usual approach is to specify an interface as a key.

Example 8.1. Example of service component configuration:

```
<?xml version="1.0" encoding="ISO-8859-1"?>
<configuration
  xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
  xsi:schemaLocation="http://www.exoplaform.org/xml/ns/kernel_1_0.xsd
    http://www.exoplaform.org/xml/ns/kernel_1_0.xsd"
  xmlns="http://www.exoplaform.org/xml/ns/kernel_1_0.xsd">
  <component>
    <key>org.exoplaform.services.database.HibernateService</key>
    <type>org.exoplaform.services.database.impl.HibernateServiceImpl</type>

    ...
```



```

</component>
</configuration>

```

8.1.3.2. External Plugins

GateIn Kernel supports non-component objects that can be configured, instantiated, and injected into registered components, using method calls. The mechanism is called 'plugins', and allows portal extensions to add additional configurations to core services.

The external plugin is defined by using the **<external-component-plugins>** wrapper element which contains one or more **<component-plugin>** definitions. **<external-component-plugins>** uses **<target-component>** to specify a target service component that will receive injected objects.

Every **<component-plugin>** defines an implementation type, and a method on the target component to use for the injection (**<set-method>**).

A plugin implementation class has to implement the **org.exoplatform.container.component.ComponentPlugin** interface.

In the following example, **PortalContainerDefinitionPlugin** implements ComponentPlugin:

Example 8.2. PortalContainerDefinitionPlugin

```

<?xml version="1.0" encoding="UTF-8"?>
<configuration
  xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
  xsi:schemaLocation="http://www.exoplaform.org/xml/ns/kernel_1_0.xsd
    http://www.exoplaform.org/xml/ns/kernel_1_0.xsd"
  xmlns="http://www.exoplaform.org/xml/ns/kernel_1_0.xsd">

  <external-component-plugins>
    <target-component>org.exoplatform.container.definition.PortalContainerConfig</target-
component>
    <component-plugin>
      <!-- The name of the plugin -->
      <name>Add PortalContainer Definitions</name>

      <!-- The name of the method to call on the PortalContainerConfig
        in order to register the PortalContainerDefinitions -->
      <set-method>registerPlugin</set-method>

      <!-- The fully qualified name of the PortalContainerDefinitionPlugin -->

```

```
<type>org.exoplatform.container.definition.PortalContainerDefinitionPlugin</type>

...

</component-plugin>
</external-component-plugins>
</configuration>
```

8.1.3.3. Includes, and special URLs

It is possible to break the **configuration.xml** file into many smaller files, that are then included into a 'master' configuration file. The included files are complete configuration.xml documents, not fragments of text.

The following is an example configuration.xml which 'outsources' its content into several files:

```
<configuration xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
  xsi:schemaLocation="http://www.exoplaform.org/xml/ns/kernel_1_0.xsd
    http://www.exoplaform.org/xml/ns/kernel_1_0.xsd"
  xmlns="http://www.exoplaform.org/xml/ns/kernel_1_0.xsd">

  <import>war:/conf/sample-ext/jcr/jcr-configuration.xml</import>
  <import>war:/conf/sample-ext/portal/portal-configuration.xml</import>

</configuration>
```

The special URL is used to refer to another configuration file. The URL schema '**war:**' means that the path following is resolved that is related to the current PortalContainer's servlet context resource path, starting at **WEB-INF** as the root.



Note

The current PortalContainer is really a newly created PortalContainer, as war: URLs only make sense for PortalContainer scoped configuration.

Also, thanks to the extension mechanism, the servlet context used for resource loading is a **unified servlet context** (as explained in a later section).

To include the resolved path related to the current classpath (context classloader), use the '**jar:**' URL schema.

8.1.3.4. Special variables

The configuration files may contain a **special variable** reference `${container.name.suffix}`. This variable resolves to the name of the current portal container, prefixed by underscore (_). This facilitates reuse of configuration files in cases where portal specific unique names need to be assigned to some resources (For example, JNDI names, Database / DataSource names, JCR repository names).

This variable is only defined when there is a current PortalContainer available - only for PortalContainer scoped services.

A good example for this is **HibernateService**:

Example 8.3. HibernateService using variables

```
<?xml version="1.0" encoding="ISO-8859-1"?>
<configuration
  xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
  xsi:schemaLocation="http://www.exoplaform.org/xml/ns/kernel_1_0.xsd
    http://www.exoplaform.org/xml/ns/kernel_1_0.xsd"
  xmlns="http://www.exoplaform.org/xml/ns/kernel_1_0.xsd">

  <component>
    <key>org.exoplaform.services.database.HibernateService</key>
    <jmx-name>database:type=HibernateService</jmx-name>
    <type>org.exoplaform.services.database.impl.HibernateServiceImpl</type>
    <init-params>
      <properties-param>
        <name>hibernate.properties</name>
        <description>Default Hibernate Service</description>
        <property name="hibernate.show_sql" value="false" />
        <property name="hibernate.cglib.use_reflection_optimizer" value="true" />
        <property name="hibernate.connection.url"
          value="jdbc:hsqldb:file:../temp/data/exodb${container.name.suffix}" />
        <property name="hibernate.connection.driver_class" value="org.hsqldb.jdbcDriver" />
        <property name="hibernate.connection.autocommit" value="true" />
        <property name="hibernate.connection.username" value="sa" />
        <property name="hibernate.connection.password" value="" />
        <property name="hibernate.dialect" value="org.hibernate.dialect.HSQLDialect" />
        <property name="hibernate.c3p0.min_size" value="5" />
        <property name="hibernate.c3p0.max_size" value="20" />
        <property name="hibernate.c3p0.timeout" value="1800" />
        <property name="hibernate.c3p0.max_statements" value="50" />
      </properties-param>
    </init-params>
  </component>
</configuration>
```

```
</init-params>
</component>
</configuration>
```

8.1.4. InitParams configuration object

`InitParams` are the configuration object that is essentially a map of key-value pairs, where key is always a `String`, and value can be any type that can be described using the kernel `configuration.xml`.

Service components that form GateIn 3.1 infrastructure use the `InitParams` object to configure themselves. A component can have one instance of `InitParams` injected at most. If the service component's constructor takes `InitParams` as any of the parameters, it will automatically be injected at the component instantiation time. The xml configuration for a service component that expects the `InitParams` object must include the `<init-params>` element (even if the empty one).

To learn about how the kernel xml configuration syntax looks for creating `InitParams` instances, see the following example.

Example 8.4. InitParams - properties-param

```
<component>
  <key>org.exoplatform.services.naming.InitialContextInitializer</key>
  <type>org.exoplatform.services.naming.InitialContextInitializer</type>
  <init-params>
    <properties-param>
      <name>default-properties</name>
      <description>Default initial context properties</description>
      <property name="java.naming.factory.initial"
        value="org.exoplatform.services.naming.SimpleContextFactory" />
    </properties-param>
  </init-params>
</component>
```

The `InitParams` object description begins with the `<init-params>` element. It can have zero or more children elements, each of which is one of `<value-param>`, `<values-param>`, `<properties-param>`, or `<object-param>`. Each of these child elements takes a `<name>` that serves as a map entry key, and an optional `<description>`. It also takes a type-specific value specification.

For `<properties-param>`, the value specification is in the form of one or more `<property>` elements, each of which specifies two strings - a property name, and a property value. Each

<properties-params> defines one `java.util.Properties` instance. Also, see [Example 8.3, “HibernateService using variables”](#) for an example.

Example 8.5. InitParams - value-param

```
<component>
  <key>org.exoplatform.services.transaction.TransactionService</key>
  <type>org.exoplatform.services.transaction.impl.jotm.TransactionServiceJotmImpl</type>
  <init-params>
    <value-param>
      <name>timeout</name>
      <value>5</value>
    </value-param>
  </init-params>
</component>
```

For <value-param>, the value specification is in the form of <value> element, which defines one `String` instance.

Example 8.6. InitParams - values-param

```
<component>
  <key>org.exoplatform.services.resources.ResourceBundleService</key>
  <type>org.exoplatform.services.resources.impl.SimpleResourceBundleService</type>
  <init-params>
    <values-param>
      <name>classpath.resources</name>
      <description>The resources that start with the following package name should be load from
file system</description>
      <value>locale.portlet</value>
    </values-param>

    <values-param>
      <name>init.resources</name>
      <description>Store the following resources into the db for the first launch </description>
      <value>locale.test.resources.test</value>
    </values-param>

    <values-param>
      <name>portal.resource.names</name>
```

```
<description>The properties files of the portal , those file will be merged
into one ResourceBundle properties </description>
<value>local.portal.portal</value>
<value>local.portal.custom</value>
</values-param>
</init-params>
</component>
```

For `<values-param>`, the value specification is in the form of one or more `<value>` elements, each of which represents one `String` instance, where all the `String` values are then collected into a `java.util.List` instance.

Example 8.7. InitParams - object-param

```
<component>
  <key>org.exoplatform.services.cache.CacheService</key>
  <jmx-name>cache:type=CacheService</jmx-name>
  <type>org.exoplatform.services.cache.impl.CacheServiceImpl</type>
  <init-params>
    <object-param>
      <name>cache.config.default</name>
      <description>The default cache configuration</description>
      <object type="org.exoplatform.services.cache.ExoCacheConfig">
        <field name="name">
          <string>default</string>
        </field>
        <field name="maxSize">
          <int>300</int>
        </field>
        <field name="liveTime">
          <long>300</long>
        </field>
        <field name="distributed">
          <boolean>false</boolean>
        </field>
        <field name="implementation">
          <string>org.exoplatform.services.cache.concurrent.ConcurrentFIFOExoCache</string>
        </field>
      </object>
    </object-param>
  </init-params>
</component>
```

```
</component>
```

For `<object-param>`, the value specification comes in a form of the `<object>` element, which is used for the POJO style object specification (you specify an implementation class - `<type>`, and property values - `<field>`).

Also see [Example 8.8, “Portal container declaration example”](#) for an example of specifying a field of the `Collection` type.

The `InitParams` structure - the names and types of entries is specific for each service, as it is the code inside service components's class that decides what entry names to look up and what types it expects to find.

8.1.5. Configuring a portal container

A **portal container** is defined by several attributes.

First, there is a **portal container name**, which is always equal to the URL context to which the current portal is bound.

Second, there is a **REST context name**, which is used for REST access to portal application - every portal has exactly one (unique) REST context name.

Then, there is a **realm name** which is the name of security realm used for authentication when users log into the portal.

Finally, there is a list of **Dependencies** - other web applications, whose resources are visible to current portal (via extension mechanism described later), and are searched in the specified order.

Example 8.8. Portal container declaration example

```
<?xml version="1.0" encoding="UTF-8"?>
<configuration
  xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
  xsi:schemaLocation="http://www.exoplaform.org/xml/ns/kernel_1_0.xsd
    http://www.exoplaform.org/xml/ns/kernel_1_0.xsd"
  xmlns="http://www.exoplaform.org/xml/ns/kernel_1_0.xsd">

  <external-component-plugins>
    <!-- The full qualified name of the PortalContainerConfig -->
    <target-component>org.exoplaform.container.definition.PortalContainerConfig</target-
component>

    <component-plugin>
```

```
<!-- The name of the plugin -->
<name>Add PortalContainer Definitions</name>

<!-- The name of the method to call on the PortalContainerConfig
      in order to register the PortalContainerDefinitions -->
<set-method>registerPlugin</set-method>

<!-- The full qualified name of the PortalContainerDefinitionPlugin -->
<type>org.exoplatform.container.definition.PortalContainerDefinitionPlugin</type>

<init-params>
  <object-param>
    <name>portal</name>
    <object type="org.exoplatform.container.definition.PortalContainerDefinition">
      <!-- The name of the portal container -->
      <field name="name"><string>portal</string></field>

      <!-- The name of the context name of the rest web application -->
      <field name="restContextName"><string>rest</string></field>

      <!-- The name of the realm -->
      <field name="realmName"><string>exo-domain</string></field>

      <!-- All the dependencies of the portal container ordered by loading priority -->
      <field name="dependencies">
        <collection type="java.util.ArrayList">
          <value>
            <string>eXoResources</string>
          </value>
          <value>
            <string>portal</string>
          </value>
          <value>
            <string>dashboard</string>
          </value>
          <value>
            <string>exoadmin</string>
          </value>
          <value>
            <string>eXoGadgets</string>
          </value>
          <value>
            <string>eXoGadgetServer</string>
          </value>
        </collection>
      </field>
    </object>
  </object-param>
</init-params>
```



```

        <value>
            <string>rest</string>
        </value>
        <value>
            <string>web</string>
        </value>
        <value>
            <string>wsrp-producer</string>
        </value>
        <!-- The sample-ext has been added at the end of the dependency list
            in order to have the highest priority -->
        <value>
            <string>sample-ext</string>
        </value>
    </collection>
</field>
</object>
</object-param>
</init-params>
</component-plugin>
</external-component-plugins>
</configuration>

```



Note

Dependencies are part of the extension mechanism.

Every **portal container** is represented by a **PortalContainer instance**, including:

- Associated **ExoContainerContext** containing information about the portal.
- **Unified servlet context** for web-archive-relative resource loading.
- **Unified classloader** for classpath based resource loading.
- Methods for retrieving services.

Unified servlet context, and **unified classloader** are part of the **extension mechanism** (explained in next section), and provide standard APIs (ServletContext, ClassLoader) with the specific resource loading behavior - visibility into the associated web application archives, configured with Dependencies property of PortalContainerDefinition. Resources from other web applications are queried in the order specified by Dependencies. The later entries in the list override the previous ones.

8.1.6. GateIn Extension Mechanism, and Portal Extensions

Extension mechanism is a functionality that makes it possible to override the portal resources in an almost plug-and-play fashion - just drop in a .war archive with the resources, and configure its position on the portal's classpath. This way any customizations of the portal do not have to involve unpacking and repacking the original portal .war archives. Instead, create your own .war archive with changed resources that override the resources in the original archive.

A web archive packaged in a way to be used through the extension mechanism is called **portal extension**.

There are two steps necessary to create a portal extension.

First, declare **PortalConfigOwner** servlet context listener in web.xml of your web application.

Example 8.9. Example of a portal extension called sample-ext:

```
<?xml version="1.0" encoding="ISO-8859-1" ?>
<!DOCTYPE web-app PUBLIC "-//Sun Microsystems, Inc.//DTD Web Application 2.3//EN
    http://java.sun.com/dtd/web-app_2_3.dtd>
<web-app>

    <display-name>sample-ext</display-name>

    <listener>
        <listener-class>org.exoplatform.container.web.PortalContainerConfigOwner</listener-class>
    </listener>

    ...

</web-app>
```

Then, add the servlet context name of this web application to a proper location in the list of Dependencies of the PortalContainerDefinition of all the portal containers that you want to access its resources.

After this step, your web archive will be on the portal's unified classpath, and unified servlet context resource path. The later in the Dependencies list your application is, the higher priority it has when resources are loaded by portal.



Note

See the 'Configuring a portal' section for example of `PortalContainerDefinition`, that has `sample-ext` at the end of its list of Dependencies.

8.1.7. Running Multiple Portals

It is possible to run several independent portal containers - each bound to a different URL context - within the same JVM instance. This kind of setup is very efficient from administration and resource consumption. The most elegant way to **reuse** configuration for different coexisting portals is by way of extension mechanism - by **inheriting** resources and configuration from existing web archives, and just **adding** extra resources to it, and **overriding** those that need to be changed by including modified copies.

In order for a portal application to correctly function when deployed in multiple portals, the application may have to dynamically query the information about the current portal container. The application should not make any assumptions about the name, and other information of the current portal, as there are now multiple different portals in play.

At any point during request processing, or lifecycle event processing, your application can retrieve this information through **`org.exoplatform.container.ExoContainerContext`**. Sometimes your application needs to make sure that the proper **`PortalContainer`** - the source of **`ExoContainerContext`** - is associated with the current call.

If you ship servlets or servlet filters as part of your portal application, and if you need to access the portal specific resources at any time during the processing of the servlet or filter request, you need to make sure the servlet/filter is associated with the current container.

The proper way to do that is to make your servlet extend **`org.exoplatform.container.web.AbstractHttpServlet`** class. This will not only properly initialize the current **`PortalContainer`** for you, but will also set the current thread's context classloader to one that looks for resources in the associated web applications in the order specified by **`Dependencies`** configuration (as explained in Extension mechanism section).

Similarly for filters, make sure your filter class extends **`org.exoplatform.container.web.AbstractFilter`**. Both **`AbstractHttpServlet`**, and **`AbstractFilter`** have the same method **`getContainer()`**, which returns the current **`PortalContainer`**. If your servlet handles the requests by implementing the **`service()`** method, you need to rename that method to match the following signature:

```
/**
 * Use this method instead of Servlet.service()
 */
protected void onService(ExoContainer container, HttpServletRequest req,
```

HttpServletResponse res) throws ServletException, IOException;



Note

The reason is that `AbstractHttpServlet` implements `service()` to perform its interception, and you don't want to overwrite (by overriding) this functionality.

You may also need to access portal information within your **HttpSessionListener**. Again, make sure to extend the provided abstract class - **org.exoplatform.container.web.AbstractHttpSessionListener**. Also, modify your method signatures as follows:

```
/**
 * Use this method instead of HttpSessionListener.sessionCreated()
 */
protected void onSessionCreated(ExoContainer container, HttpSessionEvent event);

/**
 * Use this method instead of HttpSessionListener.sessionDestroyed()
 */
protected void onSessionDestroyed(ExoContainer container, HttpSessionEvent event);
```

There is another method you have to implement in this case:

```
/**
 * Method should return true if unified servlet context,
 * and unified classloader should be made available
 */
protected boolean requirePortalEnvironment();
```

If this method returns true, the current thread's context classloader is set up according to the **Dependencies** configuration, and availability of the associated web applications. If it returns false, the standard application separation rules are used for resource loading (effectively turning off the extension mechanism). This method exists on **AbstractHttpServlet** and **AbstractFilter** as well, where there is a default implementation that automatically returns true, when it detects there is a current PortalContainer present. Otherwise, it returns false.

The followings explain how to properly perform the **ServletContextListener** based initialization, when you need to access the current PortalContainer.

GateIn has no direct control over the deployment of application archives (.war, .ear files) - it is the application server performing the deployment. For the **extension mechanism** to work properly, the applications, associated with the portal via the **Dependencies** configuration, have to be deployed before the portal, that depends on them, is initialized. On the other hand, these applications may require an already initialized PortalContainer to properly initialize themselves - we have a recursive dependency problem. To resolve this problem, a mechanism of **initialization tasks**, and **task queues**, was put in place. Web applications that depend on the current PortalContainer for their initialization have to avoid performing their initialization directly in some ServletContextListener executed during their deployment (before any PortalContainer was initialized). Instead, a web application should package its initialization logic into an init task of the appropriate type, and only use ServletContextListener to insert the init task instance into the proper init tasks queue.

An example of this is the Gadgets application which registers the Google gadgets with the current PortalContainer:

```
public class GadgetRegister implements ServletContextListener
{
    public void contextInitialized(ServletContextEvent event)
    {
        // Create a new post-init task
        final PortalContainerPostInitTask task = new PortalContainerPostInitTask() {

            public void execute(ServletContext context, PortalContainer portalContainer)
            {
                try
                {
                    SourceStorage sourceStorage =
                        (SourceStorage) portalContainer.getComponentInstanceOfType(SourceStorage.class);
                    ...
                }
                catch (RuntimeException e)
                {
                    throw e;
                }
                catch (Exception e)
                {
                    throw new RuntimeException("Initialization failed: ", e);
                }
            }
        };
    }
};
```

```
// Add post-init task for execution on all the portal containers
// that depend on the given ServletContext according to
// PortalContainerDefinitions (via Dependencies configuration)
PortalContainer.addInitTask(event.getServletContext(), task);
}
}
```

The above example uses **PortalContainerPostInitTask**, which gets executed after the portal container has been initialized. In some cases, you may want to execute the initialization after portal container was instantiated, but before it was initialized - use **PortalContainerPreInitTask** in that case. Or, you may want to execute initialization after all the post-init tasks have been executed - use **PortalContainerPostCreateTask** in that case.

Also, you may need to pay attention to **LoginModules**. If you use custom LoginModules which require the current ExoContainer, make sure they extend **org.exoplatform.services.security.jaas.AbstractLoginModule** for the proper initialization. AbstractLoginModule also takes care of the basic configuration - it recognizes two initialization options - **portalContainerName**, and **realmName** whose values you can access via protected fields of the same name.